

DECEMBER 11, 2019

JON/ROSETTE CENIZAL

#51 DACCA EXTN. BF HOMES PARANAQUE

0917-8342438/ 0917-8043184/ 0977-2607088

MODEL
KLG-SF40-3D1M

QUANTITY
1

REV2,CUSTOMER CHOICE

LIVING/DINING/KITCHEN

Area ≈ 60 sq.m

ACU 4.0hp Floor mounted Regular KLG-SF40-3D1M
Estimated Pipe Length 60 ft
Estimated Royal Cord Length 125 ft
Initial Charge P 9,500.00
Includes:
Labor
10ft Copper Tube
10ft Royal Cord
Circuit Breaker (40A-1ph)
Indoor Bracket
Other Consumables

Additional Charges	Description	Unit	Price Per Unit	Subtotal
Copper Tube	1/4" x 5/8"	50 ft P	250 / ft	P 12,500
Royal Cord	2.mm2 x 4C	115 ft P	35 / ft	P 4,025
Royal Cord (ODU-Breaker)	5.5mm2 x 3C	7 ft P	50 / ft	P 350
PVC Pipe	Blue- 3/4"	1 pc(s) P	150 / pc	P 150
Scaffolding (3sets)	w/platform	P	1,500 / deliver	P 1,500
Outdoor Bracket (fabricated)	wall	1 pc(s) P	5,000 / pc	P 5,000
Drain Hose	White -1/2"	7 ft P	25 / ft	P 175 P 23,700.00

Estimated Charges	P 33,200.00
-------------------	-------------

Total Estimated Charges	P 33,200.00
-------------------------	-------------

Validity: This quotation is valid for a period of fifteen (15) days from the date thereof, subject to our confirmation thereafter.

Note:

- 1 Location of indoor and outdoor units were agreed by the customer and Kolin's surveyor.
- 2 **Customer will restore all the damage were the coppertube is lay out.**
- 3 Need **waiver** due to undercapacity.
- 4 AC drain line will be tapped to the nearest drain provision provided by the customer's contractor.
- 5 Working Schedule: Monday to Saturday, 8am- 5pm. Need permit and gatepass. With parking.
- 6 Mechanical Plans, Permits, Electrical permits not included.
- 7 Deflectors, masonry, carpentry, chipping & plastering (finishing & restoration) are not included in the installation.
- 8 Electrical power supply (feeder line) is not included in the scope of work of Kolin.
- 9 **Final charges will be based on actual installation.**

Prepared by:

Jeoffrey Dadios
Field Surveyor

Reviewed by:

Engr. Noel Christopher Cortez
Project Survey Head

Customer Conforme:

Signature Over Printed Name