

TO : KOLIN AUTHORIZED SERVICE CENTERS
FROM : KOLIN HEAD OFFICE
SUBJECT : INSTALLATION PRICING, INCLUSIONS AND EXCLUSIONS
DATE : AUGUST 16, 2022
REF. NO. : SVC-000-2022-08-042
CC : DCO / BOO / SERVICE / SVC ACCTG / OP / KMI / SALES

Greetings to all!

Due to continuing price hike of materials due on fuel prices and wage order across the country, we would like to announce that we will be having an adjustment to installation inclusions and exclusions.

This is to maintain a competitive pricing and quality of installation to our customers despite the challenges that we facing today.

Effective September 01, 2022

- | | |
|--|-----------|
| 1. Window type (mounting + gap sealant) | P1,200.00 |
| 2. Wall Mounted Split Type (Non-inverter & Inverter) | |
| 1.0HP – 2.0HP (deduct existing promo, if any) | P7,500.00 |
| 2.5HP – 3.0HP (deduct existing promo, if any) | P8,500.00 |


Free 10 ft. Copper tube (minimum thickness: 0.028")

Inclusions:

Labor
10 ft. Royal cord 2.0mm² x 4C (**communication wire**)
Rubber Insulation (insulation materials)
Standard outdoor unit metal bracket
10 ft. Drain hose / PVC drain pipe ¾"
Consumable materials like aerotape, electrical tape, polyethylene tape, PVC elbow, PVC clamp, metal screw, log screw, etc.
Flushing, vacuum and leak test of AC system
Testing and commissioning

Exclusions: (to be paid by the customer)

Copper tube in excess of 1st 10 ft.	
1.0hp – 2.0hp	P350.00 / ft.
2.5hp – 3.0hp	P400.00 / ft.
Royal cord in excess of 1st 10 ft.	P100.00 / ft.
Circuit breaker-1 phase Nema 3R (weatherproof)	P1,000.00
Specially designed brackets / catwalk type	
Power supply and electrical wire from main panel to ACCU breaker	



Dismantling of existing unit
Scaffold, masonry, chipping and restoration works

Installation rebate (inclusive of 10ft. copper tube subsidy)

- 1.0hp – 2.0hp **P3,000.00 / unit**
- 2.5hp – 3.0hp **P3,500.00 / unit**

3. Package Type and Multi-Split Type Aircon (Non-inverter & Inverter)

Flex Match Inverter (1 st pair)	P 8,500.00
• Succeeding indoor unit	P 3,000.00 / unit
3.0TR Floor Mounted	P11,000.00
5.0TR Floor Mounted	P14,000.00
3.0TR Ceiling Suspended / Cassette	P12,000.00
5.0TR Ceiling Suspended / Cassette	P15,000.00

Inclusions:

Labor
10 ft. Copper tube (minimum thickness: 0.028")
10 ft. Royal cord 2.0mm² x 4C (**communication wire**)
Rubber insulation (insulation materials)
Indoor unit bracket
10 ft. Drain hose / PVC drain pipe
Consumable materials like aertape, electrical tape, polyethylene tape, PVC elbow, PVC clamp, metal screw, log screw, etc.
Flushing, vacuum and leak test of AC system
Testing and commissioning

Exclusions: (to be paid by the customer)

Copper tube in excess of 1st 10 ft.
3.0 TR P400.00 / ft.
5.0 TR P600.00 / ft.
Royal cord in excess of 1st 10 ft. **P100.00 / ft.**
Circuit breaker Nema 3R (weatherproof)
Outdoor unit metal bracket
Power supply and electrical wire from main panel to ACCU breaker
Dismantling of existing unit
Scaffold, masonry, chipping and restoration works

Note: Communication wire shall use royal cord only. Do not use THHN wire.

For strict compliance

Prepared by:

Mr. Alvin C. De Rivera
Service Assistant Manager

Approved by:

Mr. Oliver M. Filoteo
Executive Vice President / COO