

July 15, 2024
JIMMY MIRANDA
Tiaong Quezon Province

| MODEL | Qty |
|---------------------|-----|
| KSG-IWF-30Wfy8K1M32 | 1 |
| KSG-IWF-25Wfy8K1M32 | 1 |
| KSG-IWF-20Wfy8K1M32 | 2 |
| KSG-IWF-10Wfy8K1M32 | 3 |

| | | |
|---------------------|------|--------|
| PARENTS ROOM | Area | 11 sqm |
|---------------------|------|--------|

| | | | | | |
|--------------|-------------------------------------|----------------------------|------------|----------------------|-------------------|
| ACU 1 | 1.0 HP Wall Mounted Inverter | KSG-IWF-10Wfy8K1M32 | | | |
| | Estimated Pipe Length = 14 ft | | | | |
| | Estimated Royal Cord Length = 19 ft | | | | |
| | Initial Charge | | | | ₱ 4,500.00 |
| | Includes: | | | | |
| | Labor | | | | |
| | 10ft Copper Tube | | | | |
| | 10ft Royal Cord | | | | |
| | Outdoor Bracket (Wall) | | | | |
| | Consumables | | | | |
| | Installation Materials | Description | Qty | Price per qty | Subtotal |
| | Copper Tube | Ø 1/4" x Ø 3/8" | 4 ft | ₱ 350.00/ft | ₱ 1,400.00 |
| | Royal Cord (comm. wire) | 2.mm2 x 4C | 9 ft | ₱ 100.00/ft | ₱ 900.00 |
| | Royal Cord (ACCU-Breaker) | 3.5mm x 3c | 5 ft | ₱ 60.00/ft | ₱ 300.00 |
| | Circuit Breaker waterproof | 20A / 1Ph | 1 pc/s | ₱ 1,000.00/pc | ₱ 1,000.00 |
| | PVC blue | 3/4" x 10' | 1 pc/s | ₱ 150.00/pc | ₱ 150.00 |
| | | | | | <u>₱ 3,750.00</u> |

| | |
|--------------------------|------------|
| Estimated Charges | ₱ 8,250.00 |
|--------------------------|------------|

| | | |
|---------------|------|--------|
| LIVING | Area | 28 sqm |
|---------------|------|--------|

| | | | | | |
|--------------|-------------------------------------|----------------------------|------------|----------------------|-------------------|
| ACU 2 | 3.0 HP Wall Mounted Inverter | KSG-IWF-30Wfy8K1M32 | | | |
| | Estimated Pipe Length = 10 ft | | | | |
| | Estimated Royal Cord Length = 15 ft | | | | |
| | Initial Charge | | | | ₱ 5,500.00 |
| | Includes: | | | | |
| | Labor | | | | |
| | 10ft Copper Tube | | | | |
| | 10ft Royal Cord | | | | |
| | Outdoor Bracket (Wall) | | | | |
| | Consumables | | | | |
| | Installation Materials | Description | Qty | Price per qty | Subtotal |
| | Royal Cord (comm. wire) | 2.mm2 x 4C | 5 ft | ₱ 100.00/ft | ₱ 500.00 |
| | Royal Cord (ACCU-Breaker) | 3.5mm x 3c | 5 ft | ₱ 60.00/ft | ₱ 300.00 |
| | Circuit Breaker waterproof | 30A / 1Ph | 1 pc/s | ₱ 1,000.00/pc | ₱ 1,000.00 |
| | PVC blue | 3/4" x 10' | 1 pc/s | ₱ 150.00/pc | ₱ 150.00 |
| | | | | | <u>₱ 1,950.00</u> |

| | |
|--------------------------|------------|
| Estimated Charges | ₱ 7,450.00 |
|--------------------------|------------|

| | | |
|-----------------------|------|--------|
| DINING/KITCHEN | Area | 20 sqm |
|-----------------------|------|--------|

| | | | | | |
|--------------|-------------------------------------|----------------------------|------------|----------------------|-------------------|
| ACU 3 | 2.5 HP Wall Mounted Inverter | KSG-IWF-25Wfy8K1M32 | | | |
| | Estimated Pipe Length = 17 ft | | | | |
| | Estimated Royal Cord Length = 22 ft | | | | |
| | Initial Charge | | | | ₱ 5,500.00 |
| | Includes: | | | | |
| | Labor | | | | |
| | 10ft Copper Tube | | | | |
| | 10ft Royal Cord | | | | |
| | Outdoor Bracket (Wall) | | | | |
| | Consumables | | | | |
| | Installation Materials | Description | Qty | Price per qty | Subtotal |
| | Copper Tube | Ø 1/4" x Ø 5/8" | 7 ft | ₱ 400.00/ft | ₱ 2,800.00 |
| | Royal Cord (comm. wire) | 2.mm2 x 4C | 12 ft | ₱ 100.00/ft | ₱ 1,200.00 |
| | Royal Cord (ACCU-Breaker) | 3.5mm x 3c | 5 ft | ₱ 60.00/ft | ₱ 300.00 |
| | Circuit Breaker waterproof | 30A / 1Ph | 1 pc/s | ₱ 1,000.00/pc | ₱ 1,000.00 |
| | PVC blue | 3/4" x 10' | 1 pc/s | ₱ 150.00/pc | ₱ 150.00 |
| | | | | | <u>₱ 5,450.00</u> |

| | |
|--------------------------|-------------|
| Estimated Charges | ₱ 10,950.00 |
|--------------------------|-------------|

| | | |
|-----------------------|------|--------|
| MASTER BEDROOM | Area | 21 sqm |
|-----------------------|------|--------|

ACU 6 2.0 HP Wall Mounted Inverter KSG-IWF-20Wfy8K1M32

Estimated Pipe Length = 10 ft

Estimated Royal Cord Length = 17 ft

Initial Charge

₱ 4,500.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Outdoor Bracket (Wall)

Consumables

Installation Materials

| Description | Qty | Price per qty | Subtotal |
|----------------------------|------------|----------------------|-------------------|
| Royal Cord (comm. wire) | 2.mm2 x 4C | 7 ft ₱ 100.00/ft | ₱ 700.00 |
| Royal Cord (ACCU-Breaker) | 3.5mm x 3c | 7 ft ₱ 60.00/ft | ₱ 420.00 |
| Circuit Breaker waterproof | 20A / 1Ph | 1 pc/s ₱ 1,000.00/pc | ₱ 1,000.00 |
| PVC blue | 3/4" x 10' | 1 pc/s ₱ 150.00/pc | ₱ 150.00 |
| | | | <u>₱ 2,270.00</u> |

Estimated Charges

₱ 6,770.00

Total Estimated Charges

₱ 68,540.00

Validity: This quotation is valid for a period of fifteen (15) days from the date thereof, subject to our confirmation thereafter.

Installation notes:

- 1 Proposed capacity and location of air conditioning units are based on floor plan submitted by customer.
- 2 AC drain line will be tapped to the nearest drain provision provided by the customer's contractor.
- 3 Need for marking and site visit before installation.
- 4 Mechanical Plans, Permits, Electrical permits not included.
- 5 Deflectors, masonry, carpentry, chipping & plastering (finishing & restoration) are not included in the installation.
- 6 Air conditioning drain line and Electrical power supply (feeder line) **220v/ 60hz/ 1ph** should be provided by customer's contractor.
- 7 **Final charges will be based on actual installation.**

Prepared by:

Jeffrey Dadios

Field Surveyor

Customer Conformance:

Signature Over Printed Name

Reviewed by:

Engr. Kenneth Zamora

Service Supervisor Shop and
Field Operation