

July 8, 2024

ATTY . PETER SUCHIANGCO

119 Aquarius St, Cinco Hermanos, Marikina City

0966-624999/ 0922-814271

Email address

MODEL	Qty
KLG-IF40-5G1M32	2
KSG-IWF-30Wfy8K1M32	3
KSG-IWF-25Wfy8K1M32	3
KSG-IWF-15Wfy8K1M32	2
KAG-250WCINV	1

DINING ROOM	Area	27 sqm
--------------------	------	--------

ACU 1 3.0 HP Wall Mounted Inverter *KSG-IWF-30Wfy8K1M32*

Estimated Pipe Length = 60 ft

Estimated Royal Cord Length = 65 ft

Initial Charge ₱ 5,500.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Outdoor Bracket (Wall)

Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 5/8"	50 ft	₱ 400.00/ft	₱ 20,000.00
Royal Cord (comm. wire)	2.mm2 x 4C	55 ft	₱ 100.00/ft	₱ 5,500.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	₱ 60.00/ft	₱ 300.00
Circuit Breaker waterproof	30A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	5 pc/s	₱ 350.00/pc	₱ 1,750.00
Outdoor bracket	Fab. wall w/ledge	1 pc/s	₱ 6,500.00/pc	₱ 6,500.00
PVC blue	3/4" x 10'	1 pc/s	₱ 150.00/pc	₱ 150.00
				<u>₱ 35,200.00</u>

Estimated Charges	₱ 40,700.00
--------------------------	-------------

KITCHEN	Area	20 sqm
----------------	------	--------

ACU 2 2.5 HP Wall Mounted Inverter *KSG-IWF-25Wfy8K1M32*

Estimated Pipe Length = 40 ft

Estimated Royal Cord Length = 45 ft

Initial Charge ₱ 5,500.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 5/8"	30 ft	₱ 400.00/ft	₱ 12,000.00
Royal Cord (comm. wire)	2.mm2 x 4C	35 ft	₱ 100.00/ft	₱ 3,500.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	₱ 60.00/ft	₱ 300.00
Circuit Breaker waterproof	30A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	4 pc/s	₱ 350.00/pc	₱ 1,400.00
Outdoor bracket	Fab. wall w/ledge	1 pc/s	₱ 6,500.00/pc	₱ 6,500.00
PVC blue	3/4" x 10'	1 pc/s	₱ 150.00/pc	₱ 150.00
				<u>₱ 25,025.00</u>

Estimated Charges	₱ 30,525.00
--------------------------	-------------

HALLWAY	Area	29 sqm
----------------	------	--------

ACU 3 3.0 HP Wall Mounted Inverter **KSG-IWF-30Wfy8K1M32**

Estimated Pipe Length = 46 ft

Estimated Royal Cord Length = 51 ft

Initial Charge ₱ 5,500.00

Includes:

Labor
10ft Copper Tube
10ft Royal Cord
Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 5/8"	36 ft	₱ 350.00/ft	₱ 12,600.00
Royal Cord (comm. wire)	2.mm2 x 4C	41 ft	₱ 100.00/ft	₱ 4,100.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	₱ 60.00/ft	₱ 300.00
Circuit Breaker waterproof	30A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	6 pc/s	₱ 350.00/pc	₱ 2,100.00
Outdoor bracket	Fab. wall w/ledge	1 pc/s	₱ 6,500.00/pc	₱ 6,500.00
Dismantle	2.5HP Wall Mounted	1 set	₱ 2,500.00/set	₱ 2,500.00
PVC blue	3/4" x 10'	1 pc/s	₱ 150.00/pc	₱ 150.00
				₱ 29,250.00

Estimated Charges		₱ 34,750.00
--------------------------	--	-------------

MASTER BEDROOM	Area	24 sqm
-----------------------	------	--------

ACU 4 2.5 HP Wall Mounted Inverter **KSG-IWF-25Wfy8K1M32**

Estimated Pipe Length = 40 ft

Estimated Royal Cord Length = 45 ft

Initial Charge ₱ 5,500.00

Includes:

Labor
10ft Copper Tube
10ft Royal Cord
Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 5/8"	30 ft	₱ 350.00/ft	₱ 10,500.00
Royal Cord (comm. wire)	2.mm2 x 4C	35 ft	₱ 100.00/ft	₱ 3,500.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	₱ 60.00/ft	₱ 300.00
Circuit Breaker waterproof	30A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	4 pc/s	₱ 350.00/pc	₱ 1,400.00
Outdoor bracket	Fabricated floor	pc/s	₱ 2,500.00/pc	₱ 0.00
PVC blue	3/4" x 10'	1 pc/s	₱ 150.00/pc	₱ 150.00
				₱ 16,850.00

Estimated Charges		₱ 22,350.00
--------------------------	--	-------------

FAMILY ROOM	Area	25 sqm
--------------------	------	--------

ACU 5 3.0 HP Wall Mounted Inverter **KSG-IWF-30Wfy8K1M32**

Estimated Pipe Length = 23 ft

Estimated Royal Cord Length = 28 ft

Initial Charge ₱ 5,500.00

Includes:

Labor
10ft Copper Tube
10ft Royal Cord
Outdoor Bracket (Wall)
Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 5/8"	13 ft	₱ 350.00/ft	₱ 4,550.00
Royal Cord (comm. wire)	2.mm2 x 4C	18 ft	₱ 100.00/ft	₱ 1,800.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	₱ 60.00/ft	₱ 300.00
Circuit Breaker waterproof	30A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
PVC blue	3/4" x 10'	2 pc/s	₱ 150.00/pc	₱ 300.00
				₱ 7,950.00

Estimated Charges		₱ 13,450.00
--------------------------	--	-------------

WALK IN CLOSET	Area	10 sqm
-----------------------	------	--------

ACU 6 1.5 HP Wall Mounted Inverter **KSG-IWF-15WFY8K1M32**

Estimated Pipe Length = 33 ft

Estimated Royal Cord Length = 38 ft

Initial Charge ₱ 4,500.00

Includes:

- Labor
- 10ft Copper Tube
- 10ft Royal Cord
- Outdoor Bracket (Wall)
- Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 3/8"	23 ft	₱ 350.00/ft	₱ 8,050.00
Royal Cord (comm. wire)	2.mm2 x 4C	28 ft	₱ 100.00/ft	₱ 2,800.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	₱ 60.00/ft	₱ 300.00
Circuit Breaker waterproof	30A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	4 pc/s	₱ 350.00/pc	₱ 1,400.00
PVC blue	3/4" x 10'	2 pc/s	₱ 150.00/pc	₱ 300.00
				₱ 13,850.00

Estimated Charges		₱ 18,350.00
--------------------------	--	-------------

T & B	Area	10 sqm
------------------	------	--------

ACU 7 1.5 HP Wall Mounted Inverter **KSG-IWF-15WFY8K1M32**

Estimated Pipe Length = 15 ft

Estimated Royal Cord Length = 20 ft

Initial Charge ₱ 4,500.00

Includes:

- Labor
- 10ft Copper Tube
- 10ft Royal Cord
- Outdoor Bracket (Wall)
- Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 3/8"	5 ft	₱ 350.00/ft	₱ 1,750.00
Royal Cord (comm. wire)	2.mm2 x 4C	10 ft	₱ 100.00/ft	₱ 1,000.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	₱ 60.00/ft	₱ 300.00
Circuit Breaker waterproof	30A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	6 pc/s	₱ 350.00/pc	₱ 2,100.00
PVC blue	3/4" x 10'	2 pc/s	₱ 150.00/pc	₱ 300.00
				₱ 6,450.00

Estimated Charges		₱ 10,950.00
--------------------------	--	-------------

BEDROOM 1	Area	23 sqm
------------------	------	--------

ACU 8 2.5 HP Wall Mounted Inverter **KSG-IWF-25WFY8K1M32**

Estimated Pipe Length = 33 ft

Estimated Royal Cord Length = 38 ft

Initial Charge ₱ 5,500.00

Includes:

- Labor
- 10ft Copper Tube
- 10ft Royal Cord
- Outdoor Bracket (Wall)
- Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 5/8"	23 ft	₱ 350.00/ft	₱ 8,050.00
Royal Cord (comm. wire)	2.mm2 x 4C	28 ft	₱ 100.00/ft	₱ 2,800.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	7 ft	₱ 60.00/ft	₱ 420.00
Circuit Breaker waterproof	30A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
PVC blue	3/4" x 10'	1 pc/s	₱ 150.00/pc	₱ 150.00
				₱ 12,420.00

Estimated Charges		₱ 17,920.00
--------------------------	--	-------------

DANCE STUDIO	Area	25 sqm
---------------------	------	--------

ACU 9 2.5 HP Window type Inverter **KAG-250WCINV**

Initial Charge P 1,200.00

Includes:

Labor

Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Window type bracket		1 pc/s	P 600.00/pc	P 600.00
Drain Hose	White -1/2"	7 ft	P 25.00/ft	P 175.00
				P 775.00

Estimated Charges	P 1,975.00
--------------------------	-------------------

ENTERTAINMENT ROOM	Area	63 sqm
---------------------------	------	--------

ACU 10 4.0 HP Floor Standing Inverter **KLG-IF40-5G1M32**

Estimated Pipe Length = 40 ft

Estimated Royal Cord Length = 47 ft

Initial Charge P 11,000.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Indoor Bracket (Floor)

Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 3/8" x Ø 5/8"	30 ft	P 400.00/ft	P 12,000.00
Royal Cord (comm. wire)	2.mm2 x 4C	37 ft	P 100.00/ft	P 3,700.00
Royal Cord (ACCU-Breaker)	5.5mm x 3c	7 ft	P 70.00/ft	P 490.00
Circuit Breaker waterproof	30A / 1Ph	1 pc/s	P 1,000.00/pc	P 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	6 pc/s	P 350.00/pc	P 2,100.00
Outdoor bracket	Fab. wall w/ledge	1 pc/s	P 6,500.00/pc	P 6,500.00
PVC blue	3/4" x 10'	3 pc/s	P 150.00/pc	P 450.00
				P 26,240.00

Estimated Charges	P 37,240.00
--------------------------	--------------------

ACU 11 4.0 HP Floor Standing Inverter **KLG-IF40-5G1M32**

Estimated Pipe Length = 46 ft

Estimated Royal Cord Length = 53 ft

Initial Charge P 11,000.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Indoor Bracket (Floor)

Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 3/8" x Ø 5/8"	36 ft	P 350.00/ft	P 12,600.00
Royal Cord (comm. wire)	2.mm2 x 4C	43 ft	P 100.00/ft	P 4,300.00
Royal Cord (ACCU-Breaker)	5.5mm x 3c	7 ft	P 70.00/ft	P 490.00
Circuit Breaker waterproof	30A / 1Ph	1 pc/s	P 1,000.00/pc	P 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	6 pc/s	P 350.00/pc	P 2,100.00
Outdoor bracket	Fab. wall w/ledge	1 pc/s	P 6,500.00/pc	P 6,500.00
scaffoldings	4sets	1 mtr	P 1,500.00/mtr	P 1,500.00
PVC blue	3/4" x 10'	3 pc/s	P 150.00/pc	P 450.00
				P 28,940.00

Estimated Charges	P 39,940.00
--------------------------	--------------------

Total Estimated Charges

P 268,150.00

Validity: This quotation is valid for a period of fifteen (15) days from the date thereof, subject to our confirmation thereafter.

Installation notes:

- 1 Location based in floor plan only. Not yet final. For confirmation of location. indoor and outdoor.
- 2 AC drain line will be tapped to the nearest drain provision provided by the customer's contractor.
- 3 Need for marking and site visit before installation.
- 4 Copper tube expose in the area.
- 5 BEDROOM1 and ATTIC Outdoor location not yet final, need for confirmation.**
- 6 Working days: Monday to Saturday, 8am- 5pm with parking. Need working permit.
- 7 Mechanical Plans, Permits, Electrical permits not included.
- 8 Deflectors, masonry, carpentry, chipping & plastering (finishing & restoration) are not included in the installation.
- 9 Air conditioning drain line and Electrical power supply (feeder line) **220v/ 60hz/ 1ph**, should be provided by customer's contractor.
- 10 **Final charges will be based on actual installation.**


Prepared by:


Jeffrey Dadios
Field Surveyor

Customer Conformer:

Signature Over Printed Name

Reviewed by:


Engr. Kenneth Zamora
Service Supervisor Shop and
Field Operation