



N.V.F.S MAINTENANCE AIRCON & REFRIGERATION SYSTEM TRADING
MANILA: Office Unit Q Monserrat St B.F. Homes Phase 1 Sucat Rd Paranaque
+639171163534 | +639455920222 | +632 85146379
E-mail: sales@about-nvfs-ph.com | inquiry@about-nvfs-ph.com
www.nvfs-ph.com
TIN Number: 305-342-355-00000

QOUTATION

TO : Allan Dimapilis

ADDRESS: 82 L9B Dominique St., St. Joseph Subd., Brgy. Pulang Lupa Dos, LAS PIÑAS CITY, Metro Manila

REFERENCE NO:

DATE : August 29, 2024

CUSTOMER NO :

Repair Code	BRAND AND ITEM DESCRIPTION	QTY	UNIT	UNIT PRICE	GROSS AMOUNT	DISCOUNT	NET PRICE
*	Masters Bedroom						
*	1HP Wall Mounted - KOLIN - KSM-IW10-WCT10M1M32 - Basic Inverter	1	Set		P0.00		P0.00
*	1HP Wall Mounted - KOLIN - KSG-IWF-10WFY8K1M32 - Full DC Inverter	1	Set		P0.00		P0.00
11.1	Installation 1.0 - 2.0 hp - (Inclusive of 10FT Copper Tube , 4C Communication Wire , Ordinary Bracket, Drain Hose)	1	Set	P7,500.00	P7,500.00		P7,500.00

Mode of Payments

	Cash, Gcash, maya
	Bank Transfer or Check Payment under: NVFS Maintenance Aircon & Refrigeration System Trading
	BDO Account 004128020472 President's Avenue BF Paranaque Branch
	Metrobank Account 034-7-03452574-5 BF Homes Aguirre Branch

SCOPE OF WORKS:

- Supply , Delivery and First 10ft. Copper Tube / Communication Wirings and 10ft. drain pipe
- Rubber installation tubes for ceiling 3/4 size for outdoor exposure walls, electrical materials including Royal Cord 2.0mm2 x 4C Communication wire ,PVC drain line including fittings
- Provide Installation materials such as, copper pipes, soft drawn seamless copper pipe.
- Brazing of copper tubing & covering of polyethylene tape.
- Supply of installation tools, welding equipment, manpower and supervision.
- System dehydration and vacuuming. Testing commissioning and turnover.
- Insulated Drain Line 3/4 Size inclusive of Elbows and T extensions

TERMS & CONDITIONS

- Unit Price and Installation are VAT Inclusive.
- Full Payment within 15 days after commissioning and submission of billing statement with service report completion.
- Price are subject to change after sales offer validity which seven (7) days from the date of issue.

WARRANTY

Note : for KOLIN Models :

- * for Residential ACU : with **10** years warranty on compressor and **3** years warranty on PCB **1** year on evaporator coil and condenser coil
- * for Light Commercial ACU : with **5** years warranty on compressor and **1** year warranty on PCB / evaporator coil and condenser coil

2. Warranty may be restricted or disallowed based on the discretion of N.V.F.S.

EXCLUSIONS:

- Excess copper tube & Communication Wiring 4C with separate charges: P450/ft. for Split Type 1.0hp-2.0hp; P500/ft. for Split Type 2.5hp-3.0hp for Floor Mounted and Ceiling Mounted
- Electrical cabling for air condition power supply / Electrical Supply from Main Panel to ACCU breaker / Dismantling of existing unit / Restoration Works
- Provision and installation of NEMA 3R Circuit breaker 20 AMP / 30 AMP P1000
- Electrical cabling for air condition power supply / Indoor to Outdoor Service breaker Size # 14 THHN Wire P60/Mtr, Size # 12 THHN Wire P80/Mtr, Size # 10 THHN Wire P90/Mtr

Ryan L. Guerra

NVFS Maintenance Aircon and Refriegration System Trading

Date :

Conforme:

Client's Signature over Printed Name / Date

AUTHORIZED DEALER OF THE FOLLOWING BRANDS



AUTHORIZED SERVICE CENTER OF THE FOLLOWING BRANDS

