

Greetings!

We are pleased to send below quotation for your perusal. Should you have further clarifications, kindly let us know. Thank you for doing business with us.

Date : **May 29, 2025**  
To : **METROPOLITAN MEDICAL CENTER**  
Attn : **PROCUREMENT**  
Subject : **Proposal for the Installation of Two (2) Wall Mounted Air-condition Units**  
Address : **1357 G. Masangkay St, Brgy Tondo Manila**

#### I. SCOPE OF WORK

- a. Hauling and fabrication of support bracket
- b. Installation of indoor & outdoor unit
- c. Installation of refrigerant piping with communication wires
- d. Installation of drain line
- e. System pressure test and leak testing using Nitrogen gas
- f. Air evacuation
- g. Tapping of power supply to ACU ECB
- h. Testing and commissioning

#### II. QUOTATION

BLOOD BANK ACU #1 - 2.5HP WALL MOUNTED (OUTDOOR POWER SUPPLY 1PHASE REQUIRED)				
QTY	UNIT	DESCRIPTION	PRICE PER UNIT	TOTAL
1	LOT	Basic installation cost for the 1st 10ft	7,700.00	7,700.00
14	FT	Excess copper tube w/ rubber insulation 1/4" x 1/2"	400.00	5,600.00
19	FT	Royal cord (communication) 2.mm2 x 4C	100.00	1,900.00
7	FT	Royal cord (ODU Breaker) wire 2.mm2 x 4C	60.00	420.00
1	PC	Weather proof nema 3R w/ breaker for ACCU - 30A/1Ph	1,000.00	1,000.00
1	LOT	PVC Drain line w/ elbow from FCU to roof drain	1,800.00	1,800.00
1	PC	Special fabrication of metal bracket for ACCU floor type	2,500.00	2,500.00
Sub total :				<b>₱ 20,920.00</b>

BLOOD BANK ACU #2 - 2.5HP WALL MOUNTED (OUTDOOR POWER SUPPLY 1PHASE REQUIRED)				
QTY	UNIT	DESCRIPTION	PRICE PER UNIT	TOTAL
1	LOT	Basic installation cost for the 1st 10ft	7,700.00	7,700.00
11	FT	Excess copper tube w/ rubber insulation 1/4" x 1/2"	400.00	4,400.00
16	FT	Royal cord (communication) 2.mm2 x 4C	100.00	1,600.00
7	FT	Royal cord (ODU Breaker) wire 2.mm2 x 4C	60.00	420.00
1	PC	Weather proof nema 3R w/ breaker for ACCU - 30A/1Ph	1,000.00	1,000.00
1	LOT	PVC Drain line w/ elbow from FCU to roof drain	1,800.00	1,800.00
1	PC	Special fabrication of metal bracket for ACCU floor type	2,500.00	2,500.00
Sub total :				<b>₱ 19,420.00</b>

<b>Total cost :</b>	<b>40,340.00</b>
<b>Less 10% discount</b>	<b>4,034.00</b>
<b>Net of Discount</b>	<b>₱ 36,306.00</b>
<b>Add: 12% VAT</b>	<b>4,356.72</b>
<b>TOTAL COST VAT INCLUSIVE</b>	<b>₱ 40,662.72</b>

**"We Bring the Cool back"**

**Inclusions: For Basic Installation**

- a. Bracket and support
- b. 1st 10FT Copper Tube (**SOFT DRAWN**) w/ rubber insulation
- c. 3 meters communication wire
- d. Labor w/ equipments

**Exclusions: For the 1st 10ft Basic Installation & Other Materials**

- a. Panel Board Breaker, ACCU ECB, Coving of Ceiling , Wall Cladding, Chipping Works, Masonry Works
- b. Painting, Plastering and Restoration
- c. Mechanical Plans and permits
- d. Water proofing of flooring and roofing
- e. Supply and installation of Feeder Line to ACCU

**Warranty:**

- a. 5 years Compressor ; 1 year parts and workmanship within scope.
- b. Client is required to submit a copy of Sales Invoice or Proof of Purchase with Serial number for both indoor and outdoor unit for Manufacturer's Warranty purposes.
- c. All maintenance and services must be endorsed to AGD Aircon & Refrigeration services while on the warranty period.

**Terms of Payment:**

Full Payment Upon Completion

All payments should be payable to **AGD AIRCON & REFRIGERATION SERVICES**

Thank you,



Arcelito G. Dalit  
AGD Aircon & Refrigeration Services, Owner

**Conforme:** \_\_\_\_\_

Aircon & Ref Services