

Greetings!

We are pleased to send below quotation for your perusal. Should you have further clarifications, kindly let us know.
Thank you for doing business with us.

Date : **May 29, 2025**
To : **METROPOLITAN MEDICAL CENTER**
Attn : **PROCUREMENT**
Subject : **Proposal for the Installation of One (1) Wall Mounted Air-condition Unit**
Address : **1357 G. Masangkay St, Brgy Tondo Manila**

I. SCOPE OF WORK

- Hauling and fabrication of support bracket
- Installation of indoor & outdoor unit
- Installation of refrigerant piping with communication wires
- Installation of drain line
- System pressure test and leak testing using Nitrogen gas
- Air evacuation
- Tapping of power supply to ACU ECB
- Testing and commissioning

II. QUOTATION

HISPATHOLOGY - 2.5HP WALL MOUNTED (OUTDOOR POWER SUPPLY 1PHASE REQUIRED)				
QTY	UNIT	DESCRIPTION	PRICE PER UNIT	TOTAL
1	LOT	Basic installation cost for the 1st 10ft	7,700.00	7,700.00
6	FT	Excess copper tube w/ rubber insulation 1/4" x 1/2"	400.00	2,400.00
11	FT	Royal cord (communication) 2.mm2 x 4C	100.00	1,100.00
5	FT	Royal cord (ODU Breaker) wire 2.mm2 x 4C	60.00	300.00
1	PC	Weather proof nema 3R w/ breaker for ACCU - 30A/1Ph	1,000.00	1,000.00
1	LOT	PVC Drain line w/ elbow from FCU to roof drain	1,800.00	1,800.00
1	PC	Special fabrication of metal bracket for ACCU floor type	2,500.00	2,500.00
1	LOT	Special fabrication of wooden bracket to reinforce FCU installation and restoration	6,500.00	6,500.00

Total cost:	23,300.00
Less 10% discount	2,330.00
Net of Discount	₱ 20,970.00
Add: 12% VAT	2,516.40
TOTAL COST VAT INCLUSIVE	₱ 23,486.40

"We Bring the Cool back"

Inclusions: For Basic Installation

- a. Bracket and support
- b. 1st 10FT Copper Tube (**SOFT DRAWN**) w/ rubber insulation
- c. 3 meters communication wire
- d. Labor w/ equipments

Exclusions: For the 1st 10ft Basic Installation & Other Materials

- a. Panel Board Breaker, ACCU ECB, Coving of Ceiling, Wall Cladding, Chipping Works, Masonry Works
- b. Painting, Plastering and Restoration
- c. Mechanical Plans and permits
- d. Water proofing of flooring and roofing
- e. Supply and installation of Feeder Line to ACCU

Warranty:

- a. 5 years Compressor ; 1 year parts and workmanship within scope.
- b. Client is required to submit a copy of Sales Invoice or Proof of Purchase with Serial number for both indoor and outdoor unit for Manufacturer's Warranty purposes.
- c. All maintenance and services must be endorsed to AGD Aircon & Refrigeration services while on the warranty period.

Terms of Payment:

Full Payment Upon Completion

All payments should be payable to AGD AIRCON & REFRIGERATION SERVICES

Thank you,



Arcelito G. Dalit
AGD Aircon & Refrigeration Services, Owner

Conforme: _____

Aircon & Ref Services