

Greetings!

We are pleased to send below quotation for your perusal. Should you have further clarifications, kindly let us know.
Thank you for doing business with us.

Date : **July 9, 2025**
Attn : **Mr James Co**
Subject : **Proposal for the Installation of One (1) Wall Mounted Air-condition Unit**
Address : **5th Floor, 820 Liberty Hall Building Benavidez St, Binondo Manila**

I. SCOPE OF WORK

- a. Hauling and fabrication of support bracket
- b. Installation of indoor & outdoor unit
- c. Installation of refrigerant piping with communication wires
- d. Installation of drain line
- e. System pressure test and leak testing using Nitrogen gas
- f. Air evacuation
- g. Tapping of power supply to ACU ECB
- h. Testing and commissioning

II. QUOTATION

DANCING AREA - 6HP WALL MOUNTED (OUTDOOR POWER SUPPLY 1PHASE REQUIRED)				
QTY	UNIT	DESCRIPTION	PRICE PER UNIT	TOTAL
1	LOT	Basic installation cost for the 1st 10ft	14,000.00	14,000.00
7	FT	Royal cord (communication) 2.0mm x 4C	100.00	700.00
7	FT	Royal cord (ODU Breaker) wire 5.5mm x 3C	70.00	490.00
1	PC	Weather proof nema 3R w/ breaker for ACCU - 40A/1Ph	1,000.00	1,000.00
1	PC	Special fabrication of metal bracket for ACCU floor type	2,500.00	2,500.00
1	SET	Dismantling of existing unit 4HP floor standing	3,000.00	3,000.00
2	PC	PVC blue for drain line 3/4"x10"	150.00	300.00
1	LOT	Cutting and welding works for window to access of condenser unit going outside location	2,500.00	2,500.00
TOTAL COST :			₱	24,490.00
Less Discount:				1,490.00
Total Net of Discount Vat Exclusive :			₱	23,000.00

Inclusions: For Basic Installation

- a. Bracket and support
- b. 1st 10FT Copper Tube (SOFT DRAWN) w/ rubber insulation
- c. 3 meters communication wire
- d. Labor w/ equipments

Exclusions: For the 1st 10ft Basic Installation & Other Materials

- a. Panel Board Breaker, ACCU ECB, Coving of Ceiling , Wall Cladding, Chipping Works, Masonry Works
- b. Painting, Plastering and Restoration
- c. Mechanical Plans and permits
- d. Water proofing of flooring and roofing
- e. Supply and installation of Feeder Line to ACCU

Warranty:

- a. 5 years Compressor ; 1 year parts and workmanship within scope.
- b. Client is required to submit a copy of Sales Invoice or Proof of Purchase with Serial number for both indoor and outdoor unit for Manufacturer's Warranty purposes.
- c. All maintenance and services must be endorsed to AGD Aircon & Refrigeration services while on the warranty period.

Terms of Payment:

Full Payment Upon Completion
All payments should be payable to **AGD AIRCON & REFRIGERATION SERVICES**

Thank you,



Arcelito G. Dalit
AGD Aircon & Refrigeration Services, Owner

Conforme: _____

“We Bring the Cool back”