

kolin

air conditioner

June 4, 2024

ATTN: ARCH. RAJ ABELLA
U-B #50 SAMAR AVE. BRGY SOUTH TRIANGLE,
DILIMAN, QUEZON CITY
Tel#: 0917-576-6663

Dear Ma'am/Sir,

Kolin Marketing Inc., is extremely honored for your endorsement of Kolin brand and we are please to offer you with a special price/s for the following items.

A. EQUIPMENT & INSTALLATION

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
1	UNIT/S	MODEL: KLG-IF40-3D1M KOLIN FLOOR MOUNTED AIRCONDITIONER (3.0TR) INVERTER	106,095.00	75,754.10	PHP	75,754.10
2	UNIT/S	MODEL: KSM-IW15-WCT10M1M32 KOLIN WALL MOUNTED CERTUS SERIES AIRCONDITIONER 12,660 Kj/h (1.5HP) REGULAR INVERTER R-32	32,495.00	21,346.10	PHP	42,692.20
1	UNIT/S	MODEL: KSM-IW20-WCT10M1M32 KOLIN WALL MOUNTED CERTUS SERIES AIRCONDITIONER 18,990 Kj/h (2.0HP) REGULAR INVERTER R-32	41,495.00	28,366.10	PHP	28,366.10
1	UNIT/S	MODEL: KSM-IW25-WCT10M1M32 KOLIN WALL MOUNTED CERTUS AIRCONDITIONER 23,210 Kj/h (2.5HP) REGULAR INVERTER W/ WIFI R-32	49,495.00	34,606.10	PHP	34,606.10
TOTAL UNIT COST					PHP	181,418.50
ESTIMATED COST OF INSTALLATION (please see attached)					PHP	88,345.00
OTHERS: DELIVERY CHARGE					PHP	600.00
TOTAL ESTIMATED COST OF THE PROJECT					PHP	270,363.50

TERMS OF PAYMENT:

FULL PAYMENT OF UNIT AND DELIVERY CHARGE. IF CHECK, SUBJECT FOR 3 DAYS CLEARING.

WARRANTY:

FOR FLOOR MOUNTED (Inverter): ONE (1) YEAR FREE PARTS AND LABOR, THREE (3) YEARS WARRANTY ON COMPRESSOR.
FOR SPLIT TYPE (Commercial): ONE (1) YEAR FREE PARTS AND LABOR, TEN (10) YEARS WARRANTY ON COMPRESSOR.

NOTES: PRICES ARE SUBJECT TO CHANGE WITHOUT PRIOR NOTICE.

PRICES IS VAT INCLUSIVE.

INSTALLATION C/O AUTHORIZED SERVICE CENTER.

**** Cost of Installation is Package with the Unit(s), this cost cannot avail separately.**

We thank you for giving opportunity to offer our product and services, hoping we receive your purchase order.

If you need assistance, don't hesitate to call the under signed at 0917-807-8607 or email at kmi_asst@kolinphil.com.ph

Very Truly Yours,


JANELLEN LIM
KMI-ASSISTANT

Noted By:


MART NATHANIEL R. FLORES
KMI-SUPERVISOR

Approved By:


MS. EDITHA M. FLORES
AVP - FINANCE

Conforme:

SIGNATURE OVER PRINTED NAME

KMI-QUOTE-06-24-0512
REG-22%/7K/4K

Kolin Marketing, Inc.

1854 Sta. Rita St., Guadalupe Nuevo, Makati City

www.kolinphil.com.ph

Tel.: (632) 8852-6473

Fax: (632) 8852-2170 / (632) 8852-4792

Bringing comfort to your home.

April 3, 2024
 ARCH. RAJ ABELLA
 Unit B, #50 Samar Ave. Brgy South Triangle, Diliman Quezon City
 0917-5766663

MODEL	Qty
KLG-IF40-5G1M32	1
KSM-IW25-WCT10M1M32	1
KSM-IW20-WCT10M1M32	1
KSM-IW15-WCT10M1M32	2

LIVING/ DINING	Area	39 sqm
----------------	------	--------

ACU 1	4.0 HP Floor Standing Inverter	KLG-IF40-5G1M32
	Estimated Pipe Length = 66 ft	
	Estimated Royal Cord Length = 73 ft	
	Initial Charge	₱ 11,000.00
	Includes:	
	Labor	
	10ft Copper Tube	
	10ft Royal Cord	
	Indoor Bracket (Floor)	
	Consumables	
Installation Materials	Description	Qty Price per qty Subtotal
Copper tube	5/8" x 3/8"	56 ft ₱ 400.00/ft ₱ 22,400.00
Royal Cord (comm. wire)	2.mm2 x 4C	63 ft ₱ 100.00/ft ₱ 6,300.00
Royal Cord (ACCU-Breaker)	5.5mm x 3c	7 ft ₱ 70.00/ft ₱ 490.00
Metal Conduit	1/2"	7 ft ₱ 40.00/ft ₱ 280.00
Circuit Breaker waterproof	40A / 1Ph	1 pc/s ₱ 1,000.00/pc ₱ 1,000.00
Drain Hose	White -1/2"	7 ft ₱ 25.00/ft ₱ 175.00
		₱ 30,645.00

Estimated Charges	₱ 41,645.00
-------------------	-------------

BEDROOM 1	Area	16 sqm
-----------	------	--------

ACU 2	1.5 HP Wall Mounted Inverter	KSM-IW15-WCT10M1M32
	Estimated Pipe Length = 10 ft	
	Estimated Royal Cord Length = 15 ft	
	Initial Charge	₱ 7,500.00
	Includes:	
	Labor	
	10ft Copper Tube	
	10ft Royal Cord	
	Outdoor Bracket (Wall)	
	Consumables	
Installation Materials	Description	Qty Price per qty Subtotal
Royal Cord (comm. wire)	2.mm2 x 4C	5 ft ₱ 100.00/ft ₱ 500.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft ₱ 60.00/ft ₱ 300.00
Metal Conduit	1/2"	5 ft ₱ 40.00/ft ₱ 200.00
Circuit Breaker waterproof	20A/1PH	1 pc/s ₱ 1,000.00/pc ₱ 1,000.00
Leaktest (Existing)	1/4 x 1/2"	1 set ₱ 1,800.00/set ₱ 1,800.00
Drain Hose	White -1/2"	5 ft ₱ 25.00/ft ₱ 125.00
		₱ 3,925.00

Estimated Charges	₱ 11,425.00
-------------------	-------------

MASTER BEDROOM	Area	22 sqm
-----------------------	------	--------

ACU 3 2.0 HP Wall Mounted Inverter **KSM-IW20-WCT10M1M32**

Estimated Pipe Length = 10 ft

Estimated Royal Cord Length = 15 ft

Initial Charge

P 7,500.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Outdoor Bracket (Wall)

Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Royal Cord (comm. wire)	2.mm2 x 4C	5 ft	P 100.00/ft	P 500.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	P 60.00/ft	P 300.00
Metal Conduit	1/2"	5 ft	P 40.00/ft	P 200.00
Circuit Breaker waterproof	30A/1PH	1 pc/s	P 1,000.00/pc	P 1,000.00
Leaktest (Existing)	1/4 x 1/2"	1 set	P 1,800.00/set	P 1,800.00
Drain Hose	White -1/2"	5 ft	P 25.00/ft	P 125.00
				P 3,925.00

Estimated Charges		P 11,425.00
--------------------------	--	-------------

BEDROOM 2	Area	12 sqm
------------------	------	--------

ACU 4 1.5 HP Wall Mounted Inverter **KSM-IW15-WCT10M1M32**

Estimated Pipe Length = 10 ft

Estimated Royal Cord Length = 15 ft

Initial Charge

P 7,500.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Outdoor Bracket (Wall)

Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Royal Cord (comm. wire)	2.mm2 x 4C	5 ft	P 100.00/ft	P 500.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	P 60.00/ft	P 300.00
Metal Conduit	1/2"	5 ft	P 40.00/ft	P 200.00
Circuit Breaker waterproof	20A/1PH	1 pc/s	P 1,000.00/pc	P 1,000.00
Leaktest (Existing)	1/4 x 1/2"	1 set	P 1,800.00/set	P 1,800.00
Drain Hose	White -1/2"	5 ft	P 25.00/ft	P 125.00
				P 3,925.00

Estimated Charges		P 11,425.00
--------------------------	--	-------------

ENTERTAINMENT AREA	Area	21 sqm
---------------------------	------	--------

ACU 5 2.5 HP Wall Mounted Inverter **KSM-IW25-WCT10M1M32**

Estimated Pipe Length = 10 ft

Estimated Royal Cord Length = 15 ft

Initial Charge

P 8,500.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Outdoor Bracket (Wall)

Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Royal Cord (comm. wire)	2.mm2 x 4C	5 ft	P 100.00/ft	P 500.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	P 60.00/ft	P 300.00
Metal Conduit	1/2"	5 ft	P 40.00/ft	P 200.00
Circuit Breaker waterproof	30A/1PH	1 pc/s	P 1,000.00/pc	P 1,000.00
Leaktest (Existing)	1/4 x 1/2"	1 set	P 1,800.00/set	P 1,800.00
Drain Hose	White -1/2"	5 ft	P 25.00/ft	P 125.00
				P 3,925.00

Estimated Charges		P 12,425.00
--------------------------	--	-------------

Total Estimated Charges


P 88,345.00

Validity: This quotation is valid for a period of fifteen (15) days from the date thereof, subject to our confirmation thereafter.

Installation notes:

- 1 Indoor and outdoor units are based on existing location on site.
- 2 Mechanical Plans, Permits, Electrical permits not included.
- 3 No current unit were match for living and dining area due to existing copper tube are 3/4" x 1/2", recommends to lay out new copper tube.
- 4 **Need to leaktest existing copper tube except on living and dining area, existing of 1/4 x 1/2" Royal Cord.**
- 5 **Bring rope and harness for ACU1 Location. Put a metal conduit each feeder line.**
- 6 Deflectors, masonry, carpentry, chipping & plastering (finishing & restoration) are not included in the installation.
- 7 Air conditioning drain line and Electrical power supply (feeder line) **220v/ 60hz/ 1ph**, should be provided by customer's contractor.
- 8 **Final charges will be based on actual installation.**


Prepared by:


Jeffrey Dadios
Field Surveyor

Customer Conformer:

Signature Over Printed Name

Reviewed by:


Engr. Kenneth Zamora
Service Supervisor Shop and
Field Operation