

kolin

air conditioner

August 5, 2024

ATTY. PETER SUCHIANGCO
119 AQUARIUS ST., CINCO HERMANOS, MARIKINA CITY
TEL #: 0966-624999 / 0922-814271
Email: rdmtech.88@gmail.com

Dear Ma'am/Sir,

Kolin Marketing Inc., is extremely honored for your endorsement of Kolin brand and we are please to offer you with a special price/s for the following items.

A. EQUIPMENT & INSTALLATION

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
2	UNIT/S	MODEL: KLM-IC40-AA1M32 KOLIN FLOOR/CEILING AIRCONDITIONER 37,980 Kj/h (3.0TR) DC INVERTER R-32	117,995.00	92,036.10	PHP	184,072.20
4	UNIT/S	MODEL: KSG-IWF-30WFF-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 29,500 Kj/h (3.0HP) FULL DC INVERTER W/ WIFI R-32	76,595.00	55,744.10	PHP	222,976.40
2	UNIT/S	MODEL: KSG-IWF-25WFF-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 25,560 Kj/h (2.5HP) FULL DC INVERTER W/ WIFI R-32	68,995.00	49,816.10	PHP	99,632.20
1	UNIT/S	MODEL: KSG-IWF-20WFF-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 19,000 Kj/h (2.0HP) FULL DC INVERTER W/ WIFI R-32	59,595.00	42,484.10	PHP	42,484.10
2	UNIT/S	MODEL: KSG-IWF-10WFF-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 11,484 Kj/h (1.0HP) FULL DC INVERTER W/ WIFI R-32	42,595.00	29,224.10	PHP	58,448.20
1	UNIT/S	MODEL: KAG-250WCINV KOLIN WINDOW TYPE QUAD SERIES AIRCONDITIONER 24,120 Kj/h (2.5HP) FULL DC INVERTER W/ WIFI R-32 (WxDxH) 26"x31.5"x17"	48,695.00	36,182.10	PHP	36,182.10
TOTAL UNIT COST					PHP	643,795.20
ESTIMATED COST OF INSTALLATION (please see attached)					PHP	255,105.00
OTHERS: DELIVERY CHARGE					PHP	600.00
TOTAL ESTIMATED COST OF THE PROJECT					PHP	899,500.20

TERMS OF PAYMENT:

FULL PAYMENT OF UNIT AND DELIVERY CHARGE. IF CHECK, SUBJECT FOR 3 DAYS CLEARING.

WARRANTY:

FOR FLOOR MOUNTED (Inverter): ONE (1) YEAR FREE PARTS AND LABOR, THREE (3) YEARS WARRANTY ON COMPRESSOR.

FOR SPLIT TYPE : ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB, TEN (10) YEARS WARRANTY ON COMPRESSOR.

FOR WINDOW TYPE: ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB, TEN (10) YEARS WARRANTY ON COMPRESSOR.

NOTES: PRICES ARE SUBJECT TO CHANGE WITHOUT PRIOR NOTICE.


PRICES IS VAT INCLUSIVE.

**** Cost of Installation is Package with the Unit(s), this cost cannot avail separately.**

We thank you for giving opportunity to offer our product and services, hoping we receive your purchase order.

If you need assistance, don't hesitate to call the under signed at 0917-807-8607 or email at kmi_asst@kolinphil.com.ph

Very Truly Yours,


JANELLE S. LIM
KMI-ASSISTANT

Noted by:


MART NATHANIEL R. FLORES
KMI-SUPERVISOR

KMI-QUOTE-08-24-0690
REG-22%/4K/1.8K

Approved By:


MS. EDITHA M. FLORES
AVP - FINANCE

Conforme:

SIGNATURE OVER PRINTED NAME

Kolin Marketing, Inc.

1854 Sta. Rita St., Guadalupe Nuevo, Makati City

www.kolinphil.com.ph

Tel.: (632) 8852-6473

Fax: (632) 8852-2170 / (632) 8852-4792

Bringing comfort to your home.

AUGUST 01, 2024

ATTY. PETER SUCHIANGCO

119 Aquarius St, Cinco Hermanos, Marikina City

0966-624999/ 0922-814271

rdmtech.88@gmail.com

MODEL	Qty
KLM-IC40-AA1M32	2
KSG-IWF-30Wfy8K1M32	4
KSG-IWF-25Wfy8K1M32	2
KSG-IWF-20Wfy8K1M32	1
KSG-IWF-10Wfy8K1M32	2
KAG-250WCINV	1

rev3- This quotation is for new units

DINING ROOM	Area	27 sqm
--------------------	------	--------

ACU 1	3.0 HP Wall Mounted Inverter	KSG-IWF-30Wfy8K1M32
	Estimated Pipe Length = 50 ft	
	Estimated Royal Cord Length = 55 ft	
	Initial Charge	₱ 5,500.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Outdoor Bracket (Wall)

Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 5/8"	40 ft	₱ 400.00/ft	₱ 16,000.00
Royal Cord (comm. wire)	2.mm2 x 4C	45 ft	₱ 100.00/ft	₱ 4,500.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	₱ 60.00/ft	₱ 300.00
Circuit Breaker waterproof	30A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	5 pc/s	₱ 350.00/pc	₱ 1,750.00
PVC blue	3/4" x 10'	1 pc/s	₱ 150.00/pc	₱ 150.00
				₱ 23,700.00

Estimated Charges	₱ 29,200.00
--------------------------	-------------

KITCHEN	Area	20 sqm
----------------	------	--------

ACU 2	3.0 HP Wall Mounted Inverter	KSG-IWF-30Wfy8K1M32
	Estimated Pipe Length = 50 ft	
	Estimated Royal Cord Length = 55 ft	
	Initial Charge	₱ 5,500.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Outdoor Bracket (Wall)

Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 5/8"	40 ft	₱ 400.00/ft	₱ 16,000.00
Royal Cord (comm. wire)	2.mm2 x 4C	45 ft	₱ 100.00/ft	₱ 4,500.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	₱ 60.00/ft	₱ 300.00
Circuit Breaker waterproof	30A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	5 pc/s	₱ 350.00/pc	₱ 1,750.00
PVC blue	3/4" x 10'	2 pc/s	₱ 150.00/pc	₱ 300.00
				₱ 23,850.00

Estimated Charges	₱ 29,350.00
--------------------------	-------------

HALLWAY	Area	29 sqm
----------------	------	--------

ACU 3 3.0 HP Wall Mounted Inverter **KSG-IWF-30Wfy8K1M32**

Estimated Pipe Length = 50 ft

Estimated Royal Cord Length = 55 ft

Initial Charge P 5,500.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Outdoor Bracket (Wall)

Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 5/8"	40 ft	P 350.00/ft	P 14,000.00
Royal Cord (comm. wire)	2.mm2 x 4C	45 ft	P 100.00/ft	P 4,500.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	P 60.00/ft	P 300.00
Circuit Breaker waterproof	30A / 1Ph	1 pc/s	P 1,000.00/pc	P 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	6 pc/s	P 350.00/pc	P 2,100.00
Dismantle	2.5HP Wall Mounted	1 set	P 2,500.00/set	P 2,500.00
PVC blue	3/4" x 10'	1 pc/s	P 150.00/pc	P 150.00
				P 24,550.00

Estimated Charges		P 30,050.00
--------------------------	--	-------------

MASTER BEDROOM	Area	24 sqm
-----------------------	------	--------

ACU 4 2.5 HP Wall Mounted Inverter **KSG-IWF-25Wfy8K1M32**

Estimated Pipe Length = 40 ft

Estimated Royal Cord Length = 45 ft

Initial Charge P 5,500.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Outdoor Bracket (Wall)

Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 5/8"	30 ft	P 350.00/ft	P 10,500.00
Royal Cord (comm. wire)	2.mm2 x 4C	35 ft	P 100.00/ft	P 3,500.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	P 60.00/ft	P 300.00
Circuit Breaker waterproof	30A / 1Ph	1 pc/s	P 1,000.00/pc	P 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	4 pc/s	P 350.00/pc	P 1,400.00
PVC blue	3/4" x 10'	1 pc/s	P 150.00/pc	P 150.00
				P 16,850.00

Estimated Charges		P 22,350.00
--------------------------	--	-------------

FAMILY ROOM	Area	25 sqm
--------------------	------	--------

ACU 5 3.0 HP Wall Mounted Inverter **KSG-IWF-30Wfy8K1M32**

Estimated Pipe Length = 23 ft

Estimated Royal Cord Length = 28 ft

Initial Charge P 5,500.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Outdoor Bracket (Wall)

Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 5/8"	13 ft	P 350.00/ft	P 4,550.00
Royal Cord (comm. wire)	2.mm2 x 4C	18 ft	P 100.00/ft	P 1,800.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	P 60.00/ft	P 300.00
Circuit Breaker waterproof	30A / 1Ph	1 pc/s	P 1,000.00/pc	P 1,000.00
PVC blue	3/4" x 10'	2 pc/s	P 150.00/pc	P 300.00
				P 7,950.00

Estimated Charges		P 13,450.00
--------------------------	--	-------------

WALK IN CLOSET	Area	10 sqm
-----------------------	------	--------

ACU 6 1.0 HP Wall Mounted Inverter **KSG-IWF-10Wfy8K1M32**

Estimated Pipe Length = 40 ft

Estimated Royal Cord Length = 45 ft

Initial Charge P 4,500.00

Includes:

- Labor
- 10ft Copper Tube
- 10ft Royal Cord
- Outdoor Bracket (Wall)
- Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 3/8"	30 ft	P 350.00/ft	P 10,500.00
Royal Cord (comm. wire)	2.mm2 x 4C	35 ft	P 100.00/ft	P 3,500.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	P 60.00/ft	P 300.00
Circuit Breaker waterproof	30A / 1Ph	1 pc/s	P 1,000.00/pc	P 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	4 pc/s	P 350.00/pc	P 1,400.00
PVC blue	3/4" x 10'	2 pc/s	P 150.00/pc	P 300.00
				P 17,000.00

Estimated Charges		P 21,500.00
--------------------------	--	-------------

T & B	Area	10 sqm
------------------	------	--------

ACU 7 1.0 HP Wall Mounted Inverter **KSG-IWF-10Wfy8K1M32**

Estimated Pipe Length = 37 ft

Estimated Royal Cord Length = 42 ft

Initial Charge P 4,500.00

Includes:

- Labor
- 10ft Copper Tube
- 10ft Royal Cord
- Outdoor Bracket (Wall)
- Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 3/8"	27 ft	P 350.00/ft	P 9,450.00
Royal Cord (comm. wire)	2.mm2 x 4C	32 ft	P 100.00/ft	P 3,200.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	P 60.00/ft	P 300.00
Circuit Breaker waterproof	30A / 1Ph	1 pc/s	P 1,000.00/pc	P 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	3 pc/s	P 350.00/pc	P 1,050.00
PVC blue	3/4" x 10'	2 pc/s	P 150.00/pc	P 300.00
				P 15,300.00

Estimated Charges		P 19,800.00
--------------------------	--	-------------

HALLWAY 2ND FLOOR	Area	23 sqm
--------------------------	------	--------

ACU 8 2.5 HP Wall Mounted Inverter **KSG-IWF-25Wfy8K1M32**

Estimated Pipe Length = 23 ft

Estimated Royal Cord Length = 28 ft

Initial Charge P 5,500.00

Includes:

- Labor
- 10ft Copper Tube
- 10ft Royal Cord
- Outdoor Bracket (Wall)
- Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 5/8"	13 ft	P 350.00/ft	P 4,550.00
Royal Cord (comm. wire)	2.mm2 x 4C	18 ft	P 100.00/ft	P 1,800.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	P 60.00/ft	P 300.00
Rubber Insulation	2 1/8" x 3/4" x 6'	2 pc/s	P 350.00/pc	P 700.00
Circuit Breaker waterproof	30A / 1Ph	1 pc/s	P 1,000.00/pc	P 1,000.00
PVC blue	3/4" x 10'	1 pc/s	P 150.00/pc	P 150.00
				P 8,500.00

Estimated Charges		P 14,000.00
--------------------------	--	-------------

BEDROOM 1	Area	20 sqm
------------------	------	--------

ACU 9 2.0 HP Wall Mounted Inverter **KSG-IWF-20WFY8K1M32**

Estimated Pipe Length = 20 ft

Estimated Royal Cord Length = 25 ft

Initial Charge P 5,500.00

Includes:

Labor
10ft Copper Tube
10ft Royal Cord
Outdoor Bracket (Wall)
Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 1/2"	10 ft	P 350.00/ft	P 3,500.00
Royal Cord (comm. wire)	2.mm2 x 4C	15 ft	P 100.00/ft	P 1,500.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	P 60.00/ft	P 300.00
Circuit Breaker waterproof	30A / 1Ph	1 pc/s	P 1,000.00/pc	P 1,000.00
PVC blue	3/4" x 10'	1 pc/s	P 150.00/pc	P 150.00
				P 6,450.00

Estimated Charges	P 11,950.00
--------------------------	--------------------

DANCE STUDIO	Area	25 sqm
---------------------	------	--------

ACU 10 2.5 HP Window type Inverter **KAG-250WCINV**

Initial Charge P 1,200.00

Includes:

Labor
Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Window type bracket		1 pc/s	P 600.00/pc	P 600.00
Drain Hose	White -1/2"	7 ft	P 25.00/ft	P 175.00
				P 775.00

Estimated Charges	P 1,975.00
--------------------------	-------------------

ENTERTAINMENT ROOM	Area	63 sqm
---------------------------	------	--------

ACU 11 4.0 HP Ceiling Suspended Inverter **KLM-IC40-AA1M32**

Estimated Pipe Length = 27 ft

Estimated Royal Cord Length = 34 ft

Initial Charge P 12,000.00

Includes:

Labor
10ft Copper Tube
10ft Royal Cord
Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 3/8" x Ø 5/8"	17 ft	P 400.00/ft	P 6,800.00
Royal Cord (comm. wire)	2.mm2 x 4C	24 ft	P 100.00/ft	P 2,400.00
Royal Cord (ACCU-Breaker)	5.5mm x 3c	7 ft	P 70.00/ft	P 490.00
Circuit Breaker waterproof	40A/1PH	1 pc/s	P 1,000.00/pc	P 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	1 pc/s	P 350.00/pc	P 350.00
Indoor bracket	Fabricated floor	1 pc/s	P 1,500.00/pc	P 1,500.00
Outdoor bracket	Fab. wall w/ledge	1 pc/s	P 6,500.00/pc	P 6,500.00
Dismantle	4.0HP Floor Standing	1 set	P 3,000.00/set	P 3,000.00
PVC blue	3/4" x 10'	3 pc/s	P 150.00/pc	P 450.00
				P 22,490.00

Estimated Charges	P 34,490.00
--------------------------	--------------------

ACU 12 4.0 HP Ceiling Suspended Inverter**KLM-IC40-AA1M32**

Estimated Pipe Length = 30 ft

Estimated Royal Cord Length = 37 ft

Initial Charge

P 12,000.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Indoor Bracket (Floor)

Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 3/8" x Ø 5/8"	20 ft	P 350.00/ft	P 7,000.00
Royal Cord (comm. wire)	2.mm2 x 4C	27 ft	P 100.00/ft	P 2,700.00
Royal Cord (ACCU-Breaker)	5.5mm x 3c	7 ft	P 70.00/ft	P 490.00
Circuit Breaker waterproof	40A/1PH	1 pc/s	P 1,000.00/pc	P 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	1 pc/s	P 350.00/pc	P 350.00
Outdoor bracket	Modified	1 pc/s	P 1,500.00/pc	P 1,500.00
scaffoldings	4sets	1 mtr	P 1,500.00/mtr	P 1,500.00
PVC blue	3/4" x 10'	3 pc/s	P 150.00/pc	P 450.00
				P 14,990.00

Estimated Charges	P 26,990.00
--------------------------	--------------------

Total Estimated Charges	P 255,105.00
--------------------------------	---------------------

NOTES: DISMANTLE UNITS PRICE FOR EXISTING

1. ACU3 - 1ST FLOOR HALLWAY- 2.5HP , WALL MOUNTED - 2,500 Plus PULL-OUT 500= 3,000

2. ACU9 - 2ND FLOOR HALLWAY- 3.0HP , WALL MOUNTED - 2,500 Plus PULL-OUT 500= 3,000

Additional existing units already dismantle:for check up and install if still serviceable.

1. KSM-IW20-4F1M

2. KSM-IW30-4F1M

3. KSM-IW29AE-5G1M

Bring to shop to determined if still serviceable, SHOP will provide the check up and repair QUOTATION**Validity:** This quotation is valid for a period of fifteen (15) days from the date thereof, subject to our confirmation thereafter.**Installation notes:**

- 1 Location based in floor plan only. Not yet final. For confirmation of location. indoor and outdoor.
- 2 AC drain line will be tapped to the nearest drain provision provided by the customer's contractor.
- 3 Need for marking and site visit with installer before installation.
- 4 Coppertube expose in the area. Customer will cover the coppertube after installation.
- 5 Working days: Monday to Saturday, 8am- 5pm with parking. Need working permit.
- 6 Mechanical Plans, Permits, Electrical permits not included.
- 7 Deflectors, masonry, carpentry, chipping & plastering (finishing & restoration) are not included in the installation.
- 8 Air conditioning drain line and Electrical power supply (feeder line) **220v/ 60hz/ 1ph** , should be provided by customer's contractor.
- 9 **Final charges will be based on actual installation.**

Prepared by:

Customer Conformer:

Jeffrey Dadios

Field Surveyor

Signature Over Printed Name

Reviewed by:

Engr. Kenneth ZamoraService Supervisor Shop and
Field Operation

