

FAIRE TECHNOLOGIES INC.
49 E. FERNANDEZ ST., BATIS SAN JUAN CITY
ATTN: MR. NORVIN CO
TEL#: 0917-5317212

Dear Ma'am/Sir,

Kolin Marketing Inc., is extremely honored for your endorsement of Kolin brand and we are please to offer you with a special price/s for the following items.

A. EQUIPMENT & INSTALLATION

* OPTION 1 *

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
3	UNIT/S	MODEL: KA-100MCARINV32 KOLIN WINDOW TYPE CREO SERIES AIRCONDITIONER 9,700 Kj/h (1.0HP) FULL DC INVERTER R-32 WITH REMOTE (WxDxH) 17.7"x26.6"x13.8"	24,995.00	18,196.20	PHP	54,588.60
2	UNIT/S	MODEL: KA-200MCARINV32 KOLIN WINDOW TYPE CREO SERIES AIRCONDITIONER 19,800 Kj/h (2.0HP) FULL DC INVERTER R-32 WITH REMOTE (WxDxH) 26"x30.7"x16.8"	36,995.00	26,916.20	PHP	53,832.40
3	UNIT/S	MODEL: KSM-IW10-WCT10M1M32 KOLIN WALL MOUNTED CERTUS SERIES AIRCONDITIONER 9,800 Kj/h (1.0HP) REGULAR INVERTER W/ WIFI R-32	29,995.00	18,796.20	PHP	56,388.60
1	UNIT/S	MODEL: KSM-IW15-WCT10M1M32 KOLIN WALL MOUNTED CERTUS SERIES AIRCONDITIONER 12,660 Kj/h (1.5HP) REGULAR INVERTER W/ WIFI R-32	32,995.00	21,076.20	PHP	21,076.20
2	UNIT/S	MODEL: KSM-IW20-WCT10M1M32 KOLIN WALL MOUNTED CERTUS SERIES AIRCONDITIONER 18,990 Kj/h (2.0HP) REGULAR INVERTER W/ WIFI R-32	41,995.00	27,916.20	PHP	55,832.40
1	UNIT/S	MODEL: KSM-IW25-WCT10M1M32 KOLIN WALL MOUNTED CERTUS AIRCONDITIONER 23,210 Kj/h (2.5HP) REGULAR INVERTER W/ WIFI R-32	49,995.00	33,996.20	PHP	33,996.20
1	UNIT/S	MODEL: KSG-IWF-30WFF-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 29,500 Kj/h (3.0HP) FULL DC INVERTER W/ WIFI R-32	76,595.00	51,212.20	PHP	51,212.20
TOTAL UNIT COST					PHP	326,926.60
ESTIMATED COST OF INSTALLATION (please see attached)					PHP	161,100.00
TOTAL UNIT COST					PHP	488,026.60

TERMS OF PAYMENT:

FULL PAYMENT OF UNIT AND DELIVERY CHARGE. IF CHECK, SUBJECT FOR 3 DAYS CLEARING.

WARRANTY:

FOR WINDOW TYPE: ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB, TEN (10) YEARS WARRANTY ON COMPRESSOR.

FOR SPLIT TYPE: ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB, TEN (10) YEARS WARRANTY ON COMPRESSOR.

NOTES: PRICES ARE SUBJECT TO CHANGE WITHOUT PRIOR NOTICE.

PRICES IS VAT INCLUSIVE.

** Cost of Installation is Package with the Unit(s), this cost cannot avail separately (cost will be based on actual works).

*** You may settle first payment for unit/s & delivery. Installation payment can be settled directly to installer after actual works.

We thank you for giving opportunity to offer our product and services, hoping we receive your purchase order.

If you need assistance, don't hesitate to call the under signed at 0917-807-8607 or email at kmi_asst@kolinphil.com.ph

*Model KSM-IW15-WCT10M1M32 is already out of stock. You may consider model KSG-IWF-15WFF-8K1M32 on Option 2.

Very Truly Yours,

JANELLEN S. LIM
KMI-ASSISTANT

Noted by:
MART NATHANIEL R. FLORES
KMI-SUPERVISOR

Approved By:

MS. EDITHA M. FLORES
AVP - FINANCE

KMI-QUOTE-09-25-0723
NG-24%/800/1.2K/4K/7K

Conforme:

SIGNATURE OVER PRINTED NAME

Kolin Marketing, Inc.

1854 Sta. Rita St., Guadalupe Nuevo, Makati City

Tel.: (632) 8852-6473

Fax: (632) 8852-2170 / (632) 8852-4792

www.kolinphil.com.ph / kolinphilippines





RKH Airconditioning Services

Gomega Condo Daang Bakal Mandaluyong City

Customer Name:	Faire Technologies c/o Norvin Co	Date:	September 24, 2025
Customer Address:	49 E Fernandez st. Batis San Juan City		

Qty	Unit Model	Unit Capacity/Type
3	KAG-100WCINV	1.0Hp Window Type Inverter
2	KAG-200WCINV	2.0HP Window Type Inverter
3	KSM-IW10-WCT10M1M32	1.0HP Wall Mounted Inverter
1	KSM-IW15-WCT10M1M32	1.5HP Wall Mounted Inverter
2	KSM-IW20-WCT10M1M32	2.0HP Wall Mounted Inverter
1	KSM-IW25-WCT10M1M32	2.5HP Wall Mounted Inverter
1	KSG-IWF-30Wfy8K1M32	3.0HP Wall Mounted Inverter

Location/s:	Conference 1	Area:	7.60	sqm.
-------------	--------------	-------	------	------

ACU #:		Unit Model:	KAG-100WCINV /	Unit Capacity/Type:	1.0Hp Window Type Inverter
--------	--	-------------	----------------	---------------------	----------------------------

Initial Charge				₱	1,200.00
Installation Materials	Specification	Qty	Price per qty	Subtotal	
WAC Angle Bracket		1 set	600.00 /set	600.00	
Estimated Charges				₱	1,800.00

Location/s:	Conference 2	Area:	7.60	sqm.
-------------	--------------	-------	------	------

ACU #:	2	Unit Model:	KSM-IW10-WCT10M1M32 /	Unit Capacity/Type:	1.0HP Wall Mounted Inverter
--------	---	-------------	-----------------------	---------------------	-----------------------------

Estimated Pipe Length		=	25	ft	
Estimated Royal Cord Length		=	30	ft	
Initial Charge				₱	7,500.00
10ft Copper tube					
10ft Royal Cord					
Outdoor bracket Wall/Floor					
Consumables					
Testing and Commisioning					
Installation Materials	Specification	Qty	Price per qty	Subtotal	
Insulated Copper tube	3/8"Ø x 1/4"Ø	15 ft	₱ 350.00 /ft	₱ 5,250.00	
Royal Cord (Comm wire)	2.0 sq.mm x 4c	20 ft	100.00 /ft	2,000.00	
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	7 ft	60.00 /ft	420.00	
Circuir Breaker Weather Proof	20Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00	
Outdoor Unit Bracket Type	Fabricated floor	1 set	2,500.00 /set	2,500.00	
Estimated Charges				₱	18,670.00

Location/s:	Conference 3		Area:	13.50	sqm.
ACU #:	3	Unit Model:	KSM-IW15-WCT10M1M32	Unit Capacity/Type:	1.5HP Wall Mounted Inverter

Estimated Pipe Length = 15 ft

Estimated Royal Cord Length = 20 ft

Initial Charge ₱ 7,500.00

10ft Copper tube
10ft Royal Cord
Outdoor bracket Wall/Floor
Consumables
Testing and Commissioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	5 ft	₱ 350.00 /ft	₱ 1,750.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	10 ft	100.00 /ft	1,000.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	7 ft	60.00 /ft	420.00
Circuit Breaker Weather Proof	20Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
Outdoor Unit Bracket Type	Fabricated floor	1 set	2,500.00 /set	2,500.00

Estimated Charges ₱ 14,170.00

Location/s:	Conference Hallway		Area:	3.24	sqm.
--------------------	--------------------	--	--------------	------	------

ACU #:	4	Unit Model:	KSM-IW10-WCT10M1M32	Unit Capacity/Type:	1.0HP Wall Mounted Inverter
---------------	---	--------------------	---------------------	----------------------------	-----------------------------

Estimated Pipe Length = 15 ft

Estimated Royal Cord Length = 20 ft

Initial Charge ₱ 7,500.00

10ft Copper tube
10ft Royal Cord
Outdoor bracket Wall/Floor
Consumables
Testing and Commissioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	3/8"Ø x 1/4"Ø	5 ft	₱ 350.00 /ft	₱ 1,750.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	10 ft	100.00 /ft	1,000.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	7 ft	60.00 /ft	420.00
Circuit Breaker Weather Proof	20Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
Outdoor Unit Bracket Type	Fabricated floor	1 set	2,500.00 /set	2,500.00

Estimated Charges ₱ 14,170.00

Location/s:	Boss Office		Area:	9.60	sqm.
ACU #:	5	Unit Model:	KSM-IW10-WCT10M1M32	Unit Capacity/Type:	1.0HP Wall Mounted Inverter

Estimated Pipe Length = 25 ft

Estimated Royal Cord Length = 30 ft

Initial Charge ₱ 7,500.00

10ft Copper tube
10ft Royal Cord
Outdoor bracket Wall/Floor
Consumables
Testing and Commissioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	3/8"Ø x 1/4"Ø	15 ft	₱ 350.00 /ft	₱ 5,250.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	20 ft	100.00 /ft	2,000.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	7 ft	60.00 /ft	420.00
Circuit Breaker Weather Proof	20Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
Outdoor Unit Bracket Type	Fabricated floor	1 set	2,500.00 /set	2,500.00

Estimated Charges ₱ 18,670.00

Location/s:	HR Office		Area:	14.00	sqm.
--------------------	-----------	--	--------------	-------	------

ACU #:	6	Unit Model:	KSM-IW20-WCT10M1M32	Unit Capacity/Type:	2.0HP Wall Mounted Inverter
---------------	---	--------------------	---------------------	----------------------------	-----------------------------

Estimated Pipe Length = 25 ft

Estimated Royal Cord Length = 30 ft

Initial Charge ₱ 8,500.00

10ft Copper tube
10ft Royal Cord
Outdoor bracket Wall/Floor
Consumables
Testing and Commissioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	15 ft	₱ 350.00 /ft	₱ 5,250.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	20 ft	100.00 /ft	2,000.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	7 ft	60.00 /ft	420.00
Circuit Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
Outdoor Unit Bracket Type	Fabricated floor	1 set	2,500.00 /set	2,500.00

Estimated Charges ₱ 19,670.00

Location/s:		Audit Office		Area:	8.74	sqm.
ACU #:	7	Unit Model:	KAG-100WCINV /		Unit Capacity/Type:	1.0Hp Window Type Inverter
Initial Charge						₱ 1,200.00
Installation Materials		Specification		Qty	Price per qty	Subtotal
WAC Angle Bracket				1 set	600.00 /set	600.00
Estimated Charges						₱ 1,800.00

Location/s:		PID		Area:	40.00	sqm.
ACU #:	8A	Unit Model:	KSM-IW20-WCT10M1M32 /		Unit Capacity/Type:	2.0HP Wall Mounted Inverter
Estimated Pipe Length = 30 ft						
Estimated Royal Cord Length = 35 ft						
Initial Charge						₱ 8,500.00
10ft Copper tube						
10ft Royal Cord						
Outdoor bracket Wall/Floor						
Consumables						
Testing and Commisioning						
Installation Materials		Specification		Qty	Price per qty	Subtotal
Insulated Copper tube		1/2"Ø x 1/4"Ø		20 ft	₱ 350.00 /ft	₱ 7,000.00
Royal Cord (Comm wire)		2.0 sq.mm x 4c		25 ft	100.00 /ft	2,500.00
Royal Cord (Power Supply)		(#12) 3.5 sqmm. x 3c		7 ft	60.00 /ft	420.00
Circuir Breaker Weather Proof		30Amps / 1Ph		1 pc	1,000.00 /pc	1,000.00
Outdoor Unit Bracket Type		Fabricated floor		1 set	2,500.00 /set	2,500.00
Estimated Charges						₱ 21,920.00

ACU #:	8B	Unit Model:	KSM-IW25-WCT10M1M32	Unit Capacity/Type:	2.5HP Wall Mounted Inverter
--------	----	-------------	---------------------	---------------------	-----------------------------

Estimated Pipe Length = 30 ft

Estimated Royal Cord Length = 35 ft

Initial Charge ₱ 8,500.00

10ft Copper tube
10ft Royal Cord
Outdoor bracket Wall/Floor
Consumables
Testing and Commisioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	20 ft	₱ 350.00 /ft	₱ 7,000.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	25 ft	100.00 /ft	2,500.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	7 ft	60.00 /ft	420.00
Circuit Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
Outdoor Unit Bracket Type	Fabricated floor	1 set	2,500.00 /set	2,500.00
Estimated Charges				₱ 21,920.00

Location/s:	TCSG 1	Area:	27.00 sqm.
-------------	--------	-------	------------

ACU #:	9	Unit Model:	KSG-IWF-30WFF8K1M32	Unit Capacity/Type:	3.0HP Wall Mounted Inverter
--------	---	-------------	---------------------	---------------------	-----------------------------

Estimated Pipe Length = 30 ft

Estimated Royal Cord Length = 35 ft

Initial Charge ₱ 8,500.00

10ft Copper tube
10ft Royal Cord
Outdoor bracket Wall/Floor
Consumables
Testing and Commisioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	5/8"Ø x 1/4"Ø	20 ft	₱ 400.00 /ft	₱ 8,000.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	25 ft	100.00 /ft	2,500.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	7 ft	60.00 /ft	420.00
Circuit Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
Outdoor Unit Bracket Type	Fabricated floor	1 set	2,500.00 /set	2,500.00
Estimated Charges				₱ 22,920.00

Location/s:	TCSG 2		Area:	12.80	sqm.
ACU #:	10	Unit Model:	KAG-100WCINV /	Unit Capacity/Type:	1.0Hp Window Type Inverter
Initial Charge					₱ 1,200.00
Installation Materials		Specification	Qty	Price per qty	Subtotal
WAC Angle Bracket			1 set	600.00 /set	600.00
Estimated Charges					₱ 1,800.00

Location/s:	SERVICE INSIDE		Area:	19.85	sqm.
ACU #:	11	Unit Model:	KAG-200WCINV /	Unit Capacity/Type:	2.0HP Window Type Inverter
Initial Charge					₱ 1,200.00
Installation Materials		Specification	Qty	Price per qty	Subtotal
WAC Angle Bracket			1 set	600.00 /set	600.00
Estimated Charges					₱ 1,800.00

Location/s:	SERVICE OUTSIDE		Area:	14.70	sqm.
ACU #:	12	Unit Model:	KAG-200WCINV /	Unit Capacity/Type:	2.0HP Window Type Inverter
Initial Charge					₱ 1,200.00
Installation Materials		Specification	Qty	Price per qty	Subtotal
WAC Angle Bracket			1 set	600.00 /set	600.00
Estimated Charges					₱ 1,800.00

Total Estimated Charges					₱ 161,110.00
--------------------------------	--	--	--	--	--------------

Note:

1. Location of indoor and outdoor unit were agreed by costumer and kolin's surveyor .
2. Masonry and carpentry (plastering and finishing or retouch) are not included in the installation.
3. Electrical power supply (feeder line) not included in scope of work of KOLIN/RKH Aircon.
4. Not Included Mobilization (If Night Work)
5. Final charges will be based on actual installation.

ENGR.MICHAEL MAPA

Prepared by :