



September 10, 2025

GUEVARRA'S METRO EAST
(INFRONT OF) ROBINSON'S METRO EAST, MARCOS HI-WAY, PASIG CITY
TEL#: 0919-0987598

Dear Ma'am/Sir,

Kolin Marketing Inc., is extremely honored for your endorsement of Kolin brand and we are please to offer you with a special price/s for the following items.

A. EQUIPMENT & INSTALLATION - **OPTION 2**

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
8	UNIT/S	MODEL: KL-IF60-G6H1M32 KOLIN FLOOR MOUNTED AIRCONDITIONER 58,140 Kj/h (5.0TR) FULL DC INVERTER R32 SINGLE PHASE	165,995.00	112,156.20	PHP	897,249.60
2	UNIT/S	MODEL: KLG-IF40-5G1M32 KOLIN FLOOR MOUNTED AIRCONDITIONER 37,980 Kj/h (3.0TR) FULL DC INVERTER R-32 SINGLE PHASE	113,195.00	79,028.20	PHP	158,056.40
2	UNIT/S	MODEL: KSG-IWF-30WYF-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 29,500 Kj/h (3.0HP) FULL DC INVERTER W/ WIFI R-32	76,595.00	51,212.20	PHP	102,424.40
4	UNIT/S	MODEL: KSM-IW25-WCT10M1M32 KOLIN WALL MOUNTED CERTUS AIRCONDITIONER 23,210 Kj/h (2.5HP) REGULAR INVERTER W/ WIFI R-32	49,995.00	33,996.20	PHP	135,984.80
TOTAL UNIT COST					PHP	1,293,715.20
ESTIMATED COST OF INSTALLATION (please see attached)					PHP	805,800.00
TOTAL ESTIMATED COST OF THE PROJECT					PHP	2,099,515.20

TERMS OF PAYMENT:

FULL PAYMENT OF UNIT AND DELIVERY CHARGE. IF CHECK, SUBJECT FOR 3 DAYS CLEARING.

WARRANTY:

FOR FLOOR MOUNTED (Inverter): ONE (1) YEAR FREE PARTS AND LABOR, FIVE (5) YEARS WARRANTY ON COMPRESSOR.

FOR SPLIT TYPE : ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB , TEN (10) YEARS WARRANTY ON COMPRESSOR.

NOTES: PRICES ARE SUBJECT TO CHANGE WITHOUT PRIOR NOTICE.

PRICES IS VAT INCLUSIVE.

** Cost of Installation is Package with the Unit(s), this cost cannot avail separately (cost will be based on actual works).

*** You may settle first payment for unit/s & delivery. Installation payment can be settled directly to installer after actual works.

We thank you for giving opportunity to offer our product and services, hoping we receive your purchase order.

If you need assistance, don't hesitate to call the under signed at 0917-807-8607 or email at kmi_asst@kolinphil.com.ph

Very Truly Yours,

JANELLEN S. LIM
KMI-ASSISTANT

Noted by:
MART NATHANIEL R. FLORES
KMI-SUPERVISOR

Approved By:

MS. EDITHA M. FLORES
AVP - FINANCE

KMI-QUOTE-09-25-0679
REG-24%/14K/7K/4K

Conforme:

SIGNATURE OVER PRINTED NAME

Kolin Marketing, Inc.

1854 Sta. Rita St., Guadalupe Nuevo, Makati City

Tel.: (632) 8852-6473

Fax: (632) 8852-2170 / (632) 8852-4792

www.kolinphil.com.ph / kolinphilippines

SEPTEMBER 09, 2025
 ROBINSON METROEAST
 Robinson Metro East, Marcos Hiway, Brgy Marikina Infanta Highway Pasig City
 0919-0987598

MODEL	Qty
KL-IF60-G6H1M32	8
KLG-IF40-5G1M32	2
KSG-IWF-30Wfy8K1M32	2
KSG-IWF-25Wfy8K1M32	4

GROUND FLOOR

Location	Area	318 sqm
----------	------	---------

ACU 1	7.0 HP Floor Standing Inverter	KL-IF60-G6H1M32
	Estimated Pipe Length = 86 ft	
	Estimated Royal Cord Length = 93 ft	
	Initial Charge	₱ 14,000.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Indoor Bracket (Floor)

Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 3/8" x Ø 5/8"	76 ft	₱ 400.00/ft	₱ 30,400.00
Royal Cord (comm. wire)	2.mm2 x 4C	83 ft	₱ 100.00/ft	₱ 8,300.00
Royal Cord (ACCU-Breaker)	5.5mm x 3c	5 ft	₱ 70.00/ft	₱ 350.00
Circuit Breaker waterproof	60A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	12 pc/s	₱ 350.00/pc	₱ 4,200.00
Full thread	3/8" x 10'	2 pc/s	₱ 150.00/pc	₱ 300.00
Metal Clamp	3"	16 pc/s	₱ 120.00/pc	₱ 1,920.00
Outdoor bracket	Fabricated wall	1 pc/s	₱ 5,000.00/pc	₱ 5,000.00
PVC blue	3/4" x 10'	3 pc/s	₱ 150.00/pc	₱ 450.00
				₱ 51,920.00

Estimated Charges	₱ 65,920.00
-------------------	-------------

ACU 2	7.0 HP Floor Standing Inverter	KL-IF60-G6H1M32
	Estimated Pipe Length = 50 ft	
	Estimated Royal Cord Length = 57 ft	
	Initial Charge	₱ 14,000.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Indoor Bracket (Floor)

Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 3/8" x Ø 5/8"	40 ft	₱ 400.00/ft	₱ 16,000.00
Royal Cord (comm. wire)	2.mm2 x 4C	47 ft	₱ 100.00/ft	₱ 4,700.00
Royal Cord (ACCU-Breaker)	5.5mm x 3c	7 ft	₱ 70.00/ft	₱ 490.00
Circuit Breaker waterproof	60A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	7 pc/s	₱ 350.00/pc	₱ 2,450.00
Full thread	3/8" x 10'	2 pc/s	₱ 150.00/pc	₱ 300.00
Metal Clamp	3"	11 pc/s	₱ 120.00/pc	₱ 1,320.00
Outdoor bracket	Fabricated wall	1 pc/s	₱ 5,000.00/pc	₱ 5,000.00
PVC blue	3/4" x 10'	3 pc/s	₱ 150.00/pc	₱ 450.00
				₱ 31,710.00

Estimated Charges	₱ 45,710.00
-------------------	-------------

ACU 3	7.0 HP Floor Standing Inverter	KL-IF60-G6H1M32
-------	--------------------------------	-----------------

Estimated Pipe Length = 73 ft

Estimated Royal Cord Length = 80 ft

Initial Charge

₱ 14,000.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Indoor Bracket (Floor)

Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 3/8" x Ø 5/8"	63 ft	₱ 400.00/ft	₱ 25,200.00
Royal Cord (comm. wire)	2.mm2 x 4C	70 ft	₱ 100.00/ft	₱ 7,000.00
Royal Cord (ACCU-Breaker)	5.5mm x 3c	7 ft	₱ 70.00/ft	₱ 490.00
Circuit Breaker waterproof	60A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	11 pc/s	₱ 350.00/pc	₱ 3,850.00
Full thread	3/8" x 10'	2 pc/s	₱ 150.00/pc	₱ 300.00
Metal Clamp	3"	15 pc/s	₱ 120.00/pc	₱ 1,800.00
Outdoor bracket	Fabricated wall	1 pc/s	₱ 5,000.00/pc	₱ 5,000.00
PVC blue	3/4" x 10'	3 pc/s	₱ 150.00/pc	₱ 450.00
				₱ 45,090.00

Estimated Charges

₱ 59,090.00

ACU 4 7.0 HP Floor Standing Inverter

KL-IF60-G6H1M32

Estimated Pipe Length = 96 ft

Estimated Royal Cord Length = 103 ft

Initial Charge

₱ 14,000.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Indoor Bracket (Floor)

Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 3/8" x Ø 5/8"	86 ft	₱ 400.00/ft	₱ 34,400.00
Royal Cord (comm. wire)	2.mm2 x 4C	93 ft	₱ 100.00/ft	₱ 9,300.00
Royal Cord (ACCU-Breaker)	5.5mm x 3c	7 ft	₱ 70.00/ft	₱ 490.00
Circuit Breaker waterproof	60A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	14 pc/s	₱ 350.00/pc	₱ 4,900.00
Full thread	3/8" x 10'	2 pc/s	₱ 150.00/pc	₱ 300.00
Metal Clamp	3"	18 pc/s	₱ 120.00/pc	₱ 2,160.00
Outdoor bracket	Fabricated wall	1 pc/s	₱ 5,000.00/pc	₱ 5,000.00
PVC blue	3/4" x 10'	3 pc/s	₱ 150.00/pc	₱ 450.00
				₱ 58,000.00

Estimated Charges

₱ 72,000.00

ACU 5 7.0 HP Floor Standing Inverter**KL-IF60-G6H1M32**

Estimated Pipe Length = 69 ft

Estimated Royal Cord Length = 76 ft

Initial Charge

₱ 14,000.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Indoor Bracket (Floor)

Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 3/8" x Ø 5/8"	59 ft	₱ 400.00/ft	₱ 23,600.00
Royal Cord (comm. wire)	2.mm2 x 4C	66 ft	₱ 100.00/ft	₱ 6,600.00
Royal Cord (ACCU-Breaker)	5.5mm x 3c	7 ft	₱ 70.00/ft	₱ 490.00
Circuit Breaker waterproof	60A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	10 pc/s	₱ 350.00/pc	₱ 3,500.00
Full thread	3/8" x 10'	2 pc/s	₱ 150.00/pc	₱ 300.00
Metal Clamp	3"	14 pc/s	₱ 120.00/pc	₱ 1,680.00
Outdoor bracket	Fabricated wall	1 pc/s	₱ 5,000.00/pc	₱ 5,000.00
PVC blue	3/4" x 10'	3 pc/s	₱ 150.00/pc	₱ 450.00
				₱ 42,620.00

Estimated Charges

₱ 56,620.00

ACU 6 7.0 HP Floor Standing Inverter**KL-IF60-G6H1M32**

Estimated Pipe Length = 69 ft

Estimated Royal Cord Length = 76 ft

Initial Charge

₱ 14,000.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Indoor Bracket (Floor)

Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 3/8" x Ø 5/8"	59 ft	₱ 400.00/ft	₱ 23,600.00
Royal Cord (comm. wire)	2.mm2 x 4C	66 ft	₱ 100.00/ft	₱ 6,600.00
Royal Cord (ACCU-Breaker)	5.5mm x 3c	7 ft	₱ 70.00/ft	₱ 490.00
Circuit Breaker waterproof	60A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	10 pc/s	₱ 350.00/pc	₱ 3,500.00
Full thread	3/8" x 10'	2 pc/s	₱ 150.00/pc	₱ 300.00
Metal Clamp	3"	14 pc/s	₱ 120.00/pc	₱ 1,680.00
Outdoor bracket	Fabricated wall	1 pc/s	₱ 5,000.00/pc	₱ 5,000.00
PVC blue	3/4" x 10'	3 pc/s	₱ 150.00/pc	₱ 450.00
				₱ 42,620.00

Estimated Charges

₱ 56,620.00

ACU 7 7.0 HP Floor Standing Inverter**KL-IF60-G6H1M32**

Estimated Pipe Length = 37 ft
Estimated Royal Cord Length = 44 ft

Initial Charge

₱ 14,000.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Indoor Bracket (Floor)

Consumables

Installation Materials

	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 3/8" x Ø 5/8"	27 ft	₱ 400.00/ft	₱ 10,800.00
Royal Cord (comm. wire)	2.mm2 x 4C	34 ft	₱ 100.00/ft	₱ 3,400.00
Royal Cord (ACCU-Breaker)	5.5mm x 3c	7 ft	₱ 70.00/ft	₱ 490.00
Circuit Breaker waterproof	60A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	5 pc/s	₱ 350.00/pc	₱ 1,750.00
Full thread	3/8" x 10'	2 pc/s	₱ 150.00/pc	₱ 300.00
Metal Clamp	3"	9 pc/s	₱ 120.00/pc	₱ 1,080.00
Outdoor bracket	Fabricated wall	1 pc/s	₱ 5,000.00/pc	₱ 5,000.00
PVC blue	3/4" x 10'	3 pc/s	₱ 150.00/pc	₱ 450.00
				₱ 24,270.00

Estimated Charges**₱ 38,270.00****ACU 8 7.0 HP Floor Standing Inverter****KL-IF60-G6H1M32**

Estimated Pipe Length = 53 ft
Estimated Royal Cord Length = 60 ft

Initial Charge

₱ 14,000.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Indoor Bracket (Floor)

Consumables

Installation Materials

	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 3/8" x Ø 5/8"	43 ft	₱ 400.00/ft	₱ 17,200.00
Royal Cord (comm. wire)	2.mm2 x 4C	50 ft	₱ 100.00/ft	₱ 5,000.00
Royal Cord (ACCU-Breaker)	5.5mm x 3c	7 ft	₱ 70.00/ft	₱ 490.00
Circuit Breaker waterproof	60A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	7 pc/s	₱ 350.00/pc	₱ 2,450.00
Full thread	3/8" x 10'	2 pc/s	₱ 150.00/pc	₱ 300.00
Metal Clamp	3"	11 pc/s	₱ 120.00/pc	₱ 1,320.00
Outdoor bracket	Fabricated wall	1 pc/s	₱ 5,000.00/pc	₱ 5,000.00
PVC blue	3/4" x 10'	3 pc/s	₱ 150.00/pc	₱ 450.00
				₱ 33,210.00

Estimated Charges**₱ 47,210.00**

2ND FLOOR**DINING A**

Area 70 sqm

ACU 9 4.0 HP Floor Standing Inverter**KLG-IF40-5G1M32**

Estimated Pipe Length = 82 ft

Estimated Royal Cord Length = 89 ft

Initial Charge

₱ 11,000.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Indoor Bracket (Floor)

Consumables

Installation Materials

Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 3/8" x Ø 5/8"	72 ft ₱ 400.00/ft	₱ 28,800.00
Royal Cord (comm. wire)	2.mm2 x 4C	79 ft ₱ 100.00/ft	₱ 7,900.00
Royal Cord (ACCU-Breaker)	5.5mm x 3c	7 ft ₱ 70.00/ft	₱ 490.00
Circuit Breaker waterproof	40A / 1Ph	1 pc/s ₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	12 pc/s ₱ 350.00/pc	₱ 4,200.00
Full thread	3/8" x 10'	2 pc/s ₱ 150.00/pc	₱ 300.00
Metal Clamp	3"	16 pc/s ₱ 120.00/pc	₱ 1,920.00
Outdoor bracket	Fabricated wall	1 pc/s ₱ 5,000.00/pc	₱ 5,000.00
PVC blue	3/4" x 10'	3 pc/s ₱ 150.00/pc	₱ 450.00
			₱ 50,060.00

Estimated Charges

₱ 61,060.00

ACU 10 4.0 HP Floor Standing Inverter**KLG-IF40-5G1M32**

Estimated Pipe Length = 43 ft

Estimated Royal Cord Length = 50 ft

Initial Charge

₱ 11,000.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Indoor Bracket (Floor)

Consumables

Installation Materials

Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 3/8" x Ø 5/8"	33 ft ₱ 400.00/ft	₱ 13,200.00
Royal Cord (comm. wire)	2.mm2 x 4C	40 ft ₱ 100.00/ft	₱ 4,000.00
Royal Cord (ACCU-Breaker)	5.5mm x 3c	7 ft ₱ 70.00/ft	₱ 490.00
Circuit Breaker waterproof	40A / 1Ph	1 pc/s ₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	6 pc/s ₱ 350.00/pc	₱ 2,100.00
Full thread	3/8" x 10'	2 pc/s ₱ 150.00/pc	₱ 300.00
Metal Clamp	3"	10 pc/s ₱ 120.00/pc	₱ 1,200.00
Outdoor bracket	Fabricated wall	1 pc/s ₱ 5,000.00/pc	₱ 5,000.00
PVC blue	3/4" x 10'	3 pc/s ₱ 150.00/pc	₱ 450.00
			₱ 27,740.00

Estimated Charges

₱ 38,740.00

DINING B	Area	44 sqm
-----------------	------	--------

ACU 11 2.5 HP Wall Mounted Inverter *KSG-IWF-25Wfy8K1M32*

Estimated Pipe Length = 60 ft

Estimated Royal Cord Length = 65 ft

Initial Charge ₱ 8,500.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Outdoor Bracket (Wall)

Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 5/8"	50 ft	₱ 400.00/ft	₱ 20,000.00
Royal Cord (comm. wire)	2.mm2 x 4C	55 ft	₱ 100.00/ft	₱ 5,500.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	₱ 60.00/ft	₱ 300.00
Circuit Breaker waterproof	30A/1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	8 pc/s	₱ 350.00/pc	₱ 2,800.00
Full thread	3/8" x 10'	2 pc/s	₱ 150.00/pc	₱ 300.00
Metal Clamp	3"	12 pc/s	₱ 120.00/pc	₱ 1,440.00
PVC blue	3/4" x 10'	3 pc/s	₱ 150.00/pc	₱ 450.00
				₱ 31,790.00

Estimated Charges	₱ 40,290.00
--------------------------	--------------------

ACU 12 2.5 HP Wall Mounted Inverter *KSG-IWF-25Wfy8K1M32*

Estimated Pipe Length = 65 ft

Estimated Royal Cord Length = 70 ft

Initial Charge ₱ 8,500.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Outdoor Bracket (Wall)

Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 5/8"	55 ft	₱ 400.00/ft	₱ 22,000.00
Royal Cord (comm. wire)	2.mm2 x 4C	60 ft	₱ 100.00/ft	₱ 6,000.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	₱ 60.00/ft	₱ 300.00
Circuit Breaker waterproof	30A/1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	8 pc/s	₱ 350.00/pc	₱ 2,800.00
Full thread	3/8" x 10'	2 pc/s	₱ 150.00/pc	₱ 300.00
Metal Clamp	3"	12 pc/s	₱ 120.00/pc	₱ 1,440.00
PVC blue	3/4" x 10'	3 pc/s	₱ 150.00/pc	₱ 450.00
				₱ 34,290.00

Estimated Charges	₱ 42,790.00
--------------------------	--------------------

DINING C

Area 47 sqm

ACU 13 3.0 HP Wall Mounted Inverter**KSG-IWF-30Wfy8K1M32**

Estimated Pipe Length = 60 ft

Estimated Royal Cord Length = 65 ft

Initial Charge

₱ 8,500.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Outdoor Bracket (Wall)

Consumables

Installation Materials

Description	Qty	Price per qty	Subtotal
Copper Tube	50 ft	₱ 400.00/ft	₱ 20,000.00
Royal Cord (comm. wire)	55 ft	₱ 100.00/ft	₱ 5,500.00
Royal Cord (ACCU-Breaker)	5 ft	₱ 60.00/ft	₱ 300.00
Circuit Breaker waterproof	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	8 pc/s	₱ 350.00/pc	₱ 2,800.00
Full thread	2 pc/s	₱ 150.00/pc	₱ 300.00
Metal Clamp	12 pc/s	₱ 120.00/pc	₱ 1,440.00
PVC blue	3 pc/s	₱ 150.00/pc	₱ 450.00
			₱ 31,790.00

Estimated Charges

₱ 40,290.00

ACU 14 3.0 HP Wall Mounted Inverter**KSG-IWF-30Wfy8K1M32**

Estimated Pipe Length = 76 ft

Estimated Royal Cord Length = 81 ft

Initial Charge

₱ 8,500.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Outdoor Bracket (Wall)

Consumables

Installation Materials

Description	Qty	Price per qty	Subtotal
Copper Tube	66 ft	₱ 400.00/ft	₱ 26,400.00
Royal Cord (comm. wire)	71 ft	₱ 100.00/ft	₱ 7,100.00
Royal Cord (ACCU-Breaker)	5 ft	₱ 60.00/ft	₱ 300.00
Circuit Breaker waterproof	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	10 pc/s	₱ 350.00/pc	₱ 3,500.00
Full thread	2 pc/s	₱ 150.00/pc	₱ 300.00
Metal Clamp	14 pc/s	₱ 120.00/pc	₱ 1,680.00
PVC blue	3 pc/s	₱ 150.00/pc	₱ 450.00
			₱ 40,730.00

Estimated Charges

₱ 49,230.00

DINING D

Area 40 sqm

ACU 15 2.5 HP Wall Mounted Inverter**KSG-IWF-25Wfy8K1M32**

Estimated Pipe Length = 66 ft

Estimated Royal Cord Length = 71 ft

Initial Charge

₱ 8,500.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Outdoor Bracket (Wall)

Consumables

Installation Materials

Description	Qty	Price per qty	Subtotal
Copper Tube	56 ft	₱ 400.00/ft	₱ 22,400.00
Royal Cord (comm. wire)	61 ft	₱ 100.00/ft	₱ 6,100.00
Royal Cord (ACCU-Breaker)	5 ft	₱ 60.00/ft	₱ 300.00
Circuit Breaker waterproof	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	10 pc/s	₱ 350.00/pc	₱ 3,500.00
Full thread	2 pc/s	₱ 150.00/pc	₱ 300.00
Metal Clamp	14 pc/s	₱ 120.00/pc	₱ 1,680.00
PVC blue	3 pc/s	₱ 150.00/pc	₱ 450.00
			₱ 35,730.00

Estimated Charges

₱ 44,230.00

ACU 16 2.5 HP Wall Mounted Inverter**KSG-IWF-25Wfy8K1M32**

Estimated Pipe Length = 73 ft

Estimated Royal Cord Length = 78 ft

Initial Charge

₱ 8,500.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Outdoor Bracket (Wall)

Consumables

Installation Materials

Description	Qty	Price per qty	Subtotal
Copper Tube	63 ft	₱ 400.00/ft	₱ 25,200.00
Royal Cord (comm. wire)	68 ft	₱ 100.00/ft	₱ 6,800.00
Royal Cord (ACCU-Breaker)	5 ft	₱ 60.00/ft	₱ 300.00
Circuit Breaker waterproof	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	10 pc/s	₱ 350.00/pc	₱ 3,500.00
Full thread	2 pc/s	₱ 150.00/pc	₱ 300.00
Metal Clamp	14 pc/s	₱ 120.00/pc	₱ 1,680.00
PVC blue	3 pc/s	₱ 150.00/pc	₱ 450.00
			₱ 39,230.00

Estimated Charges


₱ 47,730.00

Validity: This quotation is valid for a period of fifteen (15) days from the date thereof, subject to our confirmation thereafter.

Installation notes:

- 1 Location based in floor plan only.
- 2 AC drain line will be tapped to the nearest drain provision provided by the customer's contractor.
- 3 Need for marking and site visit before installation.
- 4 Coppertube expose inside the area.
- 5 Working days: Monday to Saturday, 8am- 5pm with parking. Need working permit.
- 6 Mechanical Plans, Permits, Electrical permits not included.
- 7 Deflectors, masonry, carpentry, chipping & plastering (finishing & restoration) are not included in the installation.
- 8 Air conditioning drain line and Electrical power supply (feeder line) **220v/ 60hz/ 1ph** , should be provided by customer's contractor.
- 9 **Final charges will be based on actual installation.**


Prepared by:


Jeffrey Dadios
Field Surveyor

Customer Conformer:

Signature Over Printed Name

Reviewed by:


Engr. Kenneth Zamora
Service Supervisor Shop and
Field Operation

