

BY: AFFILIATED ELECTRONICS SERVICE CORP.
VAT REG. TIN: 000-050-365-000
#18 Evangelista St.
Santolan, Pasig City

PROPOSAL

Work Order No:

Date: 7/22/24

Attention: Ma'am Jaylyn Machon

Department: ASERCO

Company: Affiliated Electronics Service Corp.
Address: #18 Evangelista St. Santolan, Pasig City

Project Title: MIGUEL BARETTO

Location: Unit 26P West Tower Arton By Rockwell Katipunan Quezon City

Surveyor: Joshua Sabalza / Bryan Capistrano

Dear Sir/Ma'am:

We are pleased to present you our best offer for your consideration and approval, subject to the terms and conditions contained herein:

INVERTER TYPE

| No. | Location | Description | | Unit of Measurement | Cost | Total Cost |
|-----|--|---|--------------------|------------------------|-------------------|-------------------|
| 1 | MASTERS BEDROOM 12.90 sqm (10,276 KJ/HR) | Installation of 1.5HP Multi-Split Type (1st 10ft.) with Existing Pipe Copper Requirement: 3/8 x 1/4 Indoor Size: 820x215x285 (WxDxH) Outdoor Size: 940x330x998 (HxWxD) Wire Provision: 6 Wires Outdoor Supply | 1 | unit | ₱6,500.00 | ₱6,500.00 |
| | | Flushing with Leak Testing | 1 | lot | ₱ 1,500.00 | ₱1,500.00 |
| | | Sub-To | ₱8,000.00 | | | |
| 2 | BEDROOM 1 9.0 sqm (6,470 KJ/HR) | Installation of 1.0HP Multi-Split Type (1st 10ft.) with Existing Pipe Copper Requirement: 3/8 x 1/4 Indoor Size: 820x215x285 (WxDxH) Outdoor Size: 940x330x998 (HxWxD) Wire Provision: 6 Wires Outdoor Supply | 1 | unit | ₱6,500.00 | ₱6,500.00 |
| | (0,470 13/1111) | Flushing with Leak Testing | 1 | lot | ₱ 1,500.00 | ₱ 1,500.00 |
| | | Special Fabricated Double Deck Bracket | 1 | lot | ₽ 2,500.00 | ₽ 2,500.00 |
| | | Sub-To | ₱10,500.00 | | | |
| 3 | LIVING/DINING/KITCHEN 28.50 sqm (19,850 KJ/HR) | Installation of 2.5HP Wall Mounted Split Type (1st 10ft.) with Existing Pipe Copper Requirement: 5/8 x 1/4 Indoor Size: 1065x230x298 (WxDxH) Outdoor Size: 800x300x600 (HxWxD) Wire Provision: 6 Wires Outdoor Supply | 1 | unit | ₱6,500.00 | ₱6,500.00 |
| | | Flushing with Leak Testing | 1 | lot | ₱ 1,500.00 | ₱ 1,500.00 |
| | | Special Fabricated Double Deck Bracket | 1 | lot | ₽ 2,500.00 | ₽ 2,500.00 |
| | | Sub-To | ₱ 10,500.00 | | | |
| | | | | GRAND T | OTAL AMOUNT: | ₱29.000.00 |

| GRAND TOTAL AMOUNT: | | | | | | | | | | | ₱29,000.00 |
|---------------------|------|-----|-------------|--------|--------|---------|--------------|----------------|----------------------|--------------------------|---------------------------|
| WEST Unit | Туре | Qty | Room Served | FCU-TR | FCU-HP | ACCU-TR | TYPE | GAS LINE (in.) | LIQUID LINE (in.) | DIMENSION (WxDxH) FCU | DIMENSION (HxWxD) ACCU |
| Р | 2BR | .1 | MBR | 1 | 1.5 | 2.8 | Multi-Split | 3/8 | 1/4 | 820 x 215 x 285 | 940 x 330 x 998 |
| | | ٦ 1 | BR1 | 0.6 | 1 | | | 3/8 | 1/4 | 820 x 215 x 285 | |
| | | 1 | LDK | 1.7 | 2 | 1.7 | Single Split | 5/8 | 1/4 | 1065 x 230 x 298 | 800 x 300 x 600 |

NOTE: We will use the copper and electrical provision of the condo unit. Also, the customer will provide the restoration work of wooden door/access for the outdoor location. In addition, the customer must sign the NOUF for the 3" ceiling clearance of the indoor unit since the drain line provision was too high and we need to follow the drain provision.

Terms and Conditions:

Remarks: Items on order basis are not cancellable.

Admin cost shall apply for the cancelled P.O

Please confirm to us your purchase by signing the conforme portion below for our stocks ordering.

Payment: 70% down payment prior on the first day of installation and 30% upon completion.

Cash / Check payment payable to (ENTHALPY REFRIGERATION AND AIRCONDITIONING SERVICES)

Price Validity: Pricing/Costing is VAT inclusive and valid for 30 days upon receipt of signed quotation.

Warranty: One (1) year from the date of unit start-up.

Note:

Installation inclusion and scope of works:

Mounting/Installation of FCU and ACCU to designated and approved location.

Supply and lay-out of new refrigerant copper piping with rubber insulation. Supply and lay-out of communication control wire with electrical pipe conduit.

Supply and installation of consumable materials such as nuts, clamps, bolts, tapes, drain pipes to complete

installation works.

Flushing and Leak testing of entire unit using nitrogen gas.

Vacuuming of entire system using vacuum pump to free the system from moisture and air.

Charging of freon if needed, test run, observation and commissioning of unit.

Mobilization and demobilization.

Start-up checklist documentation of unit to be submitted to supplier for warranty purposes.

Installation Exclusion:

Restoration of civil works and painting of walls, carpentry and masonry works not included.

Glass cutting are not included. Provision of tapping point of drain.

Architectural, civil works, necessary government permits and licenses

Electrical works (power supply)

Should you have any questions, please contact the undersigned at (0949) 771 6557 (0950) 627 0369 or email us at enthalpyrefcon.27@yahoo.com / enthalpy.refcon27a@yahoo.com

Thank you and we hope to receive your valued order soon.

Prepared by: Noted by:

Meriam C. Ursal

Admin Staff Head

Client/Company Name

Conforme:

Authorized Signature over Printed Name)

Date