



September 2, 2025

MR. & MS. JG / TRINA SIMON
52 WASHINGTON ST., MERVILLE PARK, BRGY. MERVILLE PARAÑAQUE CITY
TEL#: 0967-1185333

Dear Ma'am/Sir,

Kolin Marketing Inc., is extremely honored for your endorsement of Kolin brand and we are please to offer you with a special price/s for the following items.

A. EQUIPMENT & INSTALLATION

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
4	UNIT/S	MODEL: KSM-IW25-WCT10M1M32 KOLIN WALL MOUNTED CERTUS AIRCONDITIONER 23,210 Kj/h (2.5HP) REGULAR INVERTER W/ WIFI R-32	49,995.00	33,996.20	PHP	135,984.80
1	UNIT/S	MODEL: KSM-IW20-WCT10M1M32 KOLIN WALL MOUNTED CERTUS SERIES AIRCONDITIONER 18,990 Kj/h (2.0HP) REGULAR INVERTER W/ WIFI R-32	41,995.00	27,916.20	PHP	27,916.20
1	UNIT/S	MODEL: KSM-IW15-WCT10M1M32 KOLIN WALL MOUNTED CERTUS SERIES AIRCONDITIONER 12,660 Kj/h (1.5HP) REGULAR INVERTER W/ WIFI R-32	32,995.00	21,076.20	PHP	21,076.20
TOTAL UNIT COST					PHP	184,977.20
ESTIMATED COST OF INSTALLATION (please see attached)					PHP	106,429.20
OTHERS: DELIVERY CHARGE					PHP	600.00
TOTAL ESTIMATED COST OF THE PROJECT					PHP	292,006.40

TERMS OF PAYMENT:

FULL PAYMENT OF UNIT AND DELIVERY CHARGE. IF CHECK, SUBJECT FOR 3 DAYS CLEARING.

WARRANTY:

FOR SPLIT TYPE : ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB , TEN (10) YEARS WARRANTY ON COMPRESSOR.

NOTES: *** Need to sign waiver agreement due to under capacity of unit choice.

PRICES ARE SUBJECT TO CHANGE WITHOUT PRIOR NOTICE.

PRICES IS VAT INCLUSIVE.

**** Cost of Installation is Package with the Unit(s), this cost cannot avail separately (cost will be based on actual works).**

***** You may settle first payment for unit/s & delivery. Installation payment can be settled directly to installer after actual works.**

We thank you for giving opportunity to offer our product and services, hoping we receive your purchase order.

If you need assistance, don't hesitate to call the under signed at 0917-807-8607 or email at kmi_asst@kolinphil.com.ph

Very Truly Yours,

JANELLEN S. LIM
KMI-ASSISTANT

Noted by:
MART NATHANIEL R. FLORES
KMI-SUPERVISOR

Approved By:
MS. EDITHA M. FLORES
AVP - FINANCE

KMI-QUOTE-08-25-0598-rev
ADR-24%/4K

Conforme:

SIGNATURE OVER PRINTED NAME

Kolin Marketing, Inc.

1854 Sta. Rita St., Guadalupe Nuevo, Makati City

Tel.: (632) 8852-6473

Fax: (632) 8852-2170 / (632) 8852-4792

www.kolinphil.com.ph / kolinphilippines





Airconditioning & Refrigeration Services
B72 L22 17th., Brgy. 183 Villamor Pasay city Metro Manila 1300
Cellphone: 0917-1225048/ 0999-5573715
Email: zeusrafann053012@gmail.com / carcillaroffice01@gmail.com

*SUPPLY

*INSTALLATION

*CHECK-UP

*CLEANING

*PREVENTIVE MAINTENANCE

Installation Quotation

Simon, JG / Trina
52 Washington St., Merville Park, Brgy. Merville, PARAÑAQUE CITY
0967-1185333

August 29, 2025
AIQ 25-00035

Project name: Option 4: Installation of Kolin Aircon Certus

Description		QTY			
ACU 1 (Master's Bedroom)		2.5HP Certus	1		
Estimated Pipe Length	=	23ft			
Estimated Royal Cord Length	=	28ft			
Basic Installation (10ft copper tubing and communication wire)					8,500.00
Installation materials		Description	QTY	Price Per QTY	SubTotal
Copper Tubing (excess of 10ft)		1/4"X5/8" new	13ft	400/ft	5,200.00
Royal Cord (excess of 10ft)		2.00mm2X4C	18ft	100/ft	1,800.00
Wire (Royal Cord-Breaker to ODU)		3.5mmX3C	4ft	60/ft	240.00
PVC Blue Pipe		Blue pipe 3/4"	2pcs	200/pc	400.00
Circuit Breaker		60 Amp. (NEMA 3RE-Single-Phase)	1pc	1000/pc	1,000.00
TOTAL					8,640.00
					17,140.00
ACU 2 (Guest Room)		1.5HP Certus	1		
Estimated Pipe Length	=	11ft			
Estimated Royal Cord Length	=	16ft			
Basic Installation (10ft copper tubing and communication wire)					7,500.00
Installation materials		Description	QTY	Price Per QTY	SubTotal
Copper Tubing (excess of 10ft)		1/4"X1/2" new	1ft	350/ft	350.00
Royal Cord (excess of 10ft)		2.00mm2X4C	6ft	100/ft	600.00
Wire (Royal Cord-Breaker to ODU)		3.5mmX3C	4ft	60/ft	240.00
PVC Blue Pipe		Blue pipe 3/4"	1pc	200/pc	200.00
Circuit Breaker		60 Amp. (NEMA 3RE-Single-Phase)	1pc	1000/pc	1,000.00
TOTAL					2,390.00
					9,890.00
ACU 3 (Bedroom 3)		2.5HP Certus	1		
Estimated Pipe Length	=	21ft			
Estimated Royal Cord Length	=	26ft			
Basic Installation (10ft copper tubing and communication wire)					8,500.00
Installation materials		Description	QTY	Price Per QTY	SubTotal
Copper Tubing (excess of 10ft)		1/4"X5/8" new	11ft	400/ft	4,400.00
Royal Cord (excess of 10ft)		2.00mm2X4C	16ft	100/ft	1,600.00
Wire (Royal Cord-Breaker to ODU)		3.5mmX3C	4ft	60/ft	240.00
PVC Blue Pipe		Blue pipe 3/4"	2pcs	200/pc	400.00
Circuit Breaker		60 Amp. (NEMA 3RE-Single-Phase)	1pc	1000/pc	1,000.00
TOTAL					7,640.00
					16,140.00
ACU 4 (Family Room)		2HP Certus	1		
Estimated Pipe Length	=	35ft			
Estimated Royal Cord Length	=	40ft			
Basic Installation (10ft copper tubing and communication wire)					7,500.00
Installation materials		Description	QTY	Price Per QTY	SubTotal
Copper Tubing (excess of 10ft)		1/4"X1/2" new	25ft	350/ft	8,750.00
Royal Cord (excess of 10ft)		2.00mm2X4C	31ft	100/ft	3,100.00
Wire (Royal Cord-Breaker to ODU)		5.5mm x 3	4	60/ft	240.00
PVC Blue Pipe		Blue pipe 3/4"	2pc	200/pc	400.00
Circuit Breaker		60 Amp. (NEMA 3RE-Single-Phase)	1pc	1000/pc	1,000.00
TOTAL					13,490.00
					20,990.00
ACU 5 (Dining Room)		2.5HP Certus	2		
Unit 1					
Estimated Pipe Length	=	39ft			
Estimated Royal Cord Length	=	44ft			
Basic Installation (10ft copper tubing and communication wire)					8,500.00
Installation materials		Description	QTY	Price Per QTY	SubTotal
Copper Tubing (excess of 10ft)		1/4"X5/8" new	29ft	400/ft	11,600.00
Royal Cord (excess of 10ft)		2.00mm2X4C	34ft	100/ft	3,400.00
Wire (Royal Cord-Breaker to ODU)		5.5mm x 3	4	60/ft	240.00
PVC Blue Pipe		Blue pipe 3/4"	2pcs	200/pc	400.00
Circuit Breaker		60 Amp. (NEMA 3RE-Single-Phase)	1pc	1000/pc	1,000.00

16,640.00

TOTAL

25,140.00

Unit 2

Estimated Pipe Length = 39ft
Estimated Royal Cord Length = 44ft

Basic Installation (10ft copper tubing and communication wire)

8,500.00

Installation materials	Description	QTY	Price Per QTY	SubTotal
Copper Tubing (excess of 10ft)	1/4"X5/8" new	29ft	400/ft	11,600.00
Royal Cord (excess of 10ft)	2.00mm2X4C	34ft	100/ft	3,400.00
Wire (Royal Cord-Breaker to ODU)	5.5mm x 3	4	60/ft	240.00
PVC Blue Pipe	Blue pipe 3/4"	2pcs	200/pc	400.00
Circuit Breaker	60 Amp. (NEMA 3RE-Single-Phase)	1pc	1000/pc	1,000.00

16,640.00

TOTAL

25,140.00

SubTotal

114,440.00

Discount (7%)

8,010.80

Total Charges

106,429.20

Bank details

China Bank Corporation

Account Name: Carcellar Airconditioning and Refrigeration Services
143602005343

GCASH

0999-5573715
Rafael Carcellar

Prepared by:

Melissa de Castro
Office Admin

Conformed by:



Airconditioning & Refrigeration Services

B72 L22 17th., Brgy. 183 Villamor Pasay city Metro Manila 1300

Cellphone: 0917-1225048/ 0999-5573715

Email: zeusrafann053012@gmail.com / carcillarooffice01@gmail.com

*SUPPLY

*INSTALLATION

*CHECK-UP

*CLEANING

*PREVENTIVE MAINTENANCE

Customer Name : Simon, JG/ Trina

Date: August 29, 2025

Customer Address : 52 Washington St., Merville Park, Brgy. Merville, PARAÑAQUE CITY

Please be informed that the air-conditioner you intend to purchase is under capacity as compared to the following unit that we proposed:

Location	Area	Recommendation	Customer's Choice	Remarks
Master's Bedroom	36 sqm	3HP Wall Mounted Primus	2.5HP Wall Mounted Certus	Computed capacity 2.7HP, undersize by .5HP
Bedroom 3	36 sqm	3HP Wall Mounted Primus	2.5HP Wall Mounted Certus	Computed capacity 2.9HP, undersize by .4HP
Guest Room	18.5 sqm	2HP Wall Mounted Primus	1.5HP Wall Mounted Certus	Computed capacity 1.6HP, undersize by .1HP
Family Room	24 sqm	2HP Wall Mounted Primus	1.5HP Wall Mounted Certus	Computed capacity 2HP, undersize by 0.0HP

Since the unit of your choice is under capacity, it is probable that you may experience the following;

1. Capacity of the unit to cool the area will take longer or it will not cool the area at all that may lead to your dissatisfaction with the cooling performance of our unit.
2. Power consumption will be higher due to frequent running of compressor for not reaching the desired temperature within the normal parameter.
3. Useful life of compressor will be shortened due to excessive running beyond the normal run cycle.

Considering the conditions stated above, we regret to inform you that the efficient performance of the unit cannot be guaranteed. Furthermore, the warranty coverage shall be as follows:

Labor Warranty 1 (one) year
PCB Parts Warranty 3 year(s)
Compressor warranty 10 year(s)

For your guidance and information

Prepared by:
Melissa de Castro

Signature over Printed Name

Customer Conforme:

Signature over Printed Name



Airconditioning & Refrigeration Services

B72 L22 17th., Brgy. 183 Villamor Pasay city Metro Manila 1300

Cellphone: 0917-1225048/ 0999-5573715

Email: zeusrafann053012@gmail.com / carcillaroffice01@gmail.com

*SUPPLY

*INSTALLATION

*CHECK-UP

*CLEANING

*PREVENTIVE MAINTENANCE

Customer Name : Simon, JG/ Trina

Date: August 29, 2025

Customer Address : 52 Washington St., Merville Park, Brgy. Merville, PARAÑAQUE CITY

Please be informed that the air-conditioner you intend to purchase is under capacity as compared to the following unit that we proposed:

Location	Area	Recommendation	Customer's Choice	Remarks
Dining Room	70 sqm	1 unit 6.OHP Floor Mounted and 1 unit 2.OHP Wall Mounted	2 Wall Mounted Split Type 2.5HP	Computed capacity 7.9 HP, undersize by 2.9HP

Since the unit of your choice is under capacity, it is probable that you may experience the following;

1. Capacity of the unit to cool the area will take longer or it will not cool the area at all that may lead to your dissatisfaction with the cooling performance of our unit.
2. Power consumption will be higher due to frequent running of compressor for not reaching the desired temperature within the normal parameter.
3. Useful life of compressor will be shortened due to excessive running beyond the normal run cycle.

Considering the conditions stated above, we regret to inform you that the efficient performance of the unit cannot be guaranteed. Furthermore, the warranty coverage shall be as follows:

Labor Warranty	1 (one) year
PCB Parts Warranty	<u>3</u> year(s)
Compressor warranty	<u>Void</u> year(s)

For your guidance and information

Prepared by:

Melissa de Castro

Signature over Printed Name

Customer Conforme:

Signature over Printed Name