

JRA JERRICO

Refrigeration and Air-conditioning Services

B4, 19 Felixvill, Mangahan, Stg. Niño Bilibiran, Binangonan Rizal

Email: jraairconditioning@gmail.com

Contact Nos. 09267189004/09615215615

Attn:Ma'am Mildred Uy
Uy Residences RSG.Compound Sitio Bayucan
Drive Brgy.Sampaloc Tanay Rizal
09178361790

Date: July 16,2025

Brand Kolin
FCU 1
2.5HP Wall Mounted
Event Area
Total pipe Length = 42 ft.
Estimated Royal Cord = 47 ft.
Installations charge ₱ 8,500.00

Includes:

Labor

10 ft.copper tube

10ft.Royal Cord

Consumables

Installations Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	5/8 x 1/4	32 ft.	400.00/ft	12,800.00
Royal cord (com. wire)	2mm x 4c	37 ft.	100.00/ft.	3,700.00
Royal cord (ACCU-BREAKER)	3.5mm x 3c	5ft.	60.00/ft	300.00
Pvc Blue	3/4 x 10	6pcs.	150.00/pc	900.00
Drain hose White	1/2	7ft.	25/ft.	175.00

₱ 17,875.00

Estimated CHARGES

₱ 26,375.00

FCU2
2.5HP Wall Mounted
Event Area
Total pipe Length = 40 ft.
Estimated Royal Cord = 45ft.
Installations charge ₱ 8,500.00

Includes:

Labor

10 ft.copper tube

10ft.Royal Cord

Consumables

Installations Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	5/8 x 1/4	30 ft.	400.00/ft	12,000.00
Royal cord (com. wire)	2mm x 4c	35 ft.	100.00/ft.	3,500.00
Royal cord (ACCU-BREAKER)	3.5mm x 3c	5ft.	60.00/ft	300.00
Pvc Blue	3/4 x 10	6pcs.	150.00/pc	900.00
Drain hose White	1/2	7ft.	25/ft.	175.00

₱ 16,875.00

Estimated CHARGES

₱ 25,375.00

FCU3

3.0TR

Event Area

Area 81sqm.

Total pipe Length = 53 ft.

Estimated Royal Cord = 58 ft.

Installations charge

₱ 11,000.00

Includes:

Labor

10 ft.copper tube

10ft.Royal Cord

Consumables

Installations Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	5/8 x 3/8	43 ft.	400.00/ft	17,200.00
Royal cord (com. wire)	2mm x 4c	48ft.	100.00/ft.	4,800.00
Royal cord (ACCU-BREAKER)	3.5mm x 3c	5ft.	60.00/ft	300.00
Pvc Blue	3/4 x 10	6pcs.	150.00/pc	900.00
Drain hose White	1/2	7ft.	25/ft.	175.00

₱ 28,375.00

Estimated CHARGES

₱ 39,375.00

Gym Area

2.0HP Wall Mounted

Event Area

Area 19sqm.

Total pipe Length = 10 ft.

Estimated Royal Cord = 15 ft.

Installations charge

₱ 7,500.00

Includes:

Labor

10 ft.copper tube

10ft.Royal Cord

Consumables

Installations Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	1/2 x 1/4	10 ft.		
Royal cord (com. wire)	2mm x 4c	5ft.	100.00/ft.	500.00
Royal cord (ACCU-BREAKER)	3.5mm x 3c	5ft.	60.00/ft	300.00
Pvc Blue	3/4 x 10	1pcs.	150.00/pc	150.00
Drain hose White	1/2	7ft.	25/ft.	175.00

₱ 1,125.00

Estimated CHARGES

₱ 8,625.00

OFFICE ROOM
1.5HP Wall Mounted

Event Area

Area 16sqm.

Total pipe Length = 10 ft.

Estimated Royal Cord = 15 ft.

Installations charge

₱ 7,500.00

Includes:

Labor

10 ft.copper tube

10ft.Royal Cord

Consumables

Installations Materials

Copper Tube

Royal cord (com. wire)

Royal cord (ACCU-BREAKER)

Pvc Blue

Drain hose White

Description

Qty

Price per qty

Subtotal

5/8 x 1/4

10 ft.

2mm x 4c

5 ft.

100.00/ft.

500.00

3.5mm x 3c

5ft.

60.00/ft

300.00

3/4 x 10

6pcs.

150.00/pc

150.00

1/2

7ft.

25/ft.

175.00

₱ 1,125.00

Estimated Charges

₱ 8,625.00

TOTAL ESTIMATED CHARGE

₱ 108,375.00

Circuit Breaker weatherproof 5pcs(1000/pcs) 5x1000 = 5,000.00

1.a.2.5hp (30amps) 2 units

2.b. 3TR 9 40amps) 1 unit

3.c. 2.0hp (30amps) 1 unit

4.d.1.5hp (20amps) 1 unit

Estimated Total Charge

₱ 113,375.00

(Less Discount of 10% on Actual Total) = ₱ 113,375.00 x 10% = 11,337.50

₱ 113,375 - 11,337 = 102,038.00

Total Charge

₱ 102,038.00

Installation note:

- 1..Mechanical Plans ,Permits,Electrical permit not included.
- 2.Deflector,Masonry,carpentry,chipping & plastering ,finishing & restoration are not included in the installation
- 3.Air conditioning drain line and electrical power supply should be provided by the customer's contractor.

Installation Warranty

One (1) Yr warranty for Parts & service
10yrs warranty for compressor

Mode of Payment

Cash or Bank Transfer after installation

For installation payment method

Cash or Bank Transfer

Bank Details: Metro Bank

Account name: Jerico R. De vera

Account #: 3453345441418

Prepare by
Monaliza A. Pepito

Jerico R. De Vera
Owner

CONFORME

Signature Over Printed Name

Date:_____