
OCTOBER 24, 2023 PHILIP SECOSANA

Unit 15C Forbeswood Heights Tower 1 Rizal Drive, Brgy Fort Bonifacio Taguig City 0917-3063703

MODEL Qty

KSG-IWF-20WFY8K1M32 1 KSG-IWF-10WFY8K1M32 1

| LIVING | ,DINING,KITCHEN | | | | Area | 18.5 sqm |
|--------|-------------------------------------|--------------------|---------------------|--------------|------------|-------------|
| ACU 1 | 2.0 HP Wall Mounted Inverter | | KSG-IWF-20WFY8K1M32 | | | |
| | Estimated Pipe Length = | 23 ft | | | | |
| | Estimated Royal Cord Length = | 28 ft | | | | |
| | Initial Charge | | | | | ₱ 7,500.00 |
| | Includes: | | | | | |
| | Labor | | | | | |
| | 10ft Copper Tube | | | | | |
| | 10ft Royal Cord | | | | | |
| | Outdoor Bracket (FLOOR) Consumables | | | | | |
| | Installation Materials | Description | Qty Pr | ice per qty | Subtotal | |
| | Copper Tube | Ø 1/4" x Ø 1/2" | 13 ft ₱ | 350.00/ft | ₱ 4,550.00 | |
| | Royal Cord (comm. wire) | 2.mm2 x 4C | 18 ft ₱ | 100.00/ft | ₱ 1,800.00 | |
| | Royal Cord (ACCU-Breaker) | 3.5mm x 3c | 5 ft ₱ | 60.00/ft | ₱ 300.00 | |
| | Circuit Breaker waterproof | 30A / 1Ph | 1 pc/s ₱ | 1,000.00/pc | ₱ 1,000.00 | |
| | Dismantle . | 1.5HP Wall Mounted | 1 set ₱ | 2,500.00/set | ₱ 2,500.00 | |
| | PVC blue | 3/4" x 10' | 2 pc/s ₱ | 150.00/pc | ₱ 300.00 | ₱ 10,450.00 |
| | | | • | • | | |
| | Estimated Charges | | | | | ₱ 17,950.00 |
| BEDRO | OOM | | | | Area | 8 sqm |
| ACU 1 | 1.0 HP Wall Mounted Inverter | | KSG-IWF-1 | 10WFY8K1M32 | | |
| | Estimated Pipe Length = | 27 ft | | | | |
| | Estimated Royal Cord Length = | 32 ft | | | | |
| | Initial Charge | | | | | ₱ 7,500.00 |
| | Includes: | | | | | |
| | Labor | | | | | |
| | 10ft Copper Tube | | | | | |
| | 10ft Royal Cord | | | | | |
| | Outdoor Bracket (FLOOR) Consumables | | | | | |
| | Installation Materials | Description | Qtv Pr | ice per qty | Subtotal | |
| | Copper Tube | Ø 1/4" x Ø 3/8" | 17 ft ₱ | 350.00/ft | ₱ 5,950.00 | |
| | Royal Cord (comm. wire) | 2.mm2 x 4C | 22 ft ₱ | 100.00/ft | ₱ 2,200.00 | |
| | Royal Cord (ACCU-Breaker) | 3.5mm x 3c | 5 ft ₱ | 60.00/ft | ₱ 300.00 | |
| | Circuit Breaker waterproof | 20A/ 1PH | 1 pc/s ₱ | 1,000.00/pc | ₱ 1,000.00 | |
| | Dismantle | 1.0HP Wall Mounted | 1 set ₱ | 2,500.00/set | ₱ 2,500.00 | |
| | PVC blue | 3/4" x 10' | 2 pc/s ₱ | 150.00/pc | ₱ 300.00 | ₱ 12,250.00 |
| | Estimated Charges | | | | | ₱ 19,750.0 |
| | | | | | | |



Total Estimated Charges

₱ 37,700.00

Validity: This quotation is valid for a period of fifteen (15) days from the date thereof, subject to our confirmation thereafter.

Installation notes:

- 1 Location of indoor and outdoor units were agreed by the customer and Kolin's surveyor.
- 2 AC drain line will be tapped to the nearest drain provision provided by the customer's contractor.
- 3 Need for Site visit for the renovation or repair of wall to fit the indoor units. Should have atleast 40-45cm from the ceiling for indoor unit.10cm offset from the top of unit to ceiling.
- 3 Coppertube and drainline expose inside the area.
- 4 Working days: Monday to Saturday, 8am- 5pm with parking. Need working permit. 4 pax
- 5 Mechanical Plans, Permits, Electrical permits not included.
- 6 Deflectors, masonry, carpentry, chipping & plastering (finishing & restoration) are not included in the installation.
- 7 Air conditioning drain line and Electrical power supply (feeder line) 220v/ 60hz/ 1ph, should be provided by customer's contractor.
- 8 Final charges will be based on actual installation.

| Prepared by: | Customer Conformee: | | |
|-----------------|-----------------------------|--|--|
| Com and | | | |
| Jeoffrey Dadios | | | |
| Field Surveyor | Signature Over Printed Name | | |
| Field Surveyor | Signature Over Printed Name | | |

Engr Kenneth Zamora
Service Supervisor Shop and
Field Operation

Reviewed by: