

GODSPEED

REFRIGERATION AND AIRCONDITIONING SERVICES

QUOTATION

July 4 2024

JIMMY MIRANDA

Blk. 2 a Lot 36 Phase 3-a Torres st. Colinas verdes res. SFDM Bulacan

Tel. no 090917-5055422

Subject: Installation of Airconditioning Units

Dear Sir/Madam;

Please refer to the above mentioned subject.

bedroom 1.0 hp ground floor

Installation:

Basic Installation	7,500.00
(10ft. Refrigerant pipe)	
Excess (6.56ft.)	2,296.00
royal cord excess (6.56ft.)	656.00
Breaker nema 3R	1,000.00
embedded drain pipe 2M	700.00

12,152.00

Master's bedroom 2.0 hp / 2nd floor

Installation:

Basic Installation	7,500.00
(10ft. Refrigerant pipe)	
Excess (22.96ft.)	8,036.00
royal cord excess (22.96ft.)	2,296.00
Breaker nema 3R	1,000.00
embedded drain pipe 2M	700.00
	4

19,532.00

bedroom 2 1.0 hp / 2nd floor

Installation:

Basic Installation	7,500.00	
(10ft. Refrigerant pipe)		
Excess (3.28ft.)	1,148.00	
royal cord excess (3.28ft.)	328.00	
Breaker nema 3R	1,000.00	
embedded drain pipe 2M	700.00	

10,676.00

Girls room 1.0 hp / 2nd floor

Installation:

Basic Installation	7,500.00	
(10ft. Refrigerant pipe)		
Excess (9.84ft.)	3,444.00	
royal cord excess (9.84ft.)	984.00	
Breaker nema 3R	1,000.00	
embedded drain pipe 2M	700.00	

13,628.00

Total cost of installation 4 units

optional 4 units special bracket with catwalk

55,988.00 8,000.00

NOTATION

Mounting/Installation of FCU and ACCU to designated and approved location.

lay-out of new refrigerant copper piping with rubber insulation.

lay-out of communication control wire with electrical pipe conduit.

installation of consumable materials such as nuts, clamps, bolts, tapes, drain pipes to complete installation works.

Flushing and Leak testing of entire unit using nitrogen gas.

Vacuuming of entire system using vacuum pump to free the system from moisture and a Charging of freon if needed, test run, observation and commissioning of unit.

Mobilization and demobilization.

Power supply provided by customer

Start-up checklist documentation of unit to be submitted to supplier for warranty purposes.

Mode of Payment:

* 50% - Down payment * 50% - Upon Completion

Conforme: Prepared By:

A.

Owner/Representative Bonnevie Chan Ruiz

Coordinator

Blk. 1 Lot 17-I Avante Homes, Bagumbong Rd., Bagumbong Caloocan City email: godspeed_777@gmail.com Tel: 8289-6559 / 8441-0349 Mobile No.: 0917-1756903

