



ESTINOR AIRCONDITIONING SERVICES

8 C. Jose Extension St., Brgy. 144 Malibay, Pasay City

☎ 7-621-7179; 8-800-1401 / 📠 0917-316-8463; 0925-651-7664

✉ estinor.airconditioning.services@gmail.com

VAT Reg. TIN: 231-613-080-000

No. QF2026-035

LIM GALO JR.

Unit 852 Tower A Shore 1 Residences Brgy. 76,
Pasay City

January 30, 2026

Contact No.:
Email:

Dear Sir/Madam,

This is a quotation on the units/materials/services named, subject to conditions noted below.

A. INSTALLATION COST

Area: Bedroom

(1)Unit/Model: Kolin - Wall Mounted - 2.0 HP (15 FT)

ITEM NO.	DESCRIPTION	QTY	COST	AMOUNT (PHP)
1	Initial Charge (1st 10ft. Copper Tube - .028mm, rubber insulation 1/2 thickness, communication wire, PVC drain, standard bracket)	lot	7,500.00	7,500.00
2	Excess Copper Tube	5 FT	350.00/FT	1,750.00
3	Royal Cord (comm. Wire)	10 FT	100.00/FT	1,000.00
4	Royal Cord (ACCU-Breaker)	7 FT	60.00/FT	420.00
5	Dismantle	lot	2,500.00	2,500.00
SUB TOTAL				PHP 13,170.00

TOTAL AMOUNT (VAT INCLUSIVE)	PHP	13,170.00
LESS DISCOUNT 5%	PHP	(658.50)
TOTAL AMOUNT (VAT INCLUSIVE)	PHP	12,511.50

NOTE: RESTORATION SHOULDERED BY THE CUSTOMER

B. MODE OF PAYMENT:

* **CASH** or

* Cheque payable to: *** **ESTINOR AIRCONDITIONING SERVICES** ***

C. FOR INSTALLATION

* 50% downpayment and 50% progress billing

D. MANUFACTURER'S WARRANTY

* One (1) year free parts & labor (except plastic parts, accessories and remote control)

* Ten (10) years for the compressor (wall mounted)

* Three (3) years on all PCB (wall mounted)

* Five (5) years for the compressor (Flexmatch Inverter III & Versa Match Series)

* Three (3) years for the compressor (Floor Mounted Regular)

* Five (5) years for the compressor (Floor Mounted, Ceiling Suspended & Ceiling Cassette Inverter)

* Three (3) months for the installation

E. SCOPE OF WORK

- * Installation of FCU and ACCU unit
- * Copper piping with insulation
- * Electrical and Communication wires
- * Circuit breakers with NEMA 3R rating
- * Bracketing support
- * Drain line installation
- * Leak Testing and flushing of system
- * Vacuuming and commissioning
- * Technical Supervision

F. EXCLUSIONS

- * Procurement of Permits and other Licenses (if required)
- * Installation of feeder line (main panel to unit) and electrical supply
- * Provision of drainage
- * Dismantling of old units, wall chipping and plastering (see NOTES)
- * Restoration

NOTES:

- * Recommended unit capacity **MUST** be strictly complied.
- * Signer(s) under conforme hereby agree(s) to undertake risks should installation of undersized/inappropriate units be conducted as opposed to the recommendation made by aircon surveyor/technician.
A signed waiver form is necessary.
- * Clear and concise discussion of the indoor/outdoor unit's location, along with the piping route (if applicable), is hereby approved by the customer and the below signer(s).
- * Estimated charges declared herein **IS NOT** absolute and may vary on the actual installation or completion of service.
- * Additional work to be performed, as stated under "Exclusions", if **ESTINOR AIRCONDITIONING SERVICES** agrees to conduct, shall incur additional charges.
- * **Terms of Payment - A 50% downpayment is REQUIRED** prior to commencing the work.
The remaining 50% **MUST** be settled upon completion, else the authorized technician/installer **IS HEREBY ORDERED** that the corresponding unit's remote control be **WITHHELD**.
- * **Service Invoice** is to be issued as VAT inclusive

Respectfully yours,



Eduardo D. Estinor

Proprietor

CONFORME:

Customer Name & Signature

THANK YOU FOR YOUR BUSINESS!

REVIEWED BY:



01/30/2026
ENGR. ADRIAN NOGOY
PROJECT ENGINEER-KPII