

TO : KOLIN AUTHORIZED SERVICE CENTERS
FROM : KOLIN HEAD OFFICE
SUBJECT : STANDARD INSTALLATION CHARGES
DATE : AUGUST 27, 2021
REF. NO. : SVC-000-2021-08-028
CC : DCO / BOO / SERVICE / SVC ACCTG / OP / KMI / SALES

Greetings!

In line with the company's objective to standardize Kolin installation charges, KPII shall require all ASC to adhere the following:

Effectivity: September 01, 2021

- | | |
|--|-----------|
| 1. Window type (mounting only) | P1,000.00 |
| 2. Wall Mounted Split Type (Non-inverter & Inverter) | |
| 1.0HP – 2.0HP | P7,500.00 |
| 2.5HP – 3.0HP | P8,500.00 |

Free 10 ft. Copper tube (minimum thickness: 0.028")

Inclusion:

Labor
10 ft. Royal cord 2.0mm2 x 4C (communication wire)
Rubber Insulation (insulation materials)
Circuit breaker (weatherproof)
Ordinary outdoor unit bracket
Drain hose / PVC drain pipe ¾"
Consumable materials like aerotape, electrical tape, polyethylene tape, PVC elbow, PVC clamp, metal screw, log screw, etc.
Flushing, vacuum and leak test of AC system
Testing and commissioning

Additional charge to customer:

Copper tube in excess of 10 ft.	
1.0hp – 2.0hp	P350.00 / ft.
2.5hp – 3.0hp	P400.00 / ft.
Royal cord in excess of 10 ft.	P 50.00 / ft.
Electrical wire for power supply	
Electrical supply from main panel to ACCU breaker	
Dismantling of existing unit	
Chipping and restoration works	

Installation rebate

P3,000.00 / unit

*includes 10ft. copper tube



3. Package Type and Multi-Split Type Aircon (Non-inverter & Inverter)

Flex Match Inverter (1 st pair)	P 7,500.00
• Succeeding indoor unit	P 2,000.00 / unit
3.0TR Floor Mounted	P11,000.00
5.0TR Floor Mounted	P14,000.00
3.0TR Ceiling Suspended / Cassette	P12,000.00
5.0TR Ceiling Suspended / Cassette	P15,000.00

Inclusion:

10 ft. Copper tube (minimum thickness: 0.028")
10 ft. Royal cord 2.0mm² x 4C (communication wire)
Labor
Rubber insulation (insulation materials)
Circuit breaker (weatherproof)
Ordinary indoor unit bracket
Drain hose / PVC drain pipe
Consumable materials like aerotape, electrical tape, polyethylene tape, PVC elbow, PVC clamp, metal screw, log screw, etc.
Flushing, vacuum and leak test of AC system
Testing and commissioning

Additional charge to customer:

Copper tube in excess of 10 ft.	
3.0 TR	P400.00 / ft.
5.0 TR	P600.00 / ft.
Royal cord in excess of 10 ft.	P 50.00 / ft.
Outdoor unit bracket	
Electrical wire for power supply	
Electrical supply from main panel to ACCU breaker	
Dismantling of existing unit	
Chipping and restoration works	

Note: Communication wire shall use royal cord only. Do not use THHN wire.

For strict compliance

Prepared by:

Mr. Alvin C. De Rivera
Service Assistant Manager

Approved by:

Mr. Oliver M. Filoteo
Executive Vice President