

9-Mar-17

**ATTN: Mr. Billy Dela Fuente**L-1 B-3 A Chesnut cor. Carnation Phase 2  
Executive Village, Pinagbuhatan Pasig City  
Contact#: 0917-334-1861

Sir,

Please find below the quotation of Air-conditioner as per survey results.


MODEL	DESCRIPTION	QTY	UNIT PRICE	DISCOUNTED PRICE	TOTAL
KSM-10MB1INV	1.0HP WALL MOUNTED INVERTER AC	2	29,525.00	24,210.50	48,421.00
KSM-15MB1INV	1.5HP WALL MOUNTED INVERTER AC	1	33,215.00	27,236.30	27,236.30
Add: Estimated installation charge:					
	Kid's Room 1 (KSM-10MB1INV)			7,345.00	
	Kid's Room 2 (KSM-10MB1INV)			7,495.00	
	Master Bedroom (KSM-15MB1INV)			8,535.00	23,375.00
Others: Delivey Charge					500.00
<b><u>TOTAL ESTIMATED COST OF THE PROJECT</u></b>					<b><u>99,532.30</u></b>

*Note: Prices are subject to change without prior notice.**Price is VAT Inclusive****Terms: Payment before delivery. If check subject for 3 days clearing***

We thank you for giving us the opportunity to offer our product and services, hoping that we receive your purchase order.

If you need assistance don't hesitate to call the under signed at 852-6473.

Very truly yours,

**MART NATHANIEL R. FLORES**  
Assistant Supervisor

Approved by:

**OLIVER M. FILOTEO**  
VP-FinanceKMI-QUOTE-03-17-130  
18%-DCGConforme: \_\_\_\_\_  
SIGNATURE OVER PRINTED NAME

March 3, 2017

DELA FUENTE, BILLY  
L-1 B-3 A CHESNUT COR CARNATION PHASE 2  
GREENWOODS EXECUTIVE VILLAGE, PINAGBUHATAN PASIG CITY  
0917-3341861

MODEL	QUANTITY
KSM-IW10-4FIM / <i>KSM-10VBIINV</i>	2
KSM-IW15-4FIM / <i>KSM-15VBIINV</i>	1

<b>KIDS' ROOM</b>	Area ≈ 14.8sq.m
-------------------	-----------------

ACU1	IHP WALL MOUNTED INVERTER	KSM-IW10-4FIM
	Estimated Pipe Length : 14 ft	
	Estimated Royal Cord Length : 19 ft	
	Initial Charge	P 6,000.00
	Includes:	
	10ft Copper Tube	
	10ft Royal Cord	
	Circuit Breaker (20A)	
	Outdoor Bracket	
	Other Consumables	

Additional Charges	Description	Unit	Price Per Unit	Subtotal
Copper Tube	1/4" , 3/8"	4 ft	P 200 / ft	P 800
Royal Cord	2.mm2 x 4C	9 ft	P 30 / ft	P 270
Royal Cord	3.5mm2 x 3C	5 ft	P 40 / ft	P 200
Drain Hose White		5 ft	P 15 / ft	P 75
				P 1,345

<b>Estimated Charges</b>	P 7,345.00
--------------------------	------------

<b>KIDS' ROOM 2</b>	Area ≈ 11.8sq.m
---------------------	-----------------

ACU2	IHP WALL MOUNTED INVERTER	KSM-IW10-4FIM
	Estimated Pipe Length : 14 ft	
	Estimated Royal Cord Length : 19 ft	
	Initial Charge	P 6,000.00
	Includes:	
	10ft Copper Tube	
	10ft Royal Cord	
	Circuit Breaker (20A)	
	Outdoor Bracket	
	Other Consumables	

Additional Charges	Description	Unit	Price Per Unit	Subtotal
Copper Tube	1/4" , 3/8"	4 ft	P 200 / ft	P 800
Royal Cord	2.mm2 x 4C	9 ft	P 30 / ft	P 270
Royal Cord	3.5mm2 x 3C	5 ft	P 40 / ft	P 200
PVC Pipe (Drain)	3/4"	1 pc	P 150 / pc	P 150
Drain Hose White		5 ft	P 15 / ft	P 75
				P 1,495

<b>Estimated Charges</b>	P 7,495.00
--------------------------	------------



<b>MASTER BEDROOM</b>	Area $\approx$ 19.2sq.m.
-----------------------	--------------------------

ACU3	1.5HP WALL MOUNTED INVERTER	KSM-IW15-4F1M
	Estimated Pipe Length : 17 ft	
	Estimated Royal Cord Length : 22 ft	
	Initial Charge	P 6,000.00

Includes:

10ft Copper Tube  
10ft Royal Cord  
Circuit Breaker (20A)  
Outdoor Bracket

Other Consumables


Additional Charges	Description	Unit	Price Per Unit	Subtotal
Copper Tube	1/4" , 1/2"	7 ft	P 250 / ft	P 1750
Royal Cord	2.mm2 x 4C	12 ft	P 30 / ft	P 360
Royal Cord	3.5mm2 x 3C	5 ft	P 40 / ft	P 200
PVC Pipe (Drain)	3/4"	1 pc	P 150 / pc	P 150
Drain Hose White		5 ft	P 15 / ft	P 75
				P 2535

<b>Estimated Charges</b>	<b>P 8,535.00</b>
--------------------------	-------------------

<b>Total Estimated Charges</b>	<b>P 23,375.00</b>
--------------------------------	--------------------

**Note:**

- 1 Location of indoor and outdoor units were agreed by the customer and Kolin's surveyor.
- 2 AC Drain Lines will be tapped to the nearest drain provision provided by the customer's contractor.
- 3 Mechanical Plans, Permits, Electrical permits not included.
- 4 Masonry, carpentry, chipping & plastering (*finishing & restoration*) are not included in the installation.
- 5 Electrical power supply (*feeder line*) is not included in the scope of work of Kolin.
- 6 Final charges will be based on actual installation.

  
**John Errol Berces**  
Surveyor

  
**Engr. Jayrard Corona**  
Senior Service Engineer

