

Date: 05.29.24

Name: ALABANG MED

Company Name: PAR AIRCONDITIONING SYSTEM SERVICES

Address: ALABANG MUNTINLUPA CITY

Location:

Dear Ma'am/Sir:

We are pleased to present you our best offer for your consideration and approval, subject to the terms and conditions contained herein:

No.	Location	Description	Qty.	Unit of Measurement	Cost	Total Cost
1	BLOOD STATION	INSTALLATION OF 1HP MULTI SPLIT @1ST 10 FEET (INDOOR 1)(3HP OUTDOOR)	1	UNIT	8,500.00	8,500.00
2		EXCESS PIPING	30	FT	350.00	10,500.00
3		COMMUNICATION WIRE	30	FT	100.00	3,000.00
4		CIRCUIT BREAKER	1	UNIT	1,000.00	1,000.00
5	PATHOLOGIST	INSTALLATION OF 1HP MULTI SPLIT (INDOOR 1)(3HP OUTDOOR)	1	UNIT	3,000.00	3,000.00
6		EXCESS PIPING	30	FT	350.00	10,500.00
7		COMMUNICATION WIRE	30	FT	100.00	3,000.00
9	MEDIA PRED ROOM	INSTALLATION OF 1HP MULTI SPLIT (INDOOR 1)(3HP OUTDOOR)	1	UNIT	3,000.00	3,000.00
10		EXCESS PIPING	40	FT	350.00	14,000.00
11		COMMUNICATION WIRE	40	FT	100.00	4,000.00
13	LABORATORY	INSTALLATION OF 3HP SPLIT TYPE @1ST 10 FEET	1	UNIT	5,500.00	5,500.00
14		EXCESS PIPING	50	FT	400.00	20,000.00
15		COMMUNICATION WIRE	50	FT	100.00	5,000.00
16		CIRCUIT BREAKER	1	UNIT	1,000.00	1,000.00
17		(SUREFLOW BRAND) FOR STR DRAIN PUMP AND MATERIAL	1	UNIT	6,000.00	6,000.00
Grand Total for Installation Services:						₱98,000.00

NOTES: *ANY ADDITIONALS DURING OR AFTER INSTALLATION IS SUBJECT FOR NEW QUOTATION.
POWER SUPPLY NOT INCLUDED

Terms and Conditions:

Remarks: Items on order basis are not cancellable.
Admin cost shall apply for the cancelled P.O.
Please confirm to us your purchase by signing the conforme portion below for our stocks ordering.

Payment: 70% down payment prior on the 1st day of installation and 30% upon completion.
Cash / Check payment payable to **PAR AIRCONDITIONING SYSTEM SERVICES**

Price Validity: Pricing/Costing is VAT inclusive and valid for 30 days upon receipt of signed quotation.
Lapse quotation will be subject for re-survey/new quotation.

Warranty: One (1) year from the date of unit start-up.

Installation inclusion and scope of works:

Mounting/Installing of FCU and ACCU to designated and approved location.
Supply and lay-out of new refrigerant copper piping with rubber insulation.
Supply and lay-out of communication control wire with electrical pipe conduit.
Supply and installation of consumable materials such as nuts, clamps, bolts, tapes, drain pipes to complete installation works.
Start-up checklist documentation of unit to be submitted to supplier for warranty purposes.

Installation exclusion:

Restoration of civil works and painting of walls, carpentry and masonry works not included.
Glass cutting are not included.
Provision of tapping point of drain.
Architectural, civil works, necessary government permits and licenses

Electrical works (power supply)

Should you have any questions, please contact the undersigned at
or email us at

Thank you and we hope to receive your valued order soon.

Prepared by:
HARLENE MERCADO
HEAD ADMIN

Noted by:

Admin Staff

Conforme:
Client/Company Name

(Authorized Signature over Printed Name)

Date