

kolin

air conditioner

August 5, 2024

MS. MARIEL ERNESTINE
TEL#: 0917-8399914

Dear Ma'am/Sir,

Kolin Marketing Inc., is extremely honored for your endorsement of Kolin brand and we are please to offer you with a special price/s for the following items.

A. EQUIPMENT & INSTALLATION

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
1	UNIT/S	MODEL: KLM-IC40-AA1M32 KOLIN FLOOR/CEILING AIRCONDITIONER 37,980 Kj/h (3.0TR) DC INVERTER R-32	117,995.00	92,036.10	PHP	92,036.10
1	UNIT/S	MODEL: KSG-IWF-30WFY-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 29,500 Kj/h (3.0HP) FULL DC INVERTER W/ WIFI R-32	76,595.00	55,744.10	PHP	55,744.10
1	UNIT/S	MODEL: KSG-IWF-20WFY-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 19,000 Kj/h (2.0HP) FULL DC INVERTER W/ WIFI R-32	59,595.00	42,484.10	PHP	42,484.10
1	UNIT/S	MODEL: KSG-IWF-15WFY-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 12,960 Kj/h (1.5HP) FULL DC INVERTER W/ WIFI R-32	46,595.00	32,344.10	PHP	32,344.10
5	UNIT/S	MODEL: KSG-IWF-10WFY-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 11,484 Kj/h (1.0HP) FULL DC INVERTER W/ WIFI R-32	42,595.00	29,224.10	PHP	146,120.50
TOTAL UNIT COST						368,728.90
ESTIMATED COST OF INSTALLATION (please see attached)					PHP	276,520.00
OTHERS: DELIVERY CHARGE					PHP	600.00
TOTAL UNIT COST					PHP	645,848.90

TERMS OF PAYMENT:

FULL PAYMENT OF UNIT AND DELIVERY CHARGE. IF CHECK, SUBJECT FOR 3 DAYS CLEARING.

WARRANTY:

FOR FLOOR MOUNTED (Inverter): ONE (1) YEAR FREE PARTS AND LABOR, THREE (3) YEARS WARRANTY ON COMPRESSOR.

FOR SPLIT TYPE : ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB , TEN (10) YEARS WARRANTY ON COMPRESSOR.

NOTES: PRICES ARE SUBJECT TO CHANGE WITHOUT PRIOR NOTICE.


PRICES IS VAT INCLUSIVE.

**** Cost of Installation is Package with the Unit(s), this cost cannot avail separately.**


We thank you for giving opportunity to offer our product and services, hoping we receive your purchase order.

If you need assistance, don't hesitate to call the under signed at 0917-807-8607 or email at kmi_asst@kolinphil.com.ph

Very Truly Yours,


JANELLEN S. LIM
KMI-ASSISTANT

Noted by:


MART NATHANIEL R. FLORES
KMI-SUPERVISOR

Approved By:


MS. EDITHA M. FLORES
AVP - FINANCE

Conforme:

SIGNATURE OVER PRINTED NAME

KMI-QUOTE-08-24-0691
REG-22%/4K

Kolin Marketing, Inc.

1854 Sta. Rita St., Guadalupe Nuevo, Makati City

www.kolinphil.com.ph

Tel.: (632) 8852-6473

Fax: (632) 8852-2170 / (632) 8852-4792

Bringing comfort to your home.

August 2, 2024
Ernestine, Mariel

MODEL	Qty
KLM-IC40-AA1M32	1
KSG-IWF-30Wfy8K1M32	1
KSG-IWF-20Wfy8K1M32	1
KSG-IWF-15Wfy8K1M32	1
KSG-IWF-10Wfy8K1M32	5

ROOM1/ A	Area	0 sqm
----------	------	-------

ACU 1	1.5 HP Wall Mounted Inverter	KSG-IWF-15Wfy8K1M32			
	Estimated Pipe Length = 23 ft				
	Estimated Royal Cord Length = 28 ft				
	Initial Charge				P 4,500.00
	Includes:				
	Labor				
	10ft Copper Tube				
	10ft Royal Cord				
	Outdoor Bracket (Wall)				
	Consumables				
	Installation Materials	Description	Qty	Price per qty	Subtotal
	Copper Tube	Ø 1/4" x Ø 3/8"	13 ft	P 350.00/ft	P 4,550.00
	Royal Cord (comm. wire)	2.mm2 x 4C	18 ft	P 100.00/ft	P 1,800.00
	Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	P 60.00/ft	P 300.00
	Circuit Breaker waterproof	20A / 1Ph	1 pc/s	P 1,000.00/pc	P 1,000.00
	Rubber Insulation	2 1/8" x 3/4" x 6'	2 pc/s	P 350.00/pc	P 700.00
	Full thread	3/8" x 10'	1 pc/s	P 150.00/pc	P 150.00
	Metal Clamp	3"	3 pc/s	P 120.00/pc	P 360.00
	PVC blue	3/4" x 10'	2 pc/s	P 150.00/pc	P 300.00
					P 9,160.00

Estimated Charges	P 13,660.00
-------------------	-------------

ACU 2	2.0 HP Wall Mounted Inverter	KSG-IWF-20Wfy8K1M32			
	Estimated Pipe Length = 27 ft				
	Estimated Royal Cord Length = 32 ft				
	Initial Charge				P 4,500.00
	Includes:				
	Labor				
	10ft Copper Tube				
	10ft Royal Cord				
	Outdoor Bracket (Wall)				
	Consumables				
	Installation Materials	Description	Qty	Price per qty	Subtotal
	Copper Tube	Ø 1/4" x Ø 1/2"	17 ft	P 350.00/ft	P 5,950.00
	Royal Cord (comm. wire)	2.mm2 x 4C	22 ft	P 100.00/ft	P 2,200.00
	Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	P 60.00/ft	P 300.00
	Circuit Breaker waterproof	20A / 1Ph	1 pc/s	P 1,000.00/pc	P 1,000.00
	Rubber Insulation	2 1/8" x 3/4" x 6'	3 pc/s	P 350.00/pc	P 1,050.00
	Full thread	3/8" x 10'	1 pc/s	P 150.00/pc	P 150.00
	Metal Clamp	3"	3 pc/s	P 120.00/pc	P 360.00
	PVC blue	3/4" x 10'	2 pc/s	P 150.00/pc	P 300.00
	Drain pump		1 pc/s	P 2,900.00/pc	P 2,900.00
	Drain pump hose		27 ft	P 10.00/ft	P 270.00
					P 14,480.00

Estimated Charges	P 18,980.00
-------------------	-------------

ACU 3 3.0 HP Wall Mounted Inverter**KSG-IWF-30Wfy8K1M32**

Estimated Pipe Length = 37 ft

Estimated Royal Cord Length = 42 ft

Initial Charge**P 5,500.00****Includes:**

Labor

10ft Copper Tube

10ft Royal Cord

Outdoor Bracket (Wall)

Consumables

Installation Materials

	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 5/8"	27 ft	P 350.00/ft	P 9,450.00
Royal Cord (comm. wire)	2.mm2 x 4C	32 ft	P 100.00/ft	P 3,200.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	P 60.00/ft	P 300.00
Circuit Breaker waterproof	20A / 1Ph	1 pc/s	P 1,000.00/pc	P 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	4 pc/s	P 350.00/pc	P 1,400.00
Full thread	3/8" x 10'	2 pc/s	P 150.00/pc	P 300.00
Metal Clamp	3"	5 pc/s	P 120.00/pc	P 600.00
PVC blue	3/4" x 10'	2 pc/s	P 150.00/pc	P 300.00
Drain pump		1 pc/s	P 2,900.00/pc	P 2,900.00
Drain pump hose		37 ft	P 10.00/ft	P 370.00

P 19,820.00**Estimated Charges****P 25,320.00****ROOM2/B**

Area 0 sqm

ACU 1 1.0 HP Wall Mounted Inverter**KSG-IWF-10Wfy8K1M32**

Estimated Pipe Length = 20 ft

Estimated Royal Cord Length = 25 ft

Initial Charge**P 4,500.00****Includes:**

Labor

10ft Copper Tube

10ft Royal Cord

Outdoor Bracket (Wall)

Consumables

Installation Materials

	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 3/8"	10 ft	P 350.00/ft	P 3,500.00
Royal Cord (comm. wire)	2.mm2 x 4C	15 ft	P 100.00/ft	P 1,500.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	P 60.00/ft	P 300.00
Circuit Breaker waterproof	20A / 1Ph	1 pc/s	P 1,000.00/pc	P 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	2 pc/s	P 350.00/pc	P 700.00
Full thread	3/8" x 10'	1 pc/s	P 150.00/pc	P 150.00
Metal Clamp	3"	3 pc/s	P 120.00/pc	P 360.00
PVC blue	3/4" x 10'	2 pc/s	P 150.00/pc	P 300.00
Drain pump		1 pc/s	P 2,900.00/pc	P 2,900.00
Drain pump hose		20 ft	P 10.00/ft	P 200.00

P 10,910.00**Estimated Charges****P 15,410.00**

ACU 2 4.0 HP Ceiling Suspended Inverter**KLM-IC40-AA1M32**

Estimated Pipe Length = 10 ft

Estimated Royal Cord Length = 17 ft

Initial Charge**P 12,000.00**

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Consumables

Installation Materials

	Description	Qty	Price per qty	Subtotal
Royal Cord (comm. wire)	2.mm2 x 4C	7 ft	P 100.00/ft	P 700.00
Royal Cord (ACCU-Breaker)	5.0mm x 3c	5 ft	P 70.00/ft	P 350.00
Circuit Breaker waterproof	40A/1Ph	1 pc/s	P 1,000.00/pc	P 1,000.00
Indoor bracket	Fab. floor/ceiling	1 pc/s	P 1,500.00/pc	P 1,500.00
Outdoor bracket	Fabricated wall	1 pc/s	P 5,000.00/pc	P 5,000.00
PVC blue	3/4" x 10'	2 pc/s	P 150.00/pc	P 300.00
				P 8,850.00

Estimated Charges**P 20,850.00****ROOM4/ C**

Area 0 sqm

ACU 1 1.0 HP Wall Mounted Inverter**KSG-IWF-10Wfy8K1M32**

Estimated Pipe Length = 128 ft

Estimated Royal Cord Length = 133 ft

Initial Charge**P 4,500.00**

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Outdoor Bracket (Wall)

Consumables

Installation Materials

	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 3/8"	118 ft	P 350.00/ft	P 41,300.00
Royal Cord (comm. wire)	2.mm2 x 4C	123 ft	P 100.00/ft	P 12,300.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	P 60.00/ft	P 300.00
Circuit Breaker waterproof	20A / 1Ph	1 pc/s	P 1,000.00/pc	P 1,000.00
Full thread	3/8" x 10'	9 pc/s	P 150.00/pc	P 1,350.00
Rubber Insulation	2 1/8" x 3/4" x 6'	18 pc/s	P 350.00/pc	P 6,300.00
Metal Clamp	3"	25 pc/s	P 120.00/pc	P 3,000.00
PVC blue	3/4" x 10'	2 pc/s	P 150.00/pc	P 300.00
Drain pump		1 pc/s	P 2,900.00/pc	P 2,900.00
Drain pump hose		128 ft	P 10.00/ft	P 1,280.00
				P 70,030.00

Estimated Charges**P 74,530.00**

ACU 1	1.0 HP Wall Mounted Inverter	KSG-IWF-10WFY8K1M32			
	Estimated Pipe Length = 128 ft				
	Estimated Royal Cord Length = 133 ft				
	Initial Charge	P 4,500.00			
	Includes:				
	Labor				
	10ft Copper Tube				
	10ft Royal Cord				
	Outdoor Bracket (Wall)				
	Consumables				
	Installation Materials	Description	Qty	Price per qty	Subtotal
	Copper Tube	Ø 1/4" x Ø 3/8"	118 ft	P 350.00/ft	P 41,300.00
	Royal Cord (comm. wire)	2.mm2 x 4C	123 ft	P 100.00/ft	P 12,300.00
	Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	P 60.00/ft	P 300.00
	Circuit Breaker waterproof	20A / 1Ph	1 pc/s	P 1,000.00/pc	P 1,000.00
	Rubber Insulation	2 1/8" x 3/4" x 6'	18 pc/s	P 350.00/pc	P 6,300.00
	Metal Clamp	3"	25 pc/s	P 120.00/pc	P 3,000.00
	Full thread	3/8" x 10'	9 pc/s	P 150.00/pc	P 1,350.00
	PVC blue	3/4" x 10'	2 pc/s	P 150.00/pc	P 300.00
	Drain pump		1 pc/s	P 2,900.00/pc	P 2,900.00
	Drain pump hose		128 ft	P 10.00/ft	P 1,280.00
					P 70,030.00
	Estimated Charges	P 74,530.00			

ACU 1	1.0 HP Wall Mounted Inverter	KSG-IWF-10WFY8K1M32			
	Estimated Pipe Length = 17 ft				
	Estimated Royal Cord Length = 22 ft				
	Initial Charge				P 4,500.00
	Includes:				
	Labor				
	10ft Copper Tube				
	10ft Royal Cord				
	Outdoor Bracket (Wall)				
	Consumables				
	Installation Materials	Description	Qty	Price per qty	Subtotal
	Copper Tube	Ø 1/4" x Ø 3/8"	7 ft	P 350.00/ft	P 2,450.00
	Royal Cord (comm. wire)	2.mm2 x 4C	12 ft	P 100.00/ft	P 1,200.00
	Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	P 60.00/ft	P 300.00
	Circuit Breaker waterproof	20A / 1Ph	1 pc/s	P 1,000.00/pc	P 1,000.00
	PVC blue	3/4" x 10'	2 pc/s	P 150.00/pc	P 300.00
					P 5,250.00
	Estimated Charges				P 9,750.00

ROOM7/F	Area	0 sqm
----------------	------	-------

ACU 1 1.0 HP Wall Mounted Inverter
 Estimated Pipe Length = 40 ft
 Estimated Royal Cord Length = 45 ft

KSG-IWF-10Wfy8K1M32

Initial Charge

P 4,500.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Outdoor Bracket (Wall)

Consumables

Installation Materials

Description	Qty	Price per qty	Subtotal
Copper Tube	30 ft	P 350.00/ft	P 10,500.00
Royal Cord (comm. wire)	35 ft	P 100.00/ft	P 3,500.00
Royal Cord (ACCU-Breaker)	5 ft	P 60.00/ft	P 300.00
Circuit Breaker waterproof	20A / 1Ph	1 pc/s P 1,000.00/pc	P 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	6 pc/s P 350.00/pc	P 2,100.00
Full thread	3/8" x 10'	3 pc/s P 150.00/pc	P 450.00
Metal Clamp	3"	7 pc/s P 120.00/pc	P 840.00
PVC blue	3/4" x 10'	2 pc/s P 150.00/pc	P 300.00
			P 18,990.00

Estimated Charges

P 23,490.00

Total Estimated Charges

P 276,520.00

Validity: This quotation is valid for a period of fifteen (15) days from the date thereof, subject to our confirmation thereafter.

Installation notes:

- 1 Location based in mechanical proposal.
- 2 AC drain line will be tapped to the nearest drain provision provided by the customer's contractor.
- 3 Need for site visit, to provide accurate capacity for each room.
- 4 Recommend to relocate the air conditioning unit for ROOM4 and ROOM5 with both 1HP capacity, which exceeds the maximum pipe length of 20 meters. If not, it is probable that you may experience compressor life span will be shorten, high consumption of electricity and low cooling efficiency, considering those conditions the compressor warranty will be VOID.
- 5 Mechanical Plans, Permits, Electrical permits not included.
- 6 Deflectors, masonry, carpentry, chipping & plastering (finishing & restoration) are not included in the installation.
- 7 Air conditioning drain line and Electrical power supply (feeder line) 220v/ 60hz/ 1ph, should be provided by customer's contractor.
- 8 Final charges will be based on actual installation.

Prepared by: 

Customer Conformance:

Jeffrey Dadios
 Field Surveyor

 Signature Over Printed Name

Reviewed by: 

Engr. Kenneth Zamora
 Service Supervisor Shop and
 Field Operation