

kolin

air conditioner

August 8, 2024

FIRST METRO BUS EXPRESS TRANSPORT INC
512 MC ARTHUR HIGHWAY MALANDAY, VALENZUELA CITY
TEL #: 0917-5457036
Email: rdlfirst@gmail.com

Dear Ma'am/Sir,

Kolin Marketing Inc., is extremely honored for your endorsement of Kolin brand and we are please to offer you with a special price/s for the following items.

A. EQUIPMENT & INSTALLATION

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
2	UNIT/S	MODEL: KLG-IF40-5G1M32 KOLIN FLOOR MOUNTED AIRCONDITIONER 37,980 Kj/h (3.0TR) FULL DC INVERTER R-32 SINGLE PHASE	113,195.00	81,292.10 /	PHP	162,584.20 /
4	UNIT/S	MODEL: KSM-IW25-WCT10M1M32 KOLIN WALL MOUNTED CERTUS AIRCONDITIONER 23,210 Kj/h (2.5HP) REGULAR INVERTER W/ WIFI R-32	49,995.00	34,996.10	PHP	139,984.40 /
1	UNIT/S	MODEL: KSM-IW15-WCT10M1M32 KOLIN WALL MOUNTED CERTUS SERIES AIRCONDITIONER 12,660 Kj/h (1.5HP) REGULAR INVERTER R-32	32,995.00	21,736.10 /	PHP	21,736.10
3	UNIT/S	MODEL: KAG-250WCINV KOLIN WINDOW TYPE QUAD SERIES AIRCONDITIONER 24,120 Kj/h (2.5HP) FULL DC INVERTER W/ WIFI R-32 (WxDxH) 26"x31.5"x17"	48,695.00	36,182.10 /	PHP	108,546.30 /
TOTAL UNIT COST					PHP	432,851.00
ESTIMATED COST OF INSTALLATION (please see attached)					PHP	127,140.00
OTHERS: DELIVERY CHARGE					PHP	600.00
TOTAL ESTIMATED COST OF THE PROJECT					PHP	560,591.00

TERMS OF PAYMENT:

FULL PAYMENT OF UNIT AND DELIVERY CHARGE. IF CHECK, SUBJECT FOR 3 DAYS CLEARING.

WARRANTY:

FOR FLOOR MOUNTED (Inverter): ONE (1) YEAR FREE PARTS AND LABOR, THREE (3) YEARS WARRANTY ON COMPRESSOR.
FOR SPLIT TYPE : ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB , TEN (10) YEARS WARRANTY ON COMPRESSOR.
FOR WINDOW TYPE: ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB, TEN (10) YEARS WARRANTY ON COMPRESSOR.

NOTES: PRICES ARE SUBJECT TO CHANGE WITHOUT PRIOR NOTICE.

PRICES IS VAT INCLUSIVE.


** Cost of Installation is Package with the Unit(s), this cost cannot avail separately.

** INSTALLATION C/O ASC

We thank you for giving opportunity to offer our product and services, hoping we receive your purchase order.

If you need assistance, don't hesitate to call the under signed at 0917-807-8607 or email at kmi_asst@kolinphil.com.ph

Very Truly Yours,


JANELLEN S. LIM
KMI-ASSISTANT

Noted by:


MART NATHANIEL R. FLORES
KMI-SUPERVISOR

KMI-QUOTE-08-24-0710
REG-22%/7K/4K/1.8K

Approved by:


MS. EDITHA M. FLORES
AVP - FINANCE

Conforme:

SIGNATURE OVER PRINTED NAME

EST. 1996

Kolin Marketing, Inc.

1854 Sta. Rita St., Guadalupe Nuevo, Makati City

www.kolinphil.com.ph

Tel.: (632) 8852-6473

Fax: (632) 8852-2170 / (632) 8852-4792

Bringing comfort to your home.

FIRST METRO BUS EXPRESS TRANSPORT INC

512 Mc Arthur Highway Mandalay
Valenzuela City

Date: August 08, 2024
Quotation Number: KEMSV 082024-00004

SUBJECT: Quotation for Installation of Air Conditioner

SJR No. 6551

We are pleased to present our quotation for the following service subject to the terms & conditions set forth hereunder:

Location : Accu1 & Fcu1 - Treasury Room
Type : Wall Mounted Inverter 1.5HP
Pipe Length : 16 Ft.
Wire Length : 23 Ft.
Initial Charge :
: Included

10 Ft. Copper Pipe					Php	7,500.00
10 Ft. Royal Cord						
Outdoor Bracket						
Labor and other consumables						
: Excess						
Copper Pipe	6	/Ft.	1/4 x 3/8	350.00	/Ft.	Php 2,100.00
Royal Cord	13	/Ft.	2.0mm2 x 4c	100.00	/Ft.	Php 1,300.00
Royal Cord	7	/Ft.	3.5mm2 x 3c	60.00	/Ft.	Php 420.00
Circuit Breaker	1	/Pc.	20 Amp	1,000.00	/Pc.	Php 1,000.00
Drain Pump	1	/Pc.		3,000.00	/Pc.	3,000.00
					Php	7,820.00
Total Installation:						Php 15,320.00

Location : Accu2 & Fcu2 - HR Room
Type : Wall Mounted Inverter 2.5HP
Pipe Length : 10 Ft.
Wire Length : 17 Ft.
Initial Charge :
: Included

10 Ft. Copper Pipe					Php	8,500.00
10 Ft. Royal Cord						
Outdoor Bracket						
Labor and other consumables						
: Excess						
Copper Pipe	0	/Ft.	1/4 X 1/2	400.00	/Ft.	Php 0.00
Royal Cord	7	/Ft.	2.0mm2 x 4c	100.00	/Ft.	Php 700.00
Royal Cord	7	/Ft.	3.5mm2 x 3c	60.00	/Ft.	Php 420.00
Circuit Breaker	1	/Pc.	30 Amp	1,000.00	/Pc.	Php 1,000.00
Drain Pump	1	/Pc.		3,000.00	/Pc.	Php 3,000.00
					Php	5,120.00
Total Installation:						Php 13,620.00

MAIN OFFICE:

KENGIE ELECTRO MECHANICAL SERVICES

Unit 8, Gen T. De Leon Commercial Complex Kanuhatan,
Valenzuela City.

Land Number: 02 7623 9392

Mobile Number: 09175170189, 09360544485

Email Add: kengie10818Qgmqil.com

kemtsv1215@gmail.com

BRANCH OFFICE: CAGAYAN VALLEY

KENGIE ELECTRO MECHANICAL SERVICE

24 San Rafael St. Centro Amulong, Cagayan Valley

Mobile Number: 09453092426

Email Add: kengieservicescagayan@gmail.com

Location : Accu3 & Fcu3 - Cashier Room
 Type : Wall Mounted Inverter 2.5HP
 Pipe Length : 43 Ft.
 Wire Length : 50 Ft.

Initial Charge :
 : Included

10 Ft. Copper Pipe
 10 Ft. Royal Cord
 Outdoor Bracket
 Labor and other consumables

Php 8,500.00

: Excess

Copper Pipe	33	/Ft.	1/4 X 1/2	400.00	/Ft.	Php	13,200.00
Royal Cord	40	/Ft.	2.0mm2 x 4c	100.00	/Ft.	Php	4,000.00
Royal Cord	7	/Ft.	3.5mm2 x 3c	60.00	/Ft.	Php	420.00
Circuit Breaker	1	/Pc.	30 Amp	1,000.00	/Pc.	Php	1,000.00
Drain PVC	3	/Pc.		450.00	/Pc.	Php	1,350.00

Php 19,970.00

Total Installation: Php 28,470.00

Location : Accu4 & Fcu4 - Accounting Room
 Type : Wall Mounted Inverter 2.5HP
 Pipe Length : 22 Ft.
 Wire Length : 29 Ft.

Initial Charge :
 : Included

10 Ft. Copper Pipe
 10 Ft. Royal Cord
 Outdoor Bracket
 Labor and other consumables

Php 8,500.00

: Excess

Copper Pipe	12	/Ft.	1/4 X 1/2	400.00	/Ft.	Php	4,800.00
Royal Cord	19	/Ft.	2.0mm2 x 4c	100.00	/Ft.	Php	1,900.00
Royal Cord	7	/Ft.	3.5mm2 x 3c	60.00	/Ft.	Php	420.00
Circuit Breaker	1	/Pc.	30 Amp	1,000.00	/Pc.	Php	1,000.00

Php 8,120.00

Total Installation: Php 16,620.00

Location : Accu5 & Fcu5 - Conference Room
 Type : Floor Mounted Inverter 4.0HP
 Pipe Length : 10 Ft.
 Wire Length : 17 Ft.

Initial Charge :
 : Included

10 Ft. Copper Pipe
 10 Ft. Royal Cord
 Indoor Bracket
 Labor and other consumables

Php 11,000.00

: Excess

Copper Pipe	0	/Ft.	3/8 x 5/8	400.00	/Ft.	Php	0.00
Royal Cord	7	/Ft.	2.0mm2 x 4c	100.00	/Ft.	Php	700.00
Royal Cord	7	/Ft.	3.5mm2 x 3c	60.00	/Ft.	Php	420.00
Circuit Breaker	1	/Pc.	40 Amp	1,000.00	/Pc.	Php	1,000.00
Outdoor Bracket	1	/Pc.		1,650.00	/Pc.	Php	1,650.00
Drain PVC	2	/Pc.		450.00	/Pc.	Php	900.00

Php 4,670.00

Total Installation: Php 15,670.00

Location : Accu6 & Fcu6 - Lounge Room 1
 Type : Floor Mounted 3.0TR
 Pipe Length : 18 Ft.
 Wire Length : 25 Ft.

Initial Charge :
 : Included

10 Ft. Copper Pipe
 10 Ft. Royal Cord
 Indoor Bracket
 Labor and other consumables
 Php 11,000.00

: Excess

Copper Pipe	8	/Ft.	1/4 x 1/2	400.00	/Ft.	Php	3,200.00
Royal Cord	15	/Ft.	2.0mm2 x 4c	100.00	/Ft.	Php	1,500.00
Royal Cord	7	/Ft.	3.5mm2 x 3c	60.00	/Ft.	Php	420.00
Circuit Breaker	1	/Pc.	30 Amp	1,000.00	/Pc.	Php	1,000.00
Outdoor Bracket	1	/Pc.	Large	1,650.00	/Pc.	Php	1,650.00
Drain PVC	1	/Pc.		450.00	/Pc.	Php	450.00
							Php 8,220.00

Total Installation: Php 19,220.00

Location : Accu7 & Fcu7 - Lounge Room 2
 Type : Wall Mounted Inverter 2.5HP
 Pipe Length : 18 Ft.
 Wire Length : 25 Ft.

Initial Charge :
 : Included

10 Ft. Copper Pipe
 10 Ft. Royal Cord
 Outdoor Bracket
 Labor and other consumables
 Php 8,500.00

: Excess

Copper Pipe	8	/Ft.	1/4 x 1/2	400.00	/Ft.	Php	3,200.00
Royal Cord	15	/Ft.	2.0mm2 x 4c	100.00	/Ft.	Php	1,500.00
Royal Cord	7	/Ft.	3.5mm2 x 3c	60.00	/Ft.	Php	420.00
Circuit Breaker	1	/Pc.	30 Amp	1,000.00	/Pc.	Php	1,000.00
							Php 6,120.00

Total Installation: Php 14,620.00

Location : Presidents Room
 Type : Window Type Inverter 2.5 HP
 Pipe Length :
 Wire Length :

Initial Charge :
 : Included

Support/Bracket
 Labor and other consumables
 Php 1,200.00

Total Installation: Php 1,200.00

Location : Operations Room
 Type : Window Type Inverter 2.5 HP
 Pipe Length :
 Wire Length :

Initial Charge :
 : Included

Support/Bracket
 Labor and other consumables
 Php 1,200.00

Total Installation: Php 1,200.00

Location : Maintenance Room
Type : Window Type Inverter 2.5 HP
Pipe Length :
Wire Length :

Initial Charge :
: Included

Support/Bracket
Labor and other consumables

Php 1,200.00

Total Installation: Php 1,200.00

Total Installation: Php 127,140.00

Total Cost Installation: Php 127,140.00

II. VALIDITY DATE:

Quotation - Thirty (30) days only.

III. TERMS OF PAYMENT:

50 % Down Payment

50 % Payment Upon Completion

- Note:** 1. Aging of the payment is based on the billing statement date.
2. Price is subject to change without prior notice.
3. Bank transfer/ cash or dated check (subject for clearing).

IV. BANK DETAILS:

Chinabanking Corporation
Account Name: Kengie Electro Mechanical Services
Account Number: 112400002269

V. WARRANTY:

- One (1) Year parts of airconditioner
One (1) Year labor and installation materials of airconditioner

VI. REMARKS:

1. Mansory, carpentry, chipping and palstering (Finishing or retouch) are not included in the scope of works.
2. Aircon drain line will be tapped to the nearest drain line provision/ downspout pipe.

Miriam Asis

Service Coordinator Head

FOR: MIRIAM ASIS
Service Coordinator

Christine Tacadao
Service Coordinator Staff

Kenneth Siabal
General Manager