

May 13, 2024

FORT KLAN CONSTRUCTION DEVELOPMENT, INC.
BOM, (ADB) BLDG, DPWH NCR 2ND ST. PORT AREA, MANILA
TEL#: 0991-462-7409

Dear Ma'am/Sir,

Kolin Marketing Inc., is extremely honored for your endorsement of Kolin brand and we are please to offer you with a special price/s for the following items.

A. EQUIPMENT & INSTALLATION

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
2	UNIT/S	MODEL: KLG-IF40-5G1M32 KOLIN FLOOR MOUNTED AIRCONDITIONER 37,980 KJ/h (3.0TR) FULL DC INVERTER R-32 SINGLE PHASE	111,995.00	80,356.10	PHP	160,712.20
1	UNIT/S	MODEL: KLG-IF70-5G1M32 KOLIN FLOOR MOUNTED AIRCONDITIONER 61,200 KJ/h (5.0TR) FULL DC INVERTER R-32 SINGLE PHASE	171,395.00	125,688.10	PHP	125,688.10
TOTAL UNIT COST					PHP	286,400.30
ESTIMATED COST OF INSTALLATION (please see attached)					PHP	103,545.00
OTHERS: DELIVERY CHARGE					PHP	600.00
TOTAL ESTIMATED COST OF THE PROJECT					PHP	390,545.30

TERMS OF PAYMENT:

FULL PAYMENT OF UNIT AND DELIVERY CHARGE. IF CHECK, SUBJECT FOR 3 DAYS CLEARING.

WARRANTY:

FOR FLOOR MOUNTED (Inverter): ONE (1) YEAR FREE PARTS AND LABOR, THREE (3) YEARS WARRANTY ON COMPRESSOR.

NOTES: PRICES ARE SUBJECT TO CHANGE WITHOUT PRIOP NOTICE.

PRICES IS VAT INCLUSIVE.


** Cost of Installation is Package with the Unit(s), this cost cannot avail separately.

** INSTALLATION C/O ASC


We thank you for giving opportunity to offer our product and services, hoping we receive your purchase order.

If you need assistance, don't hesitate to call the under signed at 0917-807-8607 or email at kmi_asst@kolinphil.com.ph


Very Truly Yours,


JANELLEN S. LIM
KMI-ASSISTANT

Noted by:


MART NATHANIEL R. FLORES
KMI-SUPERVISOR

Approved By:


MS. EDITHA M. FLORES
AVP - FINANCE

Conforme:

SIGNATURE OVER PRINTED NAME

25th
ANNIVERSARY
EST. 1996

Kolin Marketing, Inc.

1854 Sta. Rita St., Guadalupe Nuevo, Makati City

www.kolinphil.com.ph

Tel.: (632) 8852-6473

Fax: (632) 8852-2170 / (632) 8852-4792

Bringing comfort to your home.

May 13, 2024
 FORT KLAN CONSTRUCTION DEVELOPMENT, INC
 BOM,(ADB) Bldg, DPWH NCR 2nd St. Port Area, Manila
 0991-462-7409

MODEL	Qty
KLG-IF70-5G1M32	1
KLG-IF40-5G1M32	2

BMC OFFICE	Area	0 sqm
-------------------	------	-------

ACU 1	4.0 HP Floor Standing Inverter	KLG-IF40-5G1M32	
	Estimated Pipe Length = 37 ft		
	Estimated Royal Cord Length = 44 ft		
	Initial Charge		₱ 11,000.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Indoor Bracket (Floor)

Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 3/8" x Ø 5/8"	27 ft	₱ 400.00/ft	₱ 10,800.00
Royal Cord (comm. wire)	2.mm2 x 4C	34 ft	₱ 100.00/ft	₱ 3,400.00
Royal Cord (ACCU-Breaker)	5.5mm x 3c	7 ft	₱ 70.00/ft	₱ 490.00
Circuit Breaker waterproof	40A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Outdoor bracket	Fab. wall w/ledge	1 pc/s	₱ 6,500.00/pc	₱ 6,500.00
PVC blue	3/4" x 10'	1 pc/s	₱ 150.00/pc	₱ 150.00
Drain Hose	White -1/2"	7 ft	₱ 25.00/ft	₱ 175.00
				₱ 22,515.00

Estimated Charges	₱ 33,515.00
--------------------------	-------------

ACU 2	7.0 HP Floor Standing Inverter	KLG-IF70-5G1M32	
	Estimated Pipe Length = 37 ft		
	Estimated Royal Cord Length = 44 ft		
	Initial Charge		₱ 14,000.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Outdoor Bracket (Wall)

Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 3/8" x Ø 5/8"	27 ft	₱ 400.00/ft	₱ 10,800.00
Royal Cord (comm. wire)	2.mm2 x 4C	34 ft	₱ 100.00/ft	₱ 3,400.00
Royal Cord (ACCU-Breaker)	5.5mm x 3c	7 ft	₱ 70.00/ft	₱ 490.00
Circuit Breaker waterproof	60A/ 1ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Outdoor bracket	Fab. wall w/ledge	1 pc/s	₱ 6,500.00/pc	₱ 6,500.00
PVC blue	3/4" x 10'	1 pc/s	₱ 150.00/pc	₱ 150.00
Drain Hose	White -1/2"	7 ft	₱ 25.00/ft	₱ 175.00
				₱ 22,515.00

Estimated Charges	₱ 36,515.00
--------------------------	-------------

ACU 3 4.0 HP Floor Standing Inverter**KLG-IF40-5G1M32**

Estimated Pipe Length = 37 ft

Estimated Royal Cord Length = 44 ft

Initial Charge

₱ 11,000.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Indoor Bracket (Floor)

Consumables

Installation Materials

	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 3/8" x Ø 5/8"	27 ft	₱ 400.00/ft	₱ 10,800.00
Royal Cord (comm. wire)	2.mm2 x 4C	34 ft	₱ 100.00/ft	₱ 3,400.00
Royal Cord (ACCU-Breaker)	5.5mm x 3c	7 ft	₱ 70.00/ft	₱ 490.00
Circuit Breaker waterproof	40A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Outdoor bracket	Fab. wall w/ledge	1 pc/s	₱ 6,500.00/pc	₱ 6,500.00
PVC blue	3/4" x 10'	1 pc/s	₱ 150.00/pc	₱ 150.00
Drain Hose	White -1/2"	7 ft	₱ 25.00/ft	₱ 175.00
				₱ 22,515.00

Estimated Charges

₱ 33,515.00

Total Estimated Charges


₱ 103,545.00

Validity: This quotation is valid for a period of fifteen (15) days from the date thereof, subject to our confirmation thereafter.

Installation notes:


- 1 Location of indoor and outdoor units were agreed by the customer and Kolin's surveyor.
- 2 Mechanical Plans, Permits, Electrical permits not included.
- 3 Additional units, for the area.
- 4 Lay out first before install of unit, indoor and outdoor, fabricated outdoor unit onsite.
- 5 Defectors, masonry, carpentry, chipping & plastering (finishing & restoration) are not included in the installation.
- 6 Air conditioning drain line and Electrical power supply (feeder line) **220v/ 60hz/ 1ph** should be provided by customer's contractor.
- 7 **Final charges will be based on actual installation.**

Prepared by:


Jeffrey Dadios

Field Surveyor

Customer Conformer:


Signature Over Printed Name

Reviewed by:


Engr. Kenneth ZamoraService Supervisor Shop and
Field Operation

