

kolin

air conditioner

May 30, 2024

MR. ERIK HO
UNIT 3705 BRISOL TOWER CONDO PARKWAY AVE. COR. CORPORATE AVE. FILINVEST, ALABANG
TEL#: 0917-7281668
Email: lohuimin@gmail.com

Dear Ma'am/Sir,

Kolin Marketing Inc., is extremely honored for your endorsement of Kolin brand and we are please to offer you with a special price/s for the following items.

A. EQUIPMENT & INSTALLATION

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
1	UNIT/S	MODEL: KSG-IWF-30WYF-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 29,500 Kj/h (3.0HP) FULL DC INVERTER W/ WIFI R-32	74,995.00	54,496.10	PHP	54,496.10
1	UNIT/S	MODEL: KSG-IWF-20WYF-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 19,000 Kj/h (2.0HP) FULL DC INVERTER W/ WIFI R-32	58,395.00	41,548.10	PHP	41,548.10
1	UNIT/S	MODEL: KSG-IWF-15WYF-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 12,960 Kj/h (1.5HP) FULL DC INVERTER W/ WIFI R-32	45,795.00	31,720.10	PHP	31,720.10
TOTAL UNIT COST					PHP	127,764.30
ESTIMATED COST OF INSTALLATION (please see attached)					PHP	46,200.00
OTHERS: DELIVERY CHARGE					PHP	600.00
TOTAL ESTIMATED COST OF THE PROJECT					PHP	174,564.30

TERMS OF PAYMENT:

FULL PAYMENT OF UNIT AND DELIVERY CHARGE. IF CHECK, SUBJECT FOR 3 DAYS CLEARING.

WARRANTY:

FOR SPLIT TYPE : ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB , TEN (10) YEARS WARRANTY ON COMPRESSOR.

NOTES: PRICES ARE SUBJECT TO CHANGE WITHOUT PRIOR NOTICE.

PRICES IS VAT INCLUSIVE.


** Cost of Installation is Package with the Unit(s), this cost cannot avail separately.

** INSTALLATION C/O ASC

We thank you for giving opportunity to offer our product and services, hoping we receive your purchase order.


If you need assistance, don't hesitate to call the under signed at 0917-807-8607 or email at kmi_asst@kolinphil.com.ph

Very Truly Yours,


JANELLE S. LIM
KMI-ASSISTANT

Noted by:

MART NATHANIEL R. FLORES
KMI-SUPERVISOR

Approved By:

MS. EDITHA M. FLORES
AVP - FINANCE

Conforme:

SIGNATURE OVER PRINTED NAME

ANNIVERSARY
EST. 1996

KMI-QUOTE-05-24-0500
TYT-22%/4K

Kolin Marketing, Inc.

1854 Sta. Rita St., Guadalupe Nuevo, Makati City

www.kolinphil.com.ph

Tel.: (632) 8852-6473

Fax: (632) 8852-2170 / (632) 8852-4792

Bringing comfort to your home.

May 29, 2024
ERIK HO
Unit 3705 Bristol Tower Condo. Parkway Ave. Cor. Corporate Ave. Filinvest, Alabang
0917-7281668
lohuimin@gmail.com

MODEL		Qty
KSG-IWF-30Wfy8K1M32		1
KSG-IWF-20Wfy8K1M32		1
KSG-IWF-15Wfy8K1M32		1

LIVING/DINING		Area	46 sqm		
ACU 1	3.0 HP Wall Mounted Inverter	KSG-IWF-30Wfy8K1M32			
	Estimated Pipe Length = 30 ft				
	Estimated Royal Cord Length = 35 ft				
	Initial Charge	P 4,700.00			
	Includes:	Less Outdoor Bracket			
	Labor				
	10ft Copper Tube				
	10ft Royal Cord				
	Consumables				
Installation Materials		Description	Qty	Price per qty	Subtotal
		Copper Tube	Ø 1/4" x Ø 5/8"	20 ft P 400.00/ft	P 8,000.00
		Royal Cord (comm. wire)	2.mm2 x 4C	25 ft P 100.00/ft	P 2,500.00
		Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft P 60.00/ft	P 300.00
		Outdoor bracket	Modified	1 pc/s P 1,500.00/pc	P 1,500.00
		Dismantle	1.0HP Wall Mounted	2 set P 2,500.00/set	P 5,000.00
		PVC blue	3/4" x 10'	2 pc/s P 150.00/pc	P 300.00
					P 17,600.00
Estimated Charges					P 22,300.00

MASTER BEDROOM		Area	17 sqm		
ACU 2	2.0 HP Wall Mounted Inverter	KSG-IWF-20Wfy8K1M32			
	Estimated Pipe Length = 20 ft				
	Estimated Royal Cord Length = 25 ft				
	Initial Charge	P 3,700.00			
	Includes:	Less Outdoor Bracket			
	Labor				
	10ft Copper Tube				
	10ft Royal Cord				
	Consumables				
Installation Materials		Description	Qty	Price per qty	Subtotal
		Copper Tube	Ø 1/4" x Ø 1/2"	10 ft P 350.00/ft	P 3,500.00
		Royal Cord (comm. wire)	2.mm2 x 4C	15 ft P 100.00/ft	P 1,500.00
		Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft P 60.00/ft	P 300.00
		Outdoor bracket	Modified	1 pc/s P 1,500.00/pc	P 1,500.00
		Dismantle	1.5HP Wall Mounted	1 set P 2,500.00/set	P 2,500.00
		PVC blue	3/4" x 10'	2 pc/s P 150.00/pc	P 300.00
					P 9,600.00
Estimated Charges					P 13,300.00

KIDS ROOM		Area	11 sqm		
ACU 3	1.5 HP Wall Mounted Inverter	KSG-IWF-15Wfy8K1M32			
	Estimated Pipe Length = 14 ft				
	Estimated Royal Cord Length = 19 ft				
	Initial Charge	P 3,700.00			
	Includes:	Less Outdoor Bracket			
	Labor				
	10ft Copper Tube				
	10ft Royal Cord				
	Consumables				
Installation Materials		Description	Qty	Price per qty	Subtotal
		Copper Tube	Ø 1/4" x Ø 3/8"	4 ft P 350.00/ft	P 1,400.00
		Royal Cord (comm. wire)	2.mm2 x 4C	9 ft P 100.00/ft	P 900.00
		Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft P 60.00/ft	P 300.00
		Outdoor bracket	Modified	1 pc/s P 1,500.00/pc	P 1,500.00
		Dismantle	1.5HP Wall Mounted	1 set P 2,500.00/set	P 2,500.00
		PVC blue	3/4" x 10'	2 pc/s P 150.00/pc	P 300.00
					P 6,900.00
Estimated Charges					P 10,600.00

May 29, 2024

Ho, Erik

Unit 3705 Bristol Tower Condo. Parkway Ave. Cor. Corporate Ave. Filinvest, Alabang

0917-7281668

lohuimin@gmail.com

Please be informed that the air-conditioner you intend to purchase is under capacity as compared to the following unit that we proposed:

Location	Area	Kolin's Recommendation	Customer's Choice	Remarks
LIVING/DINING	46 sqm	KLG-IF40-5G1M32	KSG-IWF-30WFFY8K1M32	Calculated 3.4hp under by 0.4hp

Since the unit of your choice is under capacity, it is probable that you may experience the following;

1. Capacity of the unit to cool the area will take longer or it will not cool the area at all that may lead to your dissatisfaction with the cooling performance of our unit.
2. Power consumption will be higher due to frequent running of compressor for not reaching the desired temperature within the normal parameter.
3. Useful life of compressor will be shortened due to excessive running beyond the normal run cycle.

Considering the above conditions, we regret to inform you that we cannot guarantee the efficient performance of unit. **Also, One (1) year warranty for parts (compressor-10year).**

For your guidance and information

Prepared by:

Jeoffrey T. Dadios
Surveyor

Approved by:

Mr. Alvin de Rivera
Service Manager

Noted by:

Engr. Kenneth Zamora
Service Supervisor - Field
and Shop Operation

Customer Conforme:

Signature Over Printed Name