

MR. EDRIC CHAM
UNIT-21AB FUTURE POINT SUITES, #110 PANAY AVE. BRGY, SOUTH TRIANGLE QUEZON CITY
TEL#: 0917-8652300

Dear Ma'am/Sir,

Kolin Marketing Inc., is extremely honored for your endorsement of Kolin brand and we are please to offer you with a special price/s for the following items.

A. EQUIPMENT & INSTALLATION

** OPTION 1

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
2	UNIT/S	MODEL: KSM-IW15-WCT10M1M32 KOLIN WALL MOUNTED CERTUS SERIES AIRCONDITIONER 12,660 Kj/h (1.5HP) REGULAR INVERTER R-32	32,995.00	21,736.10	PHP	43,472.20
1	UNIT/S	MODEL: KSM-IW25-WCT10M1M32 KOLIN WALL MOUNTED CERTUS AIRCONDITIONER 23,210 Kj/h (2.5HP) REGULAR INVERTER W/ WIFI R-32	49,995.00	34,996.10	PHP	34,996.10
TOTAL UNIT COST					PHP	78,468.30
ESTIMATED COST OF INSTALLATION w/ dismantling of existing unit (please see attached)					PHP	53,140.00
OTHERS: DELIVERY CHARGE					PHP	600.00
TOTAL ESTIMATED COST OF THE PROJECT					PHP	132,208.30

** OPTION 2


QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
2	UNIT/S	MODEL: KSG-IWF-15WFF-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 12,960 Kj/h (1.5HP) FULL DC INVERTER W/ WIFI R-32	46,595.00	29,344.10	PHP	58,688.20
1	UNIT/S	MODEL: KSG-IWF-25WFF-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 25,560 Kj/h (2.5HP) FULL DC INVERTER W/ WIFI R-32	68,995.00	46,816.10	PHP	46,816.10
TOTAL UNIT COST					PHP	105,504.30
ESTIMATED COST OF INSTALLATION w/ dismantling of existing unit (please see attached)					PHP	53,140.00
OTHERS: DELIVERY CHARGE					PHP	600.00
TOTAL ESTIMATED COST OF THE PROJECT					PHP	159,244.30


TERMS OF PAYMENT:
FULL PAYMENT OF UNIT AND DELIVERY CHARGE. IF CHECK, SUBJECT FOR 3 DAYS CLEARING.

WARRANTY:
FOR SPLIT TYPE : ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB , TEN (10) YEARS WARRANTY ON COMPRESSOR.

NOTES: PRICES ARE SUBJECT TO CHANGE WITHOUT PRIOR NOTICE.
PRICES IS VAT INCLUSIVE.
** Cost of Installation is Package with the Unit(s), this cost cannot avail separately.
** INSTALLATION C/O ASP (cost will be based on actual)

We thank you for giving opportunity to offer our product and services, hoping we receive your purchase order.
If you need assistance, don't hesitate to call the under signed at 0917-807-8607 or email at kmi_asst@kolinphil.com.ph

Very Truly Yours,

JANELLE S. LIM
KMI-ASSISTANT

Noted by:

MART N. DANIEL R. FLORES
KMI-SUPERVISOR

Approved By:

MS. EDITHA M. FLORES
AVP - FINANCE

Conforme: _____
SIGNATURE OVER PRINTED NAME

KMI-QUOTE-10-24-0925
REG-22%/4K/7K



MJRC AIRCONDITIONING SERVICES

#68 Kabalitang St. Brgy.Krus Na Ligas Quezon City
2453114 / 09062456002 / 09272733186
Email Add: mjrc.airconditioning@gmail.com

QUOTATION

October 28,2024

Mr.Edric Cham

Unit-21AB Future Point Suites

#110 Panay Ave. Brgy.South Triangle,Quezon City

Please see the below prices for your reference

QTY	DESCRIPTION	UNIT PRICE	AMOUNT
1	MASTER'S BEDROOM		
	For Installation of 1.5HP Kolin Split Type Wall Mounted Inverter		
	1st 10ft	✓ 7,500.00	
	Nema 3R	1,000.00	8,500.00
	SMALL BEDROOM		
	For Installation of 1.5HP Kolin Split Type Wall Mounted Inverter		
	1st 10ft	✓ 7,500.00	
	Excess 40ft	14,000.00	
	Royal Cord (comm wire) 37ft	3,700.00	
	Metal Clamp 4pcs	480.00	
	Nema 3R	1,000.00	26,680.00
	LIVING ROOM		
	For Installation of 2.5HP Kolin Split Type Wall Mounted Inverter		
	1st 10ft	✓ 8,500.00	
	Exess 14ft	4,900.00	
	Metal Clamp 2pcs	240.00	
	Nema 3R	1,000.00	
	Drain Pump	2,900.00	
	Rubber Insulation 1/2x3/4 8m 4pcs	920.00	18,460.00
Sub-total			53,640.00

Less Survey Fee	500.00
Total	53,140.00

TERMS OF PAYMENT

1.For check payment,please make all payments payable to MJRC Airconditioning Services.

INSTALLATION INCLUSION:

- 1.Labor cost for back to back installation
- 2.Additional copper tubing,rubber insulation,field or communication wiring,drain piping.
- 3.Boring of holes through CHB wall up to 8 inches wall thickness and up to 4 inches diameter.
4. Installation of outdoor up to 6ft elevation.
- 5.Applicable to expose piping and drainage.
- 6.Polythelene tape covering the insulated refrigerant piping,wiring and drain piping.
- 7.Flexible hose insulating field / communicating wiring.

INSTALLATION EXCLUSION:

- 1.Extra installation work required by the customer (subject to additional charges which will be determined on the site)
- 2.Concrete chipping,glass cutting,wall plastering and restoration.
- 3.Power connection from breaker to main source.
- 4.Ducting and Ventilation of outdoor unit.
- 5.Use of scaffolding for Overhead Installation.

THANK YOU FOR YOUR BUSINESS

Phoebe Masuba

Prepared by

Conformme