



October 9, 2024

MS. JENILLE LORENA
23 KIRISHIMA ST. BF THAI, LAS PIÑAS
TEL#: 0917-8537047

Dear Ma'am/Sir,

Kolin Marketing Inc., is extremely honored for your endorsement of Kolin brand and we are please to offer you with a special price/s for the following items.

A. EQUIPMENT & INSTALLATION

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
1	UNIT/S	MODEL: KAG-100WCINV KOLIN WINDOW TYPE QUAD SERIES AIRCONDITIONER 10,200 Kj/h (1.0HP) FULL DC INVERTER W/ WIFI R-32 (WxDxH) 18"x25"x14"	28,995.00	21,316.10	PHP	21,316.10
1	UNIT/S	MODEL: KLG-IF40-5G1M32 KOLIN FLOOR MOUNTED AIRCONDITIONER 37,980 Kj/h (3.0TR) FULL DC INVERTER R-32 SINGLE PHASE	113,195.00	81,292.10	PHP	81,292.10
3	UNIT/S	MODEL: KSG-IWF-20WFF-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 19,000 Kj/h (2.0HP) FULL DC INVERTER W/ WIFI R-32	59,595.00	42,484.10	PHP	127,452.30
1	UNIT/S	MODEL: KSG-IWF-25WFF-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 25,560 Kj/h (2.5HP) FULL DC INVERTER W/ WIFI R-32	68,995.00	49,816.10	PHP	49,816.10
TOTAL UNIT COST					PHP	279,876.60
ESTIMATED COST OF INSTALLATION w/ dismantling of old unit (please see attached)					PHP	67,000.00
OTHERS: DELIVERY CHARGE					PHP	600.00
TOTAL ESTIMATED COST OF THE PROJECT					PHP	347,476.60

TERMS OF PAYMENT:

FULL PAYMENT OF UNIT AND DELIVERY CHARGE. IF CHECK, SUBJECT FOR 3 DAYS CLEARING.

WARRANTY:

FOR WINDOW TYPE: ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB, TEN (10) YEARS WARRANTY ON COMPRESSOR.

FOR FLOOR MOUNTED: ONE (1) YEAR FREE PARTS AND LABOR, FIVE (5) YEARS WARRANTY ON COMPRESSOR.

FOR SPLIT TYPE : ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB , TEN (10) YEARS WARRANTY ON COMPRESSOR.

NOTES: PRICES ARE SUBJECT TO CHANGE WITHOUT PRIOR NOTICE.

PRICES IS VAT INCLUSIVE.

** Cost of Installation is Package with the Unit(s), this cost cannot avail separately.

** INSTALLATION C/O ASP (cost will be based on actual)

We thank you for giving opportunity to offer our product and services, hoping we receive your purchase order.

If you need assistance, don't hesitate to call the under signed at 0917-807-8607 or email at kmi_asst@kolinphil.com.ph

Very Truly Yours,

JANELLEN S. LIM
KMI-ASSISTANT

Noted by:

MART NATHANIEL R. FLORES
KMI-SUPERVISOR

Approved By:

MS. EDITHA M. FLORES
AVP - FINANCE

Conforme:

SIGNATURE OVER PRINTED NAME

KMI-QUOTE-10-24-0864
ECY-22%/1.3K/7K/4K

Kolin Marketing, Inc.

1854 Sta. Rita St., Guadalupe Nuevo, Makati City

Tel.: (632) 8852-6473

Fax: (632) 8852-2170 / (632) 8852-4792

www.kolinphil.com.ph / kolinphilippines





N.V.F.S MAINTENANCE AIRCON & REFRIGERATION SYSTEM TRADING
MANILA: Office Unit Q Monserrat St B.F. Homes Phase 1 Sucat Rd Paranaque
+639171163534 | +639455920222 | +632 85146379
E-mail: sales@about-nvfs-ph.com | inquiry@about-nvfs-ph.com
www.nvfs-ph.com
TIN Number: 305-342-355-00000

QOUTATION

TO : Lorena, Jenille
ADDRESS: 23 Kirishima St. Bf Thai

REFERENCE NO:
DATE : October 08, 2024
CUSTOMER NO : 0917-8537047

Repair Code	BRAND AND ITEM DESCRIPTION	QTY	UNIT	UNIT PRICE	GROSS AMOUNT	DISCOUNT	NET PRICE
*	Guest Room - 1hp Window Type						
5	Basic Installation Mounting (No Chipping works and Major Modification)	1	Set	P1,200.00	P1,200.00		P1,200.00
*	Living Room - 4hp Floor Mounted						
18.1	Installation 4hp - Floor Mounted	1	Set	P11,000.00	P11,000.00		P11,000.00
*	Dinning Room - 2hp Wall Mounted						
11.1	Installation 1.0 - 2.0 hp	1	Set	P4,500.00	P4,500.00		P4,500.00
*	Master's Bedroom - 2.5hp Wall Mounted						
11.2	Installation 2.5 - 3.0 hp	1	Set	P5,500.00	P5,500.00		P5,500.00
31.2	Provision & Installation of Plastic Wall Pipe Cladding 2.5 - 3.0 hp / 10Ft	1	Set	P4,500.00	P4,500.00		P4,500.00
31.4	Chipping Works for Copper Pipe / Drain Line Layout (Per Meter)(Restoration works not Included) - (Est. as per Survey)	6	Mtr	P500.00	P3,000.00		P3,000.00
31.16	PVC Pipe Blue For Drain 3/4 Including Elbow's & T's	4	Pcs	P150.00	P600.00		P600.00
29.2	Copper Tube Excessof 1st 10ft - Copper Tube & Rubber Insulation 2.5 - 3.0TR - (Est. as per Survey)	5	Ft	P400.00	P2,000.00		P2,000.00
30.1	Excess Royal Cord 2.0mm2 x 4C Communication wire / Ft - (Est. as per Survey)	5	Ft	P100.00	P500.00		P500.00
						Total:	P16,100.00
*	Bedroom 2 - 2hp Wall Mounted						
11.1	Installation 1.0 - 2.0 hp	1	Set	P4,500.00	P4,500.00		P4,500.00
31.1	Provision & Installation of Plastic Wall Pipe Cladding 1.0 - 2.0 hp / 10Ft	1	Set	P3,500.00	P3,500.00		P3,500.00
31.4	Chipping Works for Copper Pipe / Drain Line Layout (Per Meter)(Restoration works not Included) - (Est. as per Survey)	6	Mtr	P500.00	P3,000.00		P3,000.00
31.16	PVC Pipe Blue For Drain 3/4 Including Elbow's & T's	4	Pcs	P150.00	P600.00		P600.00
29.1	Copper Tube Excessof 1st 10ft - Copper Tube & Rubber Insulation 1.0 - 2.0hp - (Est. as per Survey)	10	Ft	P350.00	P3,500.00		P3,500.00
30.1	Excess Royal Cord 2.0mm2 x 4C Communication wire / Ft - (Est. as per Survey)	10	Ft	P100.00	P1,000.00		P1,000.00
						Total:	P16,100.00
*	Bedroom 3 - 2hp Wall Mounted						
11.1	Installation 1.0 - 2.0 hp	1	Set	P4,500.00	P4,500.00		P4,500.00
31.1	Provision & Installation of Plastic Wall Pipe Cladding 1.0 - 2.0 hp / 10Ft	1	Set	P3,500.00	P3,500.00		P3,500.00
31.4	Chipping Works for Copper Pipe / Drain Line Layout (Per Meter)(Restoration works not Included) - (Est. as per Survey)	6	Mtr	P500.00	P3,000.00		P3,000.00
31.16	PVC Pipe Blue For Drain 3/4 Including Elbow's & T's	4	Pcs	P150.00	P600.00		P600.00
29.1	Copper Tube Excessof 1st 10ft - Copper Tube & Rubber Insulation 1.0 - 2.0hp - (Est. as per Survey)	10	Ft	P350.00	P3,500.00		P3,500.00
30.1	Excess Royal Cord 2.0mm2 x 4C Communication wire / Ft - (Est. as per Survey)	10	Ft	P100.00	P1,000.00		P1,000.00
						Total:	P16,100.00
30.7	Supply and Installation of Nema 3R Whether Proof Enclosure w/ Breaker	5	Set	P1,000.00	P5,000.00		P5,000.00
						Total Cost of Installation:	P70,000.00
						Less Survey:	P3,000.00
						Over All Total:	P67,000.00

SCOPE OF WORKS:

1. First 10ft. Copper Tube / 10ft. drain pipe
2. Basic Metal Bracket for Outdoor unit & Fabricated Cat Walk for 6 Units of Aircon Outdoor Units
3. Rubber installation tubes for ceiling and standard 1/2 size for outdoor exposure walls, electrical materials including control wiring royal cord ,Insulated PVC drain line including fittings
4. Provide installation materials such as, copper pipes, soft drawn seamless copper pipe.
5. Brazing of copper tubing & covering of polyethylene tape.
6. Supply of installation tools, welding equipment, manpower and supervision.
7. System dehydration and vacuuming. Testing commissioning and turnover.

TERMS & CONDITIONS

1. Unit Price and Installation are VAT Inclusive.
2. Full Payment on Unit before delivery.
3. Site survey is mandatory. Final Charges will be based on the actual installation during completion of work.

WARRANTY

Note : for KOLIN Models :

- * for Residential ACU : with 10 years warranty on compressor and 3 years warranty on PCB 1 year on evaporator coil and condenser coil
- * for Light Commercial ACU : with 5 years warranty on compressor and 1 year warranty on PCB / evaporator coil and condenser coil

1. Warranty may be restricted or disallowed based on the discretion of N.V.F.S.

EXCLUSIONS:

1. Excess copper tube & Communication Wiring 4C with separate charges: P450/ft. for Split Type 1.0hp-2.0hp; P500/ft. for Split Type 2.5hp-3.0hp for Floor Mounted and Ceiling Mounted
2. Electrical cabling for air condition power supply / Electrical Supply from Main Panel to ACCU breaker / Dismantling of existing unit / Restoration Works
3. Provision and installation of NEMA 3R Circuit breaker 20 AMP / 30 AMP P1000
4. Electrical cabling for air condition power supply / Indoor to Outdoor Service breaker Size # 14 THHN Wire P60/Mtr, Size # 12 THHN Wire P80/Mtr, Size # 10 THHN Wire P100/Mtr


Jerwell Tedd Palma

NVFS Maintenance Aircon and Refrigeration System Trading

Date :

Conforme:

Client's Signature over Printed Name / Date

AUTHORIZED DEALER OF THE FOLLOWING BRANDS



AUTHORIZED SERVICE CENTER OF THE FOLLOWING BRANDS

