



September 2, 2024

MR. RYAN SIA

B3 L22 MACOPA ST. COR. GUAVA, PALIPARAN ROAD, SOUTHGROVE ESTATE INSIDE AVIDA SETTINGS,

BRGY. MOLINO IV, BACOR CITY CAVITE

TEL #: 0917-8858914

Dear Ma'am/Sir,

Kolin Marketing Inc., is extremely honored for your endorsement of Kolin brand and we are please to offer you with a special price/s for the following items.

A. EQUIPMENT & INSTALLATION

(LIVING/DINING 'ROOM)

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
1	UNIT/S	MODEL: KSG-IWF-30WFY-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 29,500 Kj/h (3.0HP) FULL DC INVERTER W/ WIFI R-32	76,595.00	55,744.10	PHP	55,744.10
TOTAL UNIT COST					PHP	55,744.10
ESTIMATED COST OF INSTALLATION (please see attached)					PHP	9,745.00
OTHERS: DELIVERY CHARGE					PHP	600.00
TOTAL ESTIMATED COST OF THE PROJECT					PHP	66,089.10

TERMS OF PAYMENT:

FULL PAYMENT OF UNIT AND DELIVERY CHARGE. IF CHECK, SUBJECT FOR 3 DAYS CLEARING.

WARRANTY:

FOR SPLIT TYPE : ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB , TEN (10) YEARS WARRANTY ON COMPRESSOR.

NOTES: PRICES ARE SUBJECT TO CHANGE WITHOUT PRIOR NOTICE.

PRICES IS VAT INCLUSIVE.


**\*\* Cost of Installation is Package with the Unit(s), this cost cannot avail separately.**

**\*\* INSTALLATION C/O ASC**


We thank you for giving opportunity to offer our product and services, hoping we receive your purchase order.

If you need assistance, don't hesitate to call the under signed at 0917-807-8607 or email at [kmi\\_asst@kolinphil.com.ph](mailto:kmi_asst@kolinphil.com.ph)

Very Truly Yours,

  
JANELLEN S. LIM  
KMI-ASSISTANT

Noted by:

  
MART NATHANIEL R. FLORES  
KMI-SUPERVISOR

Approved By:

  
MS. EDITHA M. FLORES  
AVP - FINANCE

KMI-QUOTE-09-24-0760  
REG-22%/4K

Conforme:

SIGNATURE OVER PRINTED NAME

Kolin Marketing, Inc.

1854 Sta. Rita St., Guadalupe Nuevo, Makati City

Tel.: (632) 8852-6473

Fax: (632) 8852-2170 / (632) 8852-4792

 [www.kolinphil.com.ph](http://www.kolinphil.com.ph) / [kolinphilippines](http://kolinphilippines)





**KOLIN Philippines International Inc.**  
**Survey Form**

**No 003526**

Customer Name : RYAN SIA Date : 8-30-24  
 Address : B-22 MDCOR 91 SOUTH GROVE ESTATE SJR No. : 219728  
138 CORNER CITY  
 Establishment Type : Residential ☒ Area Surveyed : LIVING / DINING  
 Commercial ☐ Area Surveyed : \_\_\_\_\_  
 Recommended Product Model : K56-WF-30WTF 81K1M32

**Cooling Capacity Computation**

Floor Area : 30 sqm.  
 Ceiling Height : 2.6 mtr.

note: add 20% per meter in excess of 3 meters in the initial cooling capacity computed.

Floor Area :	<u>30</u>	x	550 Btu/h	<u>16500</u> Btu/h
Ceiling Height (excess of 3 mtrs.) :		x	20%	
Window Direct Sunlight		x	20 - 50%	<u>3300</u> Btu/h
Total Cooling Capacity				<u>19800</u> Btu/h

**Add : Additional Heat Load**

No. of Person	<u>10</u>	x	300 Btu/h	<u>3000</u> Btu/h
No. of Ordinary Light (<40w)	<u>12</u>	x	200 Btu/h	<u>2400</u> Btu/h
No. of Special Light (>40w)		x	400 Btu/h	
No. of Refrigerator (< 6 cu.ft.)		x	400 Btu/h	
No. of Refrigerator (> 6 cu.ft.)		x	800 Btu/h	
No. of Cooking Range		x	1500 Btu/h	
No. of Laptop Computer		x	150 Btu/h	
No. of Desktop Computer	<u>1</u>	x	400 Btu/h	<u>400</u> Btu/h
No. of Printer		x	500 Btu/h	
No. of Photocopier		x	1000 Btu/h	
Total Cooling Capacity				<u>5800</u> Btu/h

**Recommended Cooling Capacity**

2.8  
23600 Btu/h

Note : Compressor warranty will be reduced to \_\_\_\_ yr. if air-conditioner purchased is lower than the recommended cooling capacity or pipe lay-out is beyond the maximum allowable length.

**Scope of Work Agreement**

- |                                   |  |  |
|-----------------------------------|--|--|
| 1. Copper tube lay-out            | <input type="checkbox"/> Expose                            | <input type="checkbox"/> Embedded                                    |
| 2. Chipping                       | <input type="checkbox"/> Included                          | <input checked="" type="checkbox"/> Not Included                     |
| 3. Fabricated Bracket             | <input type="checkbox"/> Yes <input type="checkbox"/> Shop | <input type="checkbox"/> Site <input checked="" type="checkbox"/> No |
| 4. Service Ledge                  | <input type="checkbox"/> Yes                               | <input checked="" type="checkbox"/> No                               |
| 5. Dismantling of existing Aircon | <input type="checkbox"/> Included                          | <input checked="" type="checkbox"/> Not Included                     |
| 6. Ducting                        | <input type="checkbox"/> Yes                               | <input checked="" type="checkbox"/> No                               |

**Dimension :**

- Plastering, carpentry and restoration works are to be done by the customer.
- Wiring of electrical supply from main panel to air-conditioning unit are to be done by the customer.
- Processing of mechanical plan, working permit, electrical permit are to be done by the customer.
- Other concern;

CUSTOMER NEED TO PROVIDE TOWNSHIP  
AT THE OUTDOOR RELOCATION  
EXPOSE COPPER TUBE IF IN AREA  
4 INCH FROM WALL (INDOOR LOCATION)



A hand-drawn diagram on a 5x5 grid. The grid contains several symbols and numbers:

- Top row: A horizontal line spanning from the second to the fourth column, with the number "4" written above it.
- Second row: A vertical line spanning from the second to the fourth row, with the number "5" written to its left.
- Third row: A horizontal line spanning from the second to the fourth column, with the number "4" written above it.
- Fourth row: A horizontal line spanning from the second to the fourth column, with the number "4" written above it.
- Bottom row: A horizontal line spanning from the second to the fourth column, with the number "5" written below it.
- Other symbols include a cross-like shape in the third row, second column; a small rectangle in the fourth row, fourth column; and some faint markings in the bottom right corner.

Indoor Unit Location : RIGHT CORNER KITCH. OPPOSITE OF WASH SINK  
Outdoor Unit Location : AT THE RIGHT SIDE, RIGHT OF 2 HP OUTDOOR  
Pipe Length : 12 FT  
Special Note :

Installation Cost Estimate			
Material Description	Qty.	Unit Cost	Total Cost
Copper Tube (excess of 10 ft.)	2330, 2430, 2520, 3520, 4620	400	800
Wire (Royal Cord-signal wire) (excess of 10ft.)	2.0mmx4C	100	200
Wire (Royal Cord - Breaker to ODU)	3.5mm / 5.5mm x 3C	60	120
Circuit Breaker	20A, 30A, 40A/1ph, 40A/3ph	1000	1000
Bracket (ODU)	(Imptd. / Fabricated) ; (Floor / Wall)		
Bracket (WAC)	Angle Type		
PVC Pipe (drain)	1/2" , 3/4"	150	150
PVC Pipe (electrical)	3/4" , 1"		
Drain Pump			
Drain P. Hose		8	125
	mtr.		800
Dismantling Fee (existing air-conditioner)			500
Initial Charge			
TOTAL ESTIMATE			P 9,745

**Note :**

1. Initial Charge includes labor, 10ft. Copper tube, 10ft. Royal cord, Circuit breaker, Outdoor Bracket (SAC), Indoor Bracket (PAC) and Consumable materials.
2. Survey fee will be **deducted** in the installation fee.

Prepared by:

Signature Over Printed Name

**Customer Conforme:**

**Signature Over Printed Name**