



September 5, 2024

MS. KATRINA ORTEGA
UNIT-27S ARTON BY ROCKWELL, AURORA BLVD. BRGY. LOYOLA HEIGHTS, QUEZON CITY
TEL#: 0917-5322487

Dear Ma'am/Sir,

Kolin Marketing Inc., is extremely honored for your endorsement of Kolin brand and we are please to offer you with a special price/s for the following items.

A. EQUIPMENT & INSTALLATION

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
2	UNIT/S	MODEL: KFS-20BAG1M-I KOLIN FLEXMATCH SERIES III AIRCONDITIONER 18,991 Kj/h (2.0HP) INVERTER INDOOR UNIT R-410A	17,195.00	13,412.10	PHP	26,824.20
2	UNIT/S	MODEL: KFS-40DAG1M-O KOLIN FLEXMATCH SERIES III AIRCONDITIONER 37,982 Kj/h (4.0HP) INVERTER OUTDOOR UNIT R-410A	108,195.00	84,392.10	PHP	168,784.20
2	UNIT/S	MODEL: KFS-10BAG1M-I KOLIN FLEXMATCH SERIES III AIRCONDITIONER 9,496 Kj/h (1.0HP) INVERTER INDOOR UNIT R-410A	12,295.00	9,590.10	PHP	19,180.20
1	UNIT/S	MODEL: KFS-15BAG1M-I KOLIN FLEXMATCH SERIES III AIRCONDITIONER 12,661 Kj/h (1.5HP) INVERTER INDOOR UNIT R-410A	13,995.00	10,916.10	PHP	10,916.10
TOTAL UNIT COST					PHP	225,704.70
ESTIMATED COST OF INSTALLATION (please see attached)					PHP	53,500.00
OTHERS: DELIVERY CHARGE					PHP	600.00
TOTAL ESTIMATED COST OF THE PROJECT					PHP	279,804.70

TERMS OF PAYMENT:

FULL PAYMENT OF UNIT AND DELIVERY CHARGE. IF CHECK, SUBJECT FOR 3 DAYS CLEARING.

WARRANTY:

FOR FLEXMATCH: ONE (1) YEAR FREE PARTS AND LABOR, FIVE (5) YEARS WARRANTY ON COMPRESSOR.

NOTES: PRICES ARE SUBJECT TO CHANGE WITHOUT PRIOR NOTICE.

PRICES IS VAT INCLUSIVE.

** Cost of Installation is Package with the Unit(s), this cost cannot avail separately.

** INSTALLATION C/O ASC

We thank you for giving opportunity to offer our product and services, hoping we receive your purchase order.

If you need assistance, don't hesitate to call the under signed at 0917-807-8607 or email at kmi_asst@kolinphil.com.ph

Very Truly Yours,

JANELLE S. LIM
KMI-ASSISTANT

Noted by;

MART NATHANIEL R. FLORES
KMI-SUPERVISOR

Approved By:

MS. EDITHA M. FLORES
AVP - FINANCE

KMI-QUOTE-09-24-0773
REG-22%

Conforme:

SIGNATURE OVER PRINTED NAME

Kolin Marketing, Inc.
1854 Sta. Rita St., Guadalupe Nuevo, Makati City
Tel.: (632) 8852-6473
Fax: (632) 8852-2170 / (632) 8852-4792
 www.kolinphil.com.ph / kolinphilippines



MJRC AIRCONDITIONING SERVICES

#124 V.Luna Rd Extn Brgy.Sikatuna Village Quezon City
82453114 / 09062456002 / 09272733186
Email Add: mjrc.airconditioning@gmail.com

QUOTATION

August 27,2024

Katrina Ortega / Gerald Ortega
Unit-27S Arton By Rockwell
Aurora Blvd. Brgy.Loyola Hts
Quezon City

Please see the below prices for your reference

QTY	DESCRIPTION	UNIT PRICE	AMOUNT
1	ACU 1 4.0HP (FLEX MATCH) 1ST SET		
	LIVING ROOM		
	FCU A 2.0HP Wall Mounted Inverter		
	Initial Charge (succeeding unit)	7,500.00	
	Leak Testing	1,800.00	
	Nema 3R	1,000.00	
			10,300.00
1	FCU B 2.0HP Wall Mounted Inverter		
	Initial Charge	7,500.00	-
	Leak Testing	1,800.00	
			9,300.00
	Special Bracket (Outdoor)	2,500.00	2,500.00
1	ACU 4.0HP (FLEX MATCH) 2ND SET		
	BEDROOM 1		
	FCU A 1.0HP Wall Mounted Inverter		
	Initial Charge	7,500.00	
	Leak Testing	1,800.00	
	Nema 3R	1,000.00	
			10,300.00
	BEDROOM 2		
	FCU B 1.0HP Wall Mounted Inverter		
	Initial Charge	7,500.00	
	Leak Testing	1,800.00	
			9,300.00

	MASTERS BEDROOM		
	FCU C 1.5HP Wall Mounted Inverter		
	Initial Charge	7,500.00	
	Leak Testing	1,800.00	
			9,300.00
	Special Bracket (Outdoor)	2,500.00	2,500.00
	TOTAL		53,500.00

NOTATION

Please make all payments payable to **MJRC AIRCONDITIONING SERVICES**

INSTALLATION INCLUSION:

- 1.Labor cost for back to back installation
- 2.Addiotnal copper tubing,rubber insulation,field or communication wiring and drain piping
- 3.Boring of holes through CHB wall up to 8 inches wall thickness and up to 4 inches diameter.
4. Installation of outdoor up to 6ft elevation.
- 5.Applicable to expose piping and drainage.
- 6.Polythelene tape covering the insulated refrigerant piping,wiring and drain piping.
- 7.Flexible hose insulating field / communicating wiring.

INSTALLATION EXCLUSION:

- 1.Extra installation work required by the customer (subject to additional charges which will be determined on the site)
- 2.Concrete chipping,glass cutting,wall plastering and restoration.
- 3.Circuit breaker and power connection from breaker to main source.
- 4.Ducting and Ventilation of outdoor unit.
- 5.Use of scaffolding for Overhead Installation.
- 6.Mechanical Plans,Building Permits,Electrical Permits.

THANK YOU FOR YOUR BUSINESS

Phoebe Masuba

Prepared by

Conformme