



August 18, 2025

ANGEL'S PIZZA - STA. ROSA BRANCH
UNIT 3 AND 4, STA. ROSA COMMERCIAL COMPLEX, DIAMOND RD, CITY OF SANTA ROSA, LAGUNA
ATTN: MR. KENNETH TANG
TEL#: 0917-8408138

Dear Ma'am/Sir,

Kolin Marketing Inc., is extremely honored for your endorsement of Kolin brand and we are please to offer you with a special price/s for the following items.

A. EQUIPMENT & INSTALLATION - **OPTION 1**

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
2	UNIT/S	MODEL: KSG-IWF-30WFF-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 29,500 Kj/h (3.0HP) FULL DC INVERTER W/ WIFI R-32	76,595.00	51,212.20	PHP	102,424.40
TOTAL UNIT COST					PHP	102,424.40
ESTIMATED COST OF INSTALLATION (please see attached)					PHP	85,975.00
OTHERS: DELIVERY CHARGE					PHP	600.00
TOTAL ESTIMATED COST OF THE PROJECT					PHP	188,999.40

TERMS OF PAYMENT:

FULL PAYMENT OF UNIT AND DELIVERY CHARGE. IF CHECK, SUBJECT FOR 3 DAYS CLEARING.

WARRANTY:

FOR SPLIT TYPE : ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB , TEN (10) YEARS WARRANTY ON COMPRESSOR.

NOTES: ***** Need to sign waiver agreement due to under capacity of unit choice.**

PRICES ARE SUBJECT TO CHANGE WITHOUT PRIOR NOTICE.

PRICES IS VAT INCLUSIVE.

**** Cost of Installation is Package with the Unit(s), this cost cannot avail separately (cost will be based on actual works).**

***** You may settle first payment for unit/s & delivery. Installation payment can be settled directly to installer after actual works.**

We thank you for giving opportunity to offer our product and services, hoping we receive your purchase order.

If you need assistance, don't hesitate to call the under signed at 0917-807-8607 or email at kmi_asst@kolinphil.com.ph

Very Truly Yours,

JANELLEN S. LIM
KMI-ASSISTANT

Noted by:

MARTIN HANUEL R. FLORES
KMI-SUPERVISOR

Approved By:

MS. EDITHA M. FLORES
AVP - FINANCE

KMI-QUOTE-08-25-0624
JCY-24%/7K

Conforme:


SIGNATURE OVER PRINTED NAME

Kolin Marketing, Inc.

1854 Sta. Rita St., Guadalupe Nuevo, Makati City

Tel.: (632) 8852-6473

Fax: (632) 8852-2170 / (632) 8852-4792

 www.kolinphil.com.ph / kolinphilippines.com



Airkohfrigus Refrigeration and Airconditioning Services

Blk 3, Lot 10, At dramam, Parian Calamba Laguna

Contact: 0939-2989-048

August 18, 2025

Attention: Angel's Pizza Sta Rosa Laguna Branch

We are pleased to submit our Quotation for Installation of Aircon units

Option 1: Copper Tube Exposed
2 units 3hp Wall Mounted Installation Only (Customer's Choice)

Total Square meter: 90 sq. meter Total Heat Load: 123,000KJ/Hr

Note: Client agreed that portion of open space at stair going to second floor where volume of heat is high be covered.

Note: Client has existing 2 units 3hp wall mounted inverter in the area under operation. The two units has already been considered in the horse power recommendation which sums up the total horse power requirement vis-à-vis total heat load.

1. Ground Floor

ACU#1 3HP Wall Mounted (Outdoor Unit located at Second Floor Service Area)

- Pipe length = 50 feet
- Royal Cord length = 50 feet

Initial Charges Includes:

1 st 10 feet Copper tube with Inclusion of 3/4 drain first 10ft, Communication wire first 10ft	P 8,500.00
Additional 3/4 Pvc drain (5pcs x 150)	P 750.00
Excess Tubing (40ft x 400 per foot)	P 16,000.00
Royal Cord for Electrical Supply 40ft @ 100 per foot	P 4,000.00
Additional Material for Electrical Supply (7pcs. 1/2 Orange PVC)	P 1,050.00
Outdoor Bracket (Special Bracket)	P 3,400.00
Electrical Supply (Main Panel to Outdoor Service Breaker) 15 meters x 300 per meter	P 4,500.00
Circuit Breaker (Breaker Box bolt on with breaker inclusion)	P 1,000.00

Total ACU#1 39,200.00

ACU#2 3HP Wall Mounted (Outdoor Unit located at Second Floor Service Area)

- Pipe length = 70 feet (Notes: Option 2 location of Indoor unit shall be followed)
- Royal Cord length = 70 feet

Initial Charges Includes:

1 st 10feet Copper tube with inclusion of $\frac{3}{4}$ drain first 10ft,	P 8,500.00
Communication wire first 10ft	P 750.00
Additional 3/4 Pvc drain (5pcs x 150)	P 24,000.00
Excess Tubing (60ftx400 per foot)	P 6,000.00
Royal Cord for Electrical Supply 60ft@100 per foot	P 1,350.00
Additional Material for Electrical Supply (9pcs. 1/2Orange PVC)	P 3,400.00
Outdoor Bracket (Special Bracket)	
Electrical Supply (Main Panel to Outdoor Service Breaker)21 metersx300 per meter	P 6,300.00
Circuit Breaker (Breaker Box bolt on with breaker inclusion)	P 1,000.00

Total ACU#2 51,300.00

Total: ACU#1 & 2	90,500.00
Less Discount: 5%	4,525.00
Grand Total:	85,975.00


Upon confirmation of the above quotation, Fifty (50) percent downpayment shall be paid, while the remaining balance shall be paid after installation and start-up of units.

For cheque payment, please issue payable to Airkohfrigus Refrigeration and Airconditioning Services, while for bank deposit please deposit to the following BPI account details:

Account Name: Cesar Pulga Parado

Account No. 3589-3366-19

Prepared by:


Cesar Pulga Parado
General Manager

Date: August,18,2025

Customer Name:Angel's Pizza Sta Rosa Laguna Branch

Address:Unit 3 and 4, Sta Rosa Commercial Complex, Diamond Rd, CITY OF SANTA ROSA, Laguna

Please be informed that the air-conditioner you intend to purchase is under capacity as compared to the following unit that we proposed:

Location	Area	Recommendation	Customer's Choice	Remarks
Ground Floor Dining	90 sqm	2 Units Floor Mounted (4HP)	2 units 3hp wall mounted	Total Head Load 123,000Kj/hr Recommedation 12.9HP Under Capacity by .95 HP

Since the unit of your choice is under capacity, it is probable that you may experience the following;

1. Capacity of the unit to cool the area will take longer or it will not cool the area at all that may lead to your dissatisfaction with the cooling performance of our unit.
2. Power consumption will be higher due to frequent running of compressor for not reaching the desired temperature within the normal parameter.
3. Useful life of compressor will be shortened due to excessive running beyond the normal run cycle.

Considering the above conditions, we regret to inform you that we cannot guarantee the efficient performance of unit. **Also, 5 year(s) compressor warranty.**

For your guidance and information

Prepared by:

CESAR PARADO

Signature over printed name