



August 6, 2025

MR. & MS. JG / TRINA SIMON  
52 WASHINGTON ST., MERVILLE PARK, BRGY. MERVILLE PARAÑAQUE CITY  
TEL#: 0967-1185333

Dear Ma'am/Sir,

Kolin Marketing Inc., is extremely honored for your endorsement of Kolin brand and we are please to offer you with a special price/s for the following items.

A. EQUIPMENT & INSTALLATION - **OPTION 1 (CUSTOMER'S CHOICE)**

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
3	UNIT/S	MODEL: KSG-IWF-30WFF-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 29,500 Kj/h (3.0HP) FULL DC INVERTER W/ WIFI R-32	76,595.00	51,212.20	PHP	153,636.60
1	UNIT/S	MODEL: KSG-IWF-25WFF-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 25,560 Kj/h (2.5HP) FULL DC INVERTER W/ WIFI R-32	68,995.00	45,436.20	PHP	45,436.20
1	UNIT/S	MODEL: KSG-IWF-20WFF-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 19,000 Kj/h (2.0HP) FULL DC INVERTER W/ WIFI R-32	59,595.00	38,292.20	PHP	38,292.20
TOTAL UNIT COST					PHP	237,365.00
ESTIMATED COST OF INSTALLATION (please see attached)					PHP	114,440.00
OTHERS: DELIVERY CHARGE					PHP	600.00
TOTAL ESTIMATED COST OF THE PROJECT					PHP	352,405.00

TERMS OF PAYMENT:

FULL PAYMENT OF UNIT AND DELIVERY CHARGE. IF CHECK, SUBJECT FOR 3 DAYS CLEARING.

WARRANTY:

FOR SPLIT TYPE : ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB , TEN (10) YEARS WARRANTY ON COMPRESSOR.

NOTES: \*\*\* Need to sign waiver agreement due to under capacity of unit choice.

PRICES ARE SUBJECT TO CHANGE WITHOUT PRIOR NOTICE.

PRICES IS VAT INCLUSIVE.

**\*\* Cost of Installation is Package with the Unit(s), this cost cannot avail separately (cost will be based on actual works).**

**\*\*\* You may settle first payment for unit/s & delivery. Installation payment can be settled directly to installer after actual works.**

We thank you for giving opportunity to offer our product and services, hoping we receive your purchase order.

If you need assistance, don't hesitate to call the under signed at 0917-807-8607 or email at kmi\_asst@kolinphil.com.ph

Very Truly Yours,

JANELLEN S. LIM  
KMI-ASSISTANT

Noted by:  
MART NATHANIEL R. FLORES  
KMI-SUPERVISOR

Approved By:

MS. EDITHA M. FLORES  
AVP - FINANCE

KMI-QUOTE-08-25-0598  
ADR-24%/7K

Conforme:

SIGNATURE OVER PRINTED NAME





**Airconditioning & Refrigeration Services**  
 B72 L22 17th., Brgy. 183 Villamor Pasay city Metro Manila 1300  
 Cellphone: 0917-1225048/ 0999-5573715  
 Email: zeusrafann053012@gmail.com / carcillaroffice01@gmail.com

\*SUPPLY

\*INSTALLATION

\*CHECK-UP

\*CLEANING

\*PREVENTIVE MAINTENANCE

### Installation Quotation

Simon, JG / Trina  
 52 Washington St., Merville Park, Brgy. Merville, PARAÑAQUE CITY  
 0967-1185333

August 01, 2025  
 AIQ 25-00025

Project name: Option 1: Installation of Kolin Aircon

Description		QTY			
ACU 1 (Master's Bedroom)	KSG-IWF-30WFF8K1M32	1			
	Estimated Pipe Length	=	23ft		
	Estimated Royal Cord Length	=	28ft		
Basic Installation (10ft copper tubing and communication wire)					8,500.00
Installation materials		Description	QTY	Price Per QTY	SubTotal
Copper Tubing (excess of 10ft)		1/4"X5/8" new	13ft	400/ft	5,200.00
Royal Cord (excess of 10ft)		2.00mm2X4C	18ft	100/ft	1,800.00
Wire (Royal Cord-Breaker to ODU)		3.5mmX3C	4ft	60/ft	240.00
PVC Blue Pipe		Blue pipe 3/4"	2pcs	200/pc	400.00
Circuit Breaker		30Amp. (NEMA 3RE-Single-Phase)	1pc	1000/pc	1,000.00
					8,640.00
TOTAL					17,140.00
ACU 2 (Guest Room)	KSG-IWF-20WFF8K1M32	1			
	Estimated Pipe Length	=	11ft		
	Estimated Royal Cord Length	=	16ft		
Basic Installation (10ft copper tubing and communication wire)					7,500.00
Installation materials		Description	QTY	Price Per QTY	SubTotal
Copper Tubing (excess of 10ft)		1/4"X1/2" new	1ft	350/ft	350.00
Royal Cord (excess of 10ft)		2.00mm2X4C	6ft	100/ft	600.00
Wire (Royal Cord-Breaker to ODU)		3.5mmX3C	4ft	60/ft	240.00
PVC Blue Pipe		Blue pipe 3/4"	1pc	200/pc	200.00
Circuit Breaker		30Amp. (NEMA 3RE-Single-Phase)	1pc	1000/pc	1,000.00
					2,390.00
TOTAL					9,890.00
ACU 3 (Bedroom 3)	KSG-IWF-30WFF8K1M32	1			
	Estimated Pipe Length	=	21ft		
	Estimated Royal Cord Length	=	26ft		
Basic Installation (10ft copper tubing and communication wire)					8,500.00
Installation materials		Description	QTY	Price Per QTY	SubTotal
Copper Tubing (excess of 10ft)		1/4"X5/8" new	11ft	400/ft	4,400.00
Royal Cord (excess of 10ft)		2.00mm2X4C	16ft	100/ft	1,600.00
Wire (Royal Cord-Breaker to ODU)		3.5mmX3C	4ft	60/ft	240.00
PVC Blue Pipe		Blue pipe 3/4"	2pcs	200/pc	400.00
Circuit Breaker		30Amp. (NEMA 3RE-Single-Phase)	1pc	1000/pc	1,000.00
					7,640.00
TOTAL					16,140.00
ACU 4 (Family Room)	KSG-IWF-25WFF8K1M32	1			
	Estimated Pipe Length	=	35ft		
	Estimated Royal Cord Length	=	40ft		
Basic Installation (10ft copper tubing and communication wire)					7,500.00
Installation materials		Description	QTY	Price Per QTY	SubTotal
Copper Tubing (excess of 10ft)		1/4"X1/2" new	25ft	350/ft	8,750.00
Royal Cord (excess of 10ft)		2.00mm2X4C	31ft	100/ft	3,100.00
Wire (Royal Cord-Breaker to ODU)		5.5mm x 3	4	60/ft	240.00
PVC Blue Pipe		Blue pipe 3/4"	2pc	200/pc	400.00
Circuit Breaker		30Amp. (NEMA 3RE-Single-Phase)	1pc	1000/pc	1,000.00
					13,490.00
TOTAL					20,990.00
ACU 5 (Dining Room)	KSG-IWF-30WFF8K1M32	2			
Unit 1					
	Estimated Pipe Length	=	39ft		
	Estimated Royal Cord Length	=	44ft		
Basic Installation (10ft copper tubing and communication wire)					8,500.00
Installation materials		Description	QTY	Price Per QTY	SubTotal
Copper Tubing (excess of 10ft)		1/4"X5/8" new	29ft	400/ft	11,600.00
Royal Cord (excess of 10ft)		2.00mm2X4C	34ft	100/ft	3,400.00
Wire (Royal Cord-Breaker to ODU)		5.5mm x 3	4	60/ft	240.00
PVC Blue Pipe		Blue pipe 3/4"	2pcs	200/pc	400.00
Circuit Breaker		30Amp. (NEMA 3RE-Single-Phase)	1pc	1000/pc	1,000.00

16,640.00

TOTAL

25,140.00

Unit 2

Estimated Pipe Length = 39ft  
Estimated Royal Cord Length = 44ft

Basic Installation (10ft copper tubing and communication wire)

8,500.00

Installation materials	Description	QTY	Price Per QTY	SubTotal
Copper Tubing (excess of 10ft)	1/4"X5/8" new	29ft	400/ft	11,600.00
Royal Cord (excess of 10ft)	2.00mm2X4C	34ft	100/ft	3,400.00
Wire (Royal Cord-Breaker to ODU)	5.5mm x 3	4	60/ft	240.00
PVC Blue Pipe	Blue pipe 3/4"	2pcs	200/pc	400.00
Circuit Breaker	30Amp. (NEMA 3RE-Single-Phase)	1pc	1000/pc	1,000.00

16,640.00

TOTAL

25,140.00

TOTAL CHARGES

114,440.00

Bank details

China Bank Corporation

Account Name: Carcellar Airconditioning and Refrigeration Services  
143602005343

GCASH

0999-5573715

Rafael Carcellar

Prepared by:

Melissa de Castro  
Office Admin

Conformed by:





**Airconditioning & Refrigeration Services**  
B72 L22 17th., Brgy. 183 Villamor Pasay city Metro Manila 1300  
Cellphone: 0917-1225048/ 0999-5573715  
mail: zeusrafann053012@gmail.com / carcillaroffice01@gmail.com

\*SUPPLY

\*INSTALLATION

\*CHECK-UP

\*CLEANING

\*PREVENTIVE MAINTENANCE

Date: August 04, 2025  
Customer Name: Simon, JG / Trina  
Complete Address: 52 Washington St., Merville Park, Brgy. Merville, PARAÑAQUE CITY  
Contact Number: 0967-1185333  
Email Address

Please be informed that the air-conditioner you intend to purchase is under capacity as compared to the following unit that we proposed:

Location	Area	Kolin's Recommendation	Customer's Choice	Remarks
Dining Room	70 sqm	1 unit 6.0HP FloorMounted and 1 unit 2.0HP Wall Mounted	2 Wall Mounted Split Type 3HP	7.9HP


Since the unit of your choice is under capacity, it is probable that you may experience the following;

1. Capacity of the unit to cool the area will take longer or it will not cool the area at all that may lead to your dissatisfaction with the cooling performance of our unit.
2. Power consumption will be higher due to frequent running of compressor for not reaching the desired temperature within the normal parameter.
3. Useful life of compressor will be shortened due to excessive running beyond the normal run cycle.

Considering the above conditions, we regret to inform you that we cannot guarantee the efficient performance of unit. **Also, One (1) year warranty for parts (compressor 3 years warranty) and labor.**

For your guidance and information

Prepared by:

  
Melissa de Castro

Name **Rafael Carcillar**  
Job Title **Surveyor/Head Technician**

Customer Conforme:  
Signature over Printed Name