



April 8, 2025

B&B DINING INC.  
138 KATIPUNAN ST., BRGY. ST. IGNATIUS, QUEZON CITY  
TEL#: 0906-6988716  
Email: regulatory@wplates.com

Dear Ma'am/Sir,

Kolin Marketing Inc., is extremely honored for your endorsement of Kolin brand and we are please to offer you with a special price/s for the following items.

A. EQUIPMENT & INSTALLATION

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
4	UNIT/S	MODEL: KSG-IWF-30WFI-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 29,500 Kj/h (3.0HP) FULL DC INVERTER W/ WIFI R-32	76,595.00	51,212.20	PHP	204,848.80
TOTAL UNIT COST					PHP	204,848.80
ESTIMATED COST OF INSTALLATION (please see attached)					PHP	147,070.00
OTHERS: DELIVERY CHARGE					PHP	600.00
TOTAL ESTIMATED COST OF THE PROJECT					PHP	352,518.80

TERMS OF PAYMENT:

FULL PAYMENT OF UNIT AND DELIVERY CHARGE. IF CHECK, SUBJECT FOR 3 DAYS CLEARING.

WARRANTY:

FOR SPLIT TYPE : ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB , TEN (10) YEARS WARRANTY ON COMPRESSOR.

NOTES: PRICES ARE SUBJECT TO CHANGE WITHOUT PRIOR NOTICE.


PRICES IS VAT INCLUSIVE.

**\*\* Cost of Installation is Package with the Unit(s), this cost cannot avail separately (cost will be based on actual).**


We thank you for giving opportunity to offer our product and services, hoping we receive your purchase order.

If you need assistance, don't hesitate to call the under signed at 0917-807-8607 or email at kmi\_asst@kolinphil.com.ph

Very Truly Yours,

  
JANELLE S. LHM  
KMI-ASSISTANT

Noted by:

  
MART NATHANIEL R. FLORES  
KMI-SUPERVISOR

Approved By:

  
MS. EDITHA M. FLORES  
AVP - FINANCE

KMI-QUOTE-04-25-0260  
REG-24%/7K

Conforme:

SIGNATURE OVER PRINTED NAME



APRIL 07, 2025

B&B Dining Inc.

138 Katipunan St. Brgy. St. Ignatius, Quezon City

0906-698-8716

regulatory@wplates.com

Model Qty  
KSG-IWF-30Wfy-8K1M32 4

GROUND FLOOR

DINING AREA	Area ≈ 50 sq.m
-------------	----------------

ACU 1 3.0hp Wallmounted Inverter KSG-IWF-30Wfy8K1M32  
Estimated Pipe Length : 60 ft  
Estimated Royal Cord Length : 65 ft  
Initial Charge P 8,500.00

Includes:

Labor  
10ft Copper Tube  
10ft Royal Cord  
Outdoor Bracket (wall)  
Other Consumables

Additional Charges	Description	Unit	Price Per Unit	Subtotal
Copper Tube	3/8"x 5/8"	50 ft	P 400.00 / ft	P 20,000.00
Royal Cord	2.mm2 x 4C	55 ft	P 100.00 / ft	P 5,500.00
Royal Cord (ODU-Breaker)	3.5mm2 x 3C	5 ft	P 60.00 / ft	P 300.00
Circuit Breaker(NEMA)	30A/ 1Ph	1 pc(s)	P 1,000.00 / pc	P 1,000.00
Rubber Insulation	2 1/8"x3/4" x	8 pc(s)	P 350.00 / pc	P 2,800.00
Full Thread	3 meters	1 pc(s)	P 150.00 / pc	P 150.00
Pipe hanger	3 inches	10 pc(s)	P 120.00 / pc	P 1,200.00
chipping works	1 meter	1 mtr	P 500.00 / pc	P 500.00
Drain Hose	White -1/2"	5 ft	P 25.00 / ft	P 125.00
				P 31,575.00

Estimated Charges	P 40,075.00
-------------------	-------------

ACU 2 3.0hp Wallmounted Inverter KSG-IWF-30Wfy8K1M32  
Estimated Pipe Length : 43 ft  
Estimated Royal Cord Length : 48 ft  
Initial Charge P 8,500.00

Includes:

Labor  
10ft Copper Tube  
10ft Royal Cord  
Outdoor Bracket  
Other Consumables

Additional Charges	Description	Unit	Price Per Unit	Subtotal
Copper Tube	3/8"x 5/8"	33 ft	P 400.00 / ft	P 13,200.00
Royal Cord	2.mm2 x 4C	38 ft	P 100.00 / ft	P 3,800.00
Royal Cord (ODU-Breaker)	3.5mm2 x 3C	5 ft	P 60.00 / ft	P 300.00
Circuit Breaker(NEMA)	30A/ 1Ph	1 pc(s)	P 1,000.00 / pc	P 1,000.00
Rubber Insulation	2 1/8"x3/4" x	6 pc(s)	P 350.00 / pc	P 2,100.00
Full Thread	3 meters	2 pc(s)	P 150.00 / pc	P 300.00
Pipe hanger	3 inches	8 pc(s)	P 120.00 / pc	P 960.00
chipping works	1 meter	1 mtr	P 500.00 / pc	P 500.00
Drain Hose	White -1/2"	5 ft	P 25.00 / ft	P 125.00
				P 22,285.00

Estimated Charges	P 30,785.00
-------------------	-------------

ACU 3     **3.0hp Wallmounted Inverter**     *KSG-IWF-30Wfy8K1M32*  
 Estimated Pipe Length :     63     ft  
 Estimated Royal Cord Length :     68     ft  
 Initial Charge     P     8,500.00

Includes:

Labor  
 10ft Copper Tube  
 10ft Royal Cord  
 Outdoor Bracket  
 Other Consumables

Additional Charges	Description	Unit	Price Per Unit	Subtotal
Copper Tube	3/8"x 5/8"	53 ft	P 400.00 / ft	P 21,200.00
Royal Cord	2.mm2 x 4C	58 ft	P 100.00 / ft	P 5,800.00
Royal Cord (ODU-Breaker)	3.5mm2 x 3C	5 ft	P 60.00 / ft	P 300.00
Circuit Breaker(NEMA)	30A/ 1Ph	1 pc(s)	P 1,000.00 / pc	P 1,000.00
Rubber Insulation	2 1/8"x3/4" x	6 pc(s)	P 350.00 / pc	P 2,100.00
Full Thread	3 meters	2 pc(s)	P 150.00 / pc	P 300.00
Pipe hanger	3 inches	8 pc(s)	P 120.00 / pc	P 960.00
chipping works	5 meter(drain)	5 mtr	P 500.00 / pc	P 2,500.00
PVC (drainline)	blue 3/4"	2 pc(s)	P 150.00 / pc	P 300.00
Drain Hose	White -1/2"	5 ft	P 25.00 / ft	P 125.00
				P 34,585.00

<b>Estimated Charges</b>	<b>P 43,085.00</b>
--------------------------	--------------------

SECOND FLOOR

<b>DINING AREA</b>	Area ≈ 23 sq.m
--------------------	----------------

ACU 4     **3.0hp Wallmounted Inverter**     *KSG-IWF-30Wfy8K1M32*  
 Estimated Pipe Length :     37     ft  
 Estimated Royal Cord Length :     44     ft  
 Initial Charge     P     8,500.00

Includes:

Labor  
 10ft Copper Tube  
 10ft Royal Cord  
 Outdoor Bracket (wall)  
 Other Consumables

Additional Charges	Description	Unit	Price Per Unit	Subtotal
Copper Tube	1/4"x 5/8"	27 ft	P 400.00 / ft	P 10,800.00
Royal Cord	2.mm2 x 4C	34 ft	P 100.00 / ft	P 3,400.00
Royal Cord (ODU-Breaker)	3.5mm2 x 3C	5 ft	P 60.00 / ft	P 300.00
Circuit Breaker(NEMA)	30A/ 1Ph	1 pc(s)	P 1,000.00 / pc	P 1,000.00
Rubber Insulation	2 1/8"x3/4" x	6 pc(s)	P 350.00 / pc	P 2,100.00
Full Thread	3 meters	1 pc(s)	P 150.00 / pc	P 150.00
Pipe hanger	3 inches	10 pc(s)	P 120.00 / pc	P 1,200.00
Scaffoldings	3sets	1 del	P 1,500.00 / pc	P 1,500.00
chipping works	1 meter	1 del	P 500.00 / pc	P 500.00
Drain pump	realise	1 pc(s)	P 2,900.00 / pc	P 2,900.00
Drain Hose(for drainpump)	green- 1/4"	35 ft	P 10.00 / pc	P 350.00
PVC (drainline)	blue 3/4"	2 pc(s)	P 150.00 / pc	P 300.00
Drain Hose	White -1/2"	5 ft	P 25.00 / ft	P 125.00
				P 24,625.00

<b>Estimated Charges</b>	<b>P 33,125.00</b>
--------------------------	--------------------



Validity: This quotation is valid for a period of fifteen (15) days from the date thereof, subject to our confirmation thereafter.

**Note:**

- 1 Location of indoor and outdoor units were agreed by the customer and Kolin's surveyor.
- 2 AC drain line will be tapped to the nearest drain provision provided by the customer's contractor.
- 3 Need for marking and site visit before installation and open the ceiling for the lay out of copper tube.
- 4 Customer contractor will finish/restore the chip wall.
- 5 All Units need to operate at the same time to avoid undercapacity.
- 6 Working days: Monday to Saturday, 8am- 5pm with parking. 4 pax. Bring harness and rope.
- 7 Mechanical Plans, Permits, Electrical permits not included.
- 8 Deflectors, masonry, carpentry, chipping & plastering (finishing & restoration) are not included in the installation.
- 9 Electrical power supply (feeder line) **220v/ 60hz/ 1ph**, is not included in the scope of work of Kolin.
- 10 Final charges will be based on actual installation.

Prepared by:

Jeffrey Dadios

Field Surveyor

Customer Conformer:

\_\_\_\_\_  
Signature Over Printed Name

Reviewed by:

Engr. Kenneth Zamora

Service Supervisor

Field and Shop Operation

