



August 13, 2025

MS. MIDA SY
10C LAS VEGAS ST., MERVILLE PARK SUBD., BRGY. MERVILLE, PARAÑAQUE CITY
TEL#: 0961-6112576

Dear Ma'am/Sir,

Kolin Marketing Inc., is extremely honored for your endorsement of Kolin brand and we are please to offer you with a special price/s for the following items.

A. EQUIPMENT & INSTALLATION

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
1	UNIT/S	MODEL: KLG-IF40-5G1M32 KOLIN FLOOR MOUNTED AIRCONDITIONER 37,980 Kj/h (3.0TR) FULL DC INVERTER R-32 SINGLE PHASE	113,195.00	79,028.20	PHP	79,028.20
1	UNIT/S	MODEL: KAG-200WCINV KOLIN WINDOW TYPE QUAD SERIES AIRCONDITIONER 19,080 Kj/h (2.0HP) FULL DC INVERTER W/ WIFI R-32 (WxDxH) 26"x28"x17"	43,595.00	31,332.20	PHP	31,332.20
TOTAL UNIT COST					PHP	110,360.40
ESTIMATED COST OF INSTALLATION (please see attached) w/ installation of existing unit					PHP	15,580.00
OTHERS: DELIVERY CHARGE					PHP	600.00
TOTAL ESTIMATED COST OF THE PROJECT					PHP	126,540.40

* OTHER OPTION FOR WINDOW TYPE *

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
1	UNIT/S	MODEL: KA-200MCARINV32 KOLIN WINDOW TYPE CREO SERIES AIRCONDITIONER 19,800 Kj/h (2.0HP) FULL DC INVERTER R-32 WITH REMOTE (WxDxH) 26"x30.7"x16.8"	36,995.00	26,916.20	PHP	26,916.20

TERMS OF PAYMENT:

FULL PAYMENT OF UNIT AND DELIVERY CHARGE. IF CHECK, SUBJECT FOR 3 DAYS CLEARING.

WARRANTY:

FOR FLOOR MOUNTED (Inverter): ONE (1) YEAR FREE PARTS AND LABOR, FIVE (5) YEARS WARRANTY ON COMPRESSOR.

FOR WINDOW TYPE: ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB, TEN (10) YEARS WARRANTY ON COMPRESSOR.

NOTES: PRICES ARE SUBJECT TO CHANGE WITHOUT PRIOR NOTICE.

PRICES IS VAT INCLUSIVE.

** Cost of Installation is Package with the Unit(s), this cost cannot avail separately (cost will be based on actual works).

*** You may settle first payment for unit/s & delivery. Installation payment can be settled directly to installer after actual works.

We thank you for giving opportunity to offer our product and services, hoping we receive your purchase order.

If you need assistance, don't hesitate to call the under signed at 0917-807-8607 or email at kmi_asst@kolinphil.com.ph

Very Truly Yours,

JANELLEN S. LIM
KMI-ASSISTANT

Noted by:
MART NATHANIEL R. FLORES
KMI-SUPERVISOR

Approved By:

MS. EDITHA M. FLORES
AVP - FINANCE

Conforme:

SIGNATURE OVER PRINTED NAME

KMI-QUOTE-08-25-0614
NG-24%/7K/1.8K/1.2K

Kolin Marketing, Inc.

1854 Sta. Rita St., Guadalupe Nuevo, Makati City

Tel.: (632) 8852-6473

Fax: (632) 8852-2170 / (632) 8852-4792

www.kolinphil.com.ph / kolinphilippines





Airconditioning & Refrigeration Services
B72 L22 17th., Brgy. 183 Villamor Pasay city Metro Manila 1300
Cellphone: 0917-1225048/ 0999-5573715
Email: zeusrafann053012@gmail.com / carcillaroffice01@gmail.com

*SUPPLY

*INSTALLATION

*CHECK-UP

*CLEANING

*PREVENTIVE MAINTENANCE

Installation Quotation

Sy, Mida
10C. Las Vegas St. Merville Park Subd., Brgy. Merville, PARAÑAQUE CITY
9616112576

August 09, 2025
AIQ 25-00031

Project name: Installation of New Kolin Split Type Aircon

Description		QTY			
ACU 1 (Living Room)	Floor Mounted 4HP	1			
	Estimated Pipe Length	10ft			
	Estimated Royal Cord Length	15ft			
Basic Installation (10ft copper tubing and communication wire)					11,000.00
Installation materials		Description	QTY	Price Per QTY	SubTotal
	Royal Cord	2.00mm2X4C	5ft	100/ft	500.00
	Wire (Royal Cord-Breaker to ODU)	5.5mmX3C	3ft	60/ft	180.00
	PVC Blue Pipe	Blue pipe 3/4"	2pcs	200/pc	400.00
	PVC Drain Pipe	3/4x3m Blue	3pcs	200/pc	600.00
	Circuit Breaker 40A		1	1000/pc	1,000.00
					2,680.00
ACU 2 (Guest Room)	Window Type 1.5 HP	- existing unit			
	Installation + Gap Sealant				
					1,200.00
ACU 3 (Master's Bedroom)	Window Type 1.5 HP				
	Installation + Gap Sealant				
					1,200.00
Less Survey Fee					-500.00
TOTAL CHARGES					15,580.00

Note: Guest Room (ACU 2) has an existing 1.5HP (different brand). For the Master's Bedroom (ACU 3), the client specifically requested a 2HP unit.

Remarks: Should this proposal meet your approval, kindly confirm by signing below. Installation will commence upon confirmation.

Bank details

China Bank Corporation

Account Name: Carcillar Airconditioning and Refrigeration Services
143602005343

GCASH

0999-5573715

Rafael Carcillar

Prepared by:

Melissa de Castro
Office Admin

Conformed by:



CARCILLAR

Airconditioning & Refrigeration Services

872 L22 17th., Brgy. 183 Villamore Pasay city Metro Manila 1300

Cellphone: 09995573715

Tel#: (02) 8253-4637

Email: zeusrafann053012@gmail.com

SURVEY SUPPLY INSTALLATION CHECK-UP CLEANING REPAIR/MAINTENANCE

SURVEY FORM

Customer Name: SY MIRA Date: 8-1-25
Address: 106 LAL VELAZ CT - Imbrolu SJR No: _____

Establishment Type: Residential ☒ Commercial ☐ Area Surveyed: _____
Area Surveyed: _____

Recommended Product Model: Sharp Primeus 4HP 7M

Cooling Capacity Computation

Floor Area: 55 sqm
Ceiling Height: _____ mtr

note: add 20% per meter in excess of 3 meters in the initial cooling capacity computed

Floor Area	<u>55</u>	x	550 Btu/h	<u>30,250</u> Btu/h
Ceiling Height (excess of 3 mtrs.)		x	20%	Btu/h
Window Direct Sunlight		x	20% - 50%	Btu/h
Total Cooling Capacity				Btu/h

Add : Additional Heat Load

No. of Person	<u>5</u>	x	300 Btu/h	<u>1500</u> Btu/h
No. of Ordinary Light (<40w)	<u>16</u>	x	200 Btu/h	<u>3200</u> Btu/h
No. of Special Light (>40w)		x	400 Btu/h	Btu/h
No. of Refrigerator (< 6 cu ft.)	<u>1</u>	x	400 Btu/h	<u>400</u> Btu/h
No. of Refrigerator (> 6 cu ft.)		x	500 Btu/h	Btu/h
No. of Cooking Range		x	1500 Btu/h	Btu/h
No. of Laptop Computer		x	150 Btu/h	Btu/h
No. of Desktop Computer		x	400 Btu/h	Btu/h
Network Printer		x	500 Btu/h	Btu/h
No. of Photocopier		x	1000 Btu/h	Btu/h
Total Cooling Capacity				<u>35,250</u> Btu/h

Recommended Cooling Capacity

3.9hr Btu/h

Note : Compressor warranty will be reduced to _____ yr. if air-conditioner purchased is lower than the recommended cooling capacity or pipe lay-out is beyond the maximum allowable length

Scope of Work Agreement

- | | | |
|------------------------------------|--|--|
| 1. Copper tube lay-out | ☒ Expose | ☐ Embedded |
| 2. Chipping | ☐ Included | ☒ Not Included |
| 3. Fabricated Bracket | ☐ Yes ☐ Shop | ☐ Site ☒ No |
| 4. Service Ledge | ☐ Yes | ☐ No |
| 5. Dismantling of existing Aircon. | ☐ Included | ☒ Not Included |
| 6. Ducting | ☐ Yes | ☐ No |

Dimension :

- Plastering, carpentry and restoration works are to be done by the customer
- Wiring of electrical supply from main panel to air-conditioning unit are to be done by the customer
- Processing of mechanical plan, working permit, electrical permit are to be done by the customer
- Other concern: _____



Airconditioning & Refrigeration Services

872 L22 17th., Brgy. 183 Villamor Pasay city Metro Manila 1300

Cellphone: 09995573715

Tel: (02) 8253-4637

Email: zeusrafael053012@gmail.com

CARCILLAR

SURVEY FORM

Plan Lay-out

Indoor Unit Location

Outdoor Unit Location

Pipe Length

Special Note

Installation Cost Estimate

Material Description	Qty	Unit Cost	Total Cost
Copper Tube (excess of 10 ft.)	2330 2430 2520 3520 4620		
Wire (Royal Cord-signal wire) (excess of 10R)	2 0mmx4C		
Wire (Royal Cord - Breaker to ODU)	3 5mm x 5 5mm x 3C		
Circuit Breaker	20A 30A 40A/1ph 50A/1ph		
Bracket (ODU)	(Imptd / Fabricated) (1/2" / 3/4")		
Bracket (I/U)	Angle 1/2" / 3/4"		
PVC Pipe (drain)	1/2" / 3/4"		
PVC Pipe (electrical)	1/2" / 3/4"		
Drain Pump			
Drain Pump Hose			
Clipping Works	mt		
Discharging Fee (existing air conditioner)			
Initial Charge	1	12,500	12,500
TOTAL ESTIMATE	P	14780	

Note:

- Initial Charge includes labor, 10R Copper tube, 10R Royal cord, Circuit breaker, outdoor Bracket (SAC), indoor Bracket (PAC) and Consumable materials.
- Survey fee will be deducted in the installation fee.

Prepared by:

Louis Carlos Amador
Signature Over Printed Name

Customer Confirms

Signature Over Printed Name

KL6-1#40-5G/m32
SALA



CARCILLAR

Airconditioning & Refrigeration Services

872 L22 17th, Brgy. 183 Villamore Pasay city Metro Manila 1300

Cellphone: 09995573715

Tel: (02) 8253-4637

Email: zeusrafann053012@gmail.com

SURVEY FORM

Customer Name SY MIDA Date 8-9-25
Address 10 C LAS VEGAS ST, MERULU SJR No. _____

Establishment Type Residential ☒ Commercial ☐ Area Surveyed GUEST RM
Area Surveyed _____

Recommended Product Model: 1.5HP, EXISTING AIRCON AND DUCTWORK

Cooling Capacity Computation

Floor Area 17.58 sqm
Ceiling Height _____ mtr
note: add 20% per meter in excess of 3 meters in the initial cooling capacity computed

Floor Area	<u>17.58</u>	x	550 Btu/h	<u>9,669</u> Btu/h
Ceiling Height (excess of 3 mtrs.)		x	20%	Btu/h
Window Direct Sunlight		x	20% - 50%	Btu/h
Total Cooling Capacity				Btu/h

Add : Additional Heat Load

No. of Person	<u>1</u>	x	300 Btu/h	<u>300</u> Btu/h
No. of Ordinary Light (<40w)	<u>5</u>	x	200 Btu/h	<u>1000</u> Btu/h
No. of Special Light (>40w)		x	400 Btu/h	Btu/h
No. of Refrigerator (< 6 cu ft)		x	400 Btu/h	Btu/h
No. of Refrigerator (> 6 cu ft)		x	800 Btu/h	Btu/h
No. of Cooking Range		x	1500 Btu/h	Btu/h
No. of Laptop Computer		x	150 Btu/h	Btu/h
No. of Desktop Computer		x	400 Btu/h	Btu/h
No. of Printer		x	500 Btu/h	Btu/h
No. of Photocopier		x	1000 Btu/h	Btu/h
Total Cooling Capacity				<u>10,969</u> Btu/h

Recommended Cooling Capacity

1.2hp (Btu/h)

Note : Compressor warranty will be reduced to _____ yr. if air-conditioner purchased is lower than the recommended cooling capacity or pipe lay-out is beyond the maximum allowable length.

Scope of Work Agreement

1. Copper tube lay-out	☐ Expose	☒ Embedded
2. Chipping	☐ Included	☒ Not Included
3. Fabricated Bracket	☐ Yes ☒ Shop	☐ Site ☒ No
4. Service Ledge	☐ Yes	☐ No
5. Dismantling of existing Aircon	☒ Included	☐ Not Included
6. Ducting	☐ Yes	☒ No

Dimension :

- Plastering, carpentry and restoration works are to be done by the customer.
- Wiring of electrical supply from main panel to air-conditioning unit are to be done by the customer.
- Processing of mechanical plan, working permit, electrical permit are to be done by the customer.
- Other concern: _____

may existing unit si client na 1.5hp
Guest room



Airconditioning & Refrigeration Services

872 L22 17th, Brgy. 183 Villamore Pasay city Metro Manila 1300

Cellphone: 09995573715

Tel# (02) 8253-4637

Email: reusafant053012@gmail.com

SURVEY FORM

Customer Name SY, MIDA Date 8-9-25
 Address 100 LAS VEGAS ST., MERVILLE PARK
 Establishment Type Residential ☒ Commercial ☐ Area Surveyed MASTER Rm
 Recommended Product Model: 1.5hp but client want 2hp WT

Cooling Capacity Computation

Floor Area 17.28 sqm
 Ceiling Height 2.8 mtr

Note: add 20% per meter in excess of 3 meters in the initial cooling capacity computed

Floor Area	<u>17.28</u>	x	550 Btu/h	<u>9,504</u> Btu/h
Ceiling Height (excess of 3 mtrs.)		x	20%	
Window Direct Sunlight		x	20% - 50%	
Total Cooling Capacity				

Add : Additional Heat Load

No. of Person	<u>2</u>	x	300 Btu/h	<u>600</u> Btu/h
No. of Ordinary Light (<40w)	<u>5</u>	x	200 Btu/h	<u>1000</u> Btu/h
No. of Special Light (>40w)		x	400 Btu/h	
No. of Refrigerator (< 6 cu ft.)		x	400 Btu/h	
No. of Refrigerator (> 6 cu ft.)		x	800 Btu/h	
No. of Cooking Range		x	1500 Btu/h	
No. of Laptop Computer		x	150 Btu/h	
No. of Desktop Computer		x	400 Btu/h	
No. of Printer		x	500 Btu/h	
No. of Photocopier		x	1000 Btu/h	
Total Cooling Capacity				<u>11,104</u> Btu/h

Recommended Cooling Capacity

Note : Compressor warranty will be reduced to ___ yr. if air-conditioner purchased is lower than the recommended cooling capacity or pipe lay-out is beyond the maximum allowable length

Scope of Work Agreement

1. Copper tube lay-out	☐ Expose	☐ Embedded
2. Chipping	☐ Included	☐ Not Included
3. Fabricated Bracket	☐ Yes ☐ No	☐ Site ☐ No
4. Service Ledge	☐ Yes	☐ No
5. Dismantling of existing Aircon	☐ Included	☐ Not Included
6. Ducting	☐ Yes	☐ No

Dimension :

- Plastering, carpentry and restoration works are to be done by the customer
- Wiring of electrical supply from main panel to air-conditioning unit are to be done by the customer
- Processing of mechanical plan, working permit, electrical permit are to be done by the customer
- Other concern:

* client want 2hp new

* drying room has ceiling fan
 * Master room



Email: reuscafano053012@gmail.com

Signature Over Printed Name