

August 13, 2025  
 ATTY . PETER SUCHIANGCO  
 119 Aquarius St, Cinco Hermanos, Marikina City  
 0966-624999/ 0922-814271  
[rdmtech.88@gmail.com](mailto:rdmtech.88@gmail.com)

MODEL	Qty
KSM-IW20-WCT10M1M32	1
KSM-IW20-4F1M	1

**SWAPPING OF UNITS FROM 34 C LIBRA ST. TO #119 AQUARIUS ST.**


<b>BEDROOM 1/ELLAS ROOM 119 AQUARIUS ST.</b>		Area	20 sqm
ACU 1	2.0HP Wall Mounted Inverter	<b>KSM-IW20-WCT10M1M32</b>	
	Initial Charge		₱ 7,300.00
	Includes:		
	Labor		Dismantle and
	Consumables		Installation
<b>Estimated Charges</b>			<b>₱ 7,300.00</b>

<b>MASTER BEDROOM 34 C LIBRA ST.</b>		Area	0 sqm
ACU 2	2.0HP Wall Mounted Inverter	<b>KSM-IW20-4F1M</b>	
	Estimated Pipe Length = 27 ft		
	Estimated Royal Cord Length = 32 ft		
	Initial Charge		₱ 7,300.00
	Includes:		
	Labor		Dismantle and
	Consumables		Installation
<b>Installation Materials</b>	<b>Description</b>	<b>Qty</b>	<b>Price per qty</b>
Copper Tube	Ø 1/4" x Ø 1/2"	27 ft	₱ 350.00/ft
Royal Cord (comm. wire)	2 mm2 x 4C	34 ft	₱ 100.00/ft
Rubber Insulation	2 1/8" x 3/4" x 6'	2 pc/s	₱ 350.00/pc
			₱ 9,450.00
			₱ 3,400.00
			₱ 700.00
			<b>₱ 13,550.00</b>
<b>Estimated Charges</b>			<b>₱ 20,850.00</b>
<b>Total Estimated Charges</b>			<b>₱ 28,150.00</b>

**Validity:** This quotation is valid for a period of fifteen (15) days from the date thereof, subject to our confirmation thereafter.


**Installation notes:**

- 1 Location of indoor and outdoor units agree by customer and kolin surveyor.
- 2 AC drain line will be tapped to the nearest drain provision provided by the customer's contractor.
- 3 ACU1 and ACU2 swapping of units. Indoor and Outdoor From 34c libra St. to 119 Aquarius St. and Vice versa.**
- 4 Need to dismantle and chipping at wall for new coppertube lay out for **ACU2**.
- 5 Working days: Monday to Saturday, 8am- 5pm with parking.Need working permit.
- 6 Mechanical Plans, Permits, Electrical permits not included.
- 7 Deflectors, masonry, carpentry, chipping & plastering (finishing & restoration) are not included in the installation.
- 8 Air conditioning drain line and Electrical power supply (feeder line) **220v/ 60hz/ 1ph** , should be provided by customer's contractor.
- 9 Final charges will be based on actual installation.**

Prepared by:  
  
**Jeffrey Dadios**  
 Field Surveyor

Customer Conformee:

\_\_\_\_\_  
 Signature Over Printed Name

Reviewed by:  
  
**Engr. Kenneth Zamora**  
 Service Supervisor Shop and  
 Field Operation