



August 6, 2025

MS. KATE GOMEZ
62 KARUHATAN ROAD, VALENZUELA CITY
TEL#: 0917-1474191

Dear Ma'am/Sir,

Kolin Marketing Inc., is extremely honored for your endorsement of Kolin brand and we are please to offer you with a special price/s for the following items.

A. EQUIPMENT & INSTALLATION - **OPTION 2**

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
1	UNIT/S	MODEL: KL-IF60-G6H1M32 KOLIN FLOOR MOUNTED AIRCONDITIONER 58,140 Kj/h (5.0TR) FULL DC INVERTER R32 SINGLE PHASE	165,995.00	115,476.10	PHP	115,476.10
2	UNIT/S	MODEL: KSG-IWF-30WFY-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 29,500 Kj/h (3.0HP) FULL DC INVERTER W/ WIFI R-32	76,595.00	52,744.10	PHP	105,488.20
2	UNIT/S	MODEL: KSG-IWF-20WFY-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 19,000 Kj/h (2.0HP) FULL DC INVERTER W/ WIFI R-32	59,595.00	39,484.10	PHP	78,968.20
1	UNIT/S	MODEL: KSG-IWF-15WFY-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 12,960 Kj/h (1.5HP) FULL DC INVERTER W/ WIFI R-32	46,595.00	29,344.10	PHP	29,344.10
TOTAL UNIT COST					PHP	329,276.60
ESTIMATED COST OF INSTALLATION (please see attached)					PHP	129,610.00
OTHERS: DELIVERY CHARGE					PHP	600.00
TOTAL ESTIMATED COST OF THE PROJECT					PHP	459,486.60

TERMS OF PAYMENT:

FULL PAYMENT OF UNIT AND DELIVERY CHARGE. IF CHECK, SUBJECT FOR 3 DAYS CLEARING.

WARRANTY:

FOR FLOOR MOUNTED (Inverter): ONE (1) YEAR FREE PARTS AND LABOR, FIVE (5) YEARS WARRANTY ON COMPRESSOR.
FOR SPLIT TYPE : ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB , TEN (10) YEARS WARRANTY ON COMPRESSOR.

NOTES: PRICES ARE SUBJECT TO CHANGE WITHOUT PRIOR NOTICE.

PRICES IS VAT INCLUSIVE.

** Cost of Installation is Package with the Unit(s), this cost cannot avail separately (cost will be based on actual works).

*** You may settle first payment for unit/s & delivery. Installation payment can be settled directly to installer after actual works.

We thank you for giving opportunity to offer our product and services, hoping we receive your purchase order.

If you need assistance, don't hesitate to call the under signed at 0917-807-8607 or email at kmi_asst@kolinphil.com.ph

Very Truly Yours,

JANELLEN S. LIM
KMI-ASSISTANT

Noted by:
MART NATHANIEL R. FLORES
KMI-SUPERVISOR

Approved By:

MS. EDITHA M. FLORES
AVP - FINANCE

KMI-QUOTE-08-25-0601
NG-22%/14K/7K

Conforme:

SIGNATURE OVER PRINTED NAME

Kolin Marketing, Inc.

1854 Sta. Rita St., Guadalupe Nuevo, Makati City

Tel.: (632) 8852-6473

Fax: (632) 8852-2170 / (632) 8852-4792

www.kolinphil.com.ph / kolinphilippines





ELECTRO MECHANICAL SERVICES

KATE GOMEZ

62 Karuhatan Road, Valenzuela City.

Date: August 06, 2025

Quotation Number: KEMSV 072025-00053

SUBJECT: Quotation for Installation of Air Conditioner

SJR No. 9234

We are pleased to present our quotation for the following service subject to the terms & conditions set forth hereunder:

I. MATERIALS :

Location : FCU 1 **Manager's Room**

Type : Wall Mounted Split Type 2.0HP- Kolin

Pipe Length : 34 Ft.

Wire Length : 41 Ft.

Initial Charge :

: Included

10 Ft. Copper Pipe 1/4x1/2
10 Ft. ThnnWire 2.0mm2x4c
Labor and other consumables

Php 6,700.00

: Excess

24 Ft. Copper Pipe 1/4x1/2 350 /Ft. Php 8,400.00
31 Ft. ThnnWire 2.0mm2x4c 100 /Ft. Php 3,100.00
7 Ft. ThnnWire 3.5mm2x2c 60 /Ft. Php 420.00
1 Pc. Circuit Breaker 30 Amp 1000 /Pc. Php 1,000.00
Fabricated Bracket (c/o Customer)

Php 12,920.00

FCU1 Installation Cost: Php 19,620.00

Location : FCU 2 **Conference Room**

Type : Wall Mounted Split Type 2.0HP- Kolin

Pipe Length : 20 Ft.

Wire Length : 27 Ft.

Initial Charge :

: Included

10 Ft. Copper Pipe 1/4x1/2
10 Ft. ThnnWire 2.0mm2x4c
Labor and other consumables

Php 6,700.00

: Excess

10 Ft. Copper Pipe 1/4x1/2 350 /Ft. Php 3,500.00
17 Ft. ThnnWire 2.0mm2x4c 100 /Ft. Php 1,700.00
7 Ft. ThnnWire 3.5mm2x2c 60 /Ft. Php 420.00
1 Pc. Circuit Breaker 30 Amp 1000 /Pc. Php 1,000.00
Fabricated Bracket (c/o Customer)

Php 6,620.00

FCU2 Installation Cost: Php 13,320.00

Location : FCU 3 **Admin Office**

Type : Wall Mounted Split Type 3.0HP- Kolin

Pipe Length : 42 Ft.

Wire Length : 49 Ft.

Initial Charge :

: Included

10 Ft. Copper Pipe 1/4x5/8
10 Ft. ThnnWire 2.0mm2x4c
Labor and other consumables

Php 7,700.00

: Excess

32 Ft. Copper Pipe 1/4x5/8 400 /Ft. Php 12,800.00
39 Ft. ThnnWire 2.0mm2x4c 100 /Ft. Php 3,900.00
7 Ft. ThnnWire 3.5mm2x2c 60 /Ft. Php 420.00
1 Pc. Circuit Breaker 30 Amp 1000 /Pc. Php 1,000.00
Fabricated Bracket (c/o Customer)

Php 18,120.00

FCU3 Installation Cost: Php 25,820.00

MAIN OFFICE:

KENGIE ELECTRO MECHANICAL SERVICES

Unit 8, Gen T. De Leon Commercial Complex Karuhatan,
Valenzuela City.

Land Number: 02 7623 9392

Mobile Number: 09175170189, 09360544485

Email Add: kengie10818@gmail.com

kemtsv1215@gmail.com

BRANCH OFFICE: CAGAYAN VALLEY

KENGIE ELECTRO MECHANICAL SERVICES

24 San Rafael St. Centro Amulung, Cagayan Valley

Mobile Number: 09453092426

Email Add: kengieservicescagayan@gmail.com

Location : FCU 4 Admin Office
Type : Wall Mounted Split Type 3.0HP- Kolin
Pipe Length : 49 Ft.
Wire Length : 56 Ft.

Initial Charge :

: Included

10 Ft. Copper Pipe 1/4x5/8
10 Ft. ThnnWire 2.0mm2x4c
Labor and other consumables

Php 7,700.00

: Excess

39 Ft. Copper Pipe 1/4x5/8 400 /Ft. Php 15,600.00
46 Ft. ThnnWire 2.0mm2x4c 100 /Ft. Php 4,600.00
7 Ft. ThnnWire 3.5mm2x2c 60 /Ft. Php 420.00
1 Pc. Circuit Breaker 30 Amp 1000 /Pc. Php 1,000.00
Fabricated Bracket (c/o Customer)

Php 21,620.00

FCU4 Installation Cost: Php 29,320.00

Location : FCU 5 Admin Office
Type : Floor Mounted 5.0HP- Kolin
Pipe Length : 40 Ft.
Wire Length : 47 Ft.

Initial Charge :

: Included

10 Ft. Copper Pipe 3/8x5/8
10 Ft. ThnnWire 2.0mm2x4c
Labor and other consumables

Php 13,200.00

: Excess

30 Ft. Copper Pipe 3/8x5/8 400 /Ft. Php 12,000.00
37 Ft. ThnnWire 2.0mm2x4c 100 /Ft. Php 3,700.00
7 Ft. ThnnWire 5.5mm2x2c 70 /Ft. Php 490.00
1 Pc. Circuit Breaker 60 Amp 1000 /Pc. Php 1,000.00
Fabricated Bracket (c/o Customer)

Php 17,190.00

FCU5 Installation Cost: Php 30,390.00

Location : FCU 6 Pantry
Type : Wall Mounted Split Type 1.5HP- Kolin
Pipe Length : 15 Ft.
Wire Length : 22 Ft.

Initial Charge :

: Included

10 Ft. Copper Pipe 3/8x1/4
10 Ft. ThnnWire 2.0mm2x4c
Labor and other consumables

Php 6,700.00

: Excess

5 Ft. Copper Pipe 1/4x3/8 350 /Ft. Php 1,750.00
12 Ft. ThnnWire 2.0mm2x4c 100 /Ft. Php 1,200.00
7 Ft. ThnnWire 3.5mm2x2c 70 /Ft. Php 490.00
1 Pc. Circuit Breaker 20 Amp 1000 /Pc. Php 1,000.00
Fabricated Bracket (c/o Customer)

Php 4,440.00

FCU6 Installation Cost: Php 11,140.00

Total Project Installation Cost : Php 129,610.00
Vat Included

II. VALIDITY DATE:

Quotation - Thirty (30) days only.

III. TERMS OF PAYMENT:

50% Down Payment

50% Full Payment Upon Completion

Note: 1. Aging of the payment is based on the billing statement date.

2. Price is subject to change without prior notice.

3. Bank transfer/ cash or dated check (subject for clearing).

IV. BANK DETAILS:

Chinabanking Corporation

Account Name: Kengie Electro Mechanical Services

Account Number: 112400002269

V. WARRANTY:

One (1) Year parts of airconditioner

One (1) Year labor and installation materials of airconditioner

VI. REMARKS:

1. Mansory, carpentry, chipping and palstering (Finishing or retouch) are not included in the scope of works.
2. Electrical power supply (Feeder line) are not included in the scope of works.
3. Aircon drain line will be tapped to the nearest drain line provision/ downspout pipe.


Mirriam Asis
Service Coordinator Head

For:


MIRRIAM ASIS
Service Coordinator
Kenneth C. Siubal
General Manager


Queenie Cantillon
Service Coordinator Staff