



February 20, 2025

E-LITES INNOVATION CONSTRUCTION CORP.
ATTN: MR. ERIK MOYO

Dear Ma'am/Sir,

Kolin Marketing Inc., is extremely honored for your endorsement of Kolin brand and we are please to offer you with a special price/s for the following items.

A. EQUIPMENT

**** OPTION 2**

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
3	UNIT/S	MODEL: KSG-IWF-30WFF-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 29,500 Kj/h (3.0HP) FULL DC INVERTER W/ WIFI R-32	76,595.00	51,212.20	PHP	153,636.60
2	UNIT/S	MODEL: KSM-IW20-WCT10M1M32 KOLIN WALL MOUNTED CERTUS SERIES AIRCONDITIONER 18,990 Kj/h (2.0HP) REGULAR INVERTER R-32	41,995.00	27,916.20	PHP	55,832.40
1	UNIT/S	MODEL: KSM-IW15-WCT10M1M32 KOLIN WALL MOUNTED CERTUS SERIES AIRCONDITIONER 12,660 Kj/h (1.5HP) REGULAR INVERTER R-32	32,995.00	21,076.20	PHP	21,076.20
6	UNIT/S	MODEL: KSM-IW10-WCT10M1M32 KOLIN WALL MOUNTED CERTUS SERIES AIRCONDITIONER 9,800 Kj/h (1.0HP) REGULAR INVERTER R-32	29,995.00	18,796.20	PHP	112,777.20
TOTAL UNIT COST					PHP	343,322.40
ESTIMATED COST OF INSTALLATION (please see attached)					PHP	242,660.00
OTHERS: DELIVERY CHARGE					PHP	600.00
TOTAL ESTIMATED COST OF THE PROJECT					PHP	586,582.40

TERMS OF PAYMENT:

FULL PAYMENT OF UNIT AND DELIVERY CHARGE. IF CHECK, SUBJECT FOR 3 DAYS CLEARING.

WARRANTY:

FOR SPLIT TYPE : ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB , TEN (10) YEARS WARRANTY ON COMPRESSOR.

NOTES: PRICES ARE SUBJECT TO CHANGE WITHOUT PRIOR NOTICE.

PRICES IS VAT INCLUSIVE.

We thank you for giving opportunity to offer our product and services, hoping we receive your purchase order.

If you need assistance, don't hesitate to call the under signed at 0917-807-8607 or email at kmi_asst@kolinphil.com.ph

**** SUBJECT FOR ACTUAL SURVEY.**

Very Truly Yours,

JANELLEN S. LIM
KMI-ASSISTANT

Noted by:

MART NATHANIEL R. FLORES
KMI-SUPERVISOR

Approved By:

MS. EDITHA M. FLORES
AVP - FINANCE

KMI-QUOTE-02-25-0142
REG-24%/7K/4K

Conforme:

SIGNATURE OVER PRINTED NAME

Kolin Marketing, Inc.

1854 Sta. Rita St., Guadalupe Nuevo, Makati City

Tel.: (632) 8852-6473

Fax: (632) 8852-2170 / (632) 8852-4792

www.kolinphil.com.ph / kolinphilippines

MODEL	Qty
KSG-IWF-30WY8K1M32	3
KSG-IWF-20WY8K1M32	2
KSG-IWF-15WY8K1M32	1
KSG-IWF-10WY8K1M32	6

AREA 1	Area	16.5 sqm
--------	------	----------

ACU 1	1.5 HP Wall Mounted Inverter	KSG-IWF-15WY8K1M32
	Estimated Pipe Length =	37 ft
	Estimated Royal Cord Length =	42 ft
	Initial Charge	₱ 7,500.00

Includes:
Labor
10ft Copper Tube
10ft Royal Cord
Outdoor Bracket (Wall)
Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 3/8"	27 ft	₱ 350.00/ft	₱ 9,450.00
Royal Cord (comm. wire)	2.mm2 x 4C	32 ft	₱ 100.00/ft	₱ 3,200.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	₱ 60.00/ft	₱ 300.00
Circuit Breaker waterproof	20A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	4 pc/s	₱ 350.00/pc	₱ 1,400.00
Full thread	3/8" x 10'	2 pc/s	₱ 150.00/pc	₱ 300.00
Metal Clamp	3"	6 pc/s	₱ 120.00/pc	₱ 720.00
PVC blue	3/4" x 10'	1 pc/s	₱ 150.00/pc	₱ 150.00
				₱ 16,520.00

Estimated Charges	₱ 24,020.00
-------------------	-------------

OPEN AREA	Area	120 sqm
-----------	------	---------

ACU 2	3.0 HP Wall Mounted Inverter	KSG-IWF-30WY8K1M32
	Estimated Pipe Length =	30 ft
	Estimated Royal Cord Length =	35 ft
	Initial Charge	₱ 8,500.00

Includes:
Labor
10ft Copper Tube
10ft Royal Cord
Outdoor Bracket (Wall)
Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 5/8"	20 ft	₱ 350.00/ft	₱ 7,000.00
Royal Cord (comm. wire)	2.mm2 x 4C	25 ft	₱ 100.00/ft	₱ 2,500.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	7 ft	₱ 60.00/ft	₱ 420.00
Circuit Breaker waterproof	20A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	3 pc/s	₱ 350.00/pc	₱ 1,050.00
Full thread	3/8" x 10'	2 pc/s	₱ 150.00/pc	₱ 300.00
Metal Clamp	3"	4 pc/s	₱ 120.00/pc	₱ 480.00
PVC blue	3/4" x 10'	1 pc/s	₱ 150.00/pc	₱ 150.00
				₱ 12,900.00

Estimated Charges	₱ 21,400.00
-------------------	-------------

ACU 3	3.0 HP Wall Mounted Inverter	KSG-IWF-30WY8K1M32
	Estimated Pipe Length =	33 ft
	Estimated Royal Cord Length =	38 ft
	Initial Charge	₱ 8,500.00

Includes:
Labor
10ft Copper Tube
10ft Royal Cord
Outdoor Bracket (Wall)
Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 5/8"	23 ft	₱ 350.00/ft	₱ 8,050.00
Royal Cord (comm. wire)	2.mm2 x 4C	28 ft	₱ 100.00/ft	₱ 2,800.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	₱ 60.00/ft	₱ 300.00
Circuit Breaker waterproof	20A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	3 pc/s	₱ 350.00/pc	₱ 1,050.00
Full thread	3/8" x 10'	2 pc/s	₱ 150.00/pc	₱ 300.00
Metal Clamp	3"	3 pc/s	₱ 120.00/pc	₱ 360.00
PVC blue	3/4" x 10'	1 pc/s	₱ 150.00/pc	₱ 150.00
				₱ 14,010.00

Estimated Charges	₱ 22,510.00
-------------------	-------------

ACU 4 3.0 HP Wall Mounted Inverter **KSG-IWF-30Wfy8K1M32**
 Estimated Pipe Length = 40 ft
 Estimated Royal Cord Length = 45 ft
Initial Charge ₱ 8,500.00

Includes:
 Labor
 10ft Copper Tube
 10ft Royal Cord
 Outdoor Bracket (Wall)
 Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 5/8"	30 ft	₱ 350.00/ft	₱ 10,500.00
Royal Cord (comm. wire)	2.mm2 x 4C	35 ft	₱ 100.00/ft	₱ 3,500.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	₱ 60.00/ft	₱ 300.00
Circuit Breaker waterproof	20A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	4 pc/s	₱ 350.00/pc	₱ 1,400.00
Full thread	3/8" x 10'	2 pc/s	₱ 150.00/pc	₱ 300.00
Metal Clamp	3"	8 pc/s	₱ 120.00/pc	₱ 960.00
PVC blue	3/4" x 10'	1 pc/s	₱ 150.00/pc	₱ 150.00
				₱ 18,110.00

Estimated Charges **₱ 26,610.00**

AREA 2 Area 27 sqm

ACU 5 1.0 HP Wall Mounted Inverter **KSG-IWF-10Wfy8K1M32**
 Estimated Pipe Length = 27 ft
 Estimated Royal Cord Length = 32 ft
Initial Charge ₱ 7,500.00

Includes:
 Labor
 10ft Copper Tube
 10ft Royal Cord
 Outdoor Bracket (Wall)
 Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 3/8"	17 ft	₱ 350.00/ft	₱ 5,950.00
Royal Cord (comm. wire)	2.mm2 x 4C	22 ft	₱ 100.00/ft	₱ 2,200.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	₱ 60.00/ft	₱ 300.00
Circuit Breaker waterproof	20A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	2 pc/s	₱ 350.00/pc	₱ 700.00
Full thread	3/8" x 10'	1 pc/s	₱ 150.00/pc	₱ 150.00
Metal Clamp	3"	6 pc/s	₱ 120.00/pc	₱ 720.00
PVC blue	3/4" x 10'	1 pc/s	₱ 150.00/pc	₱ 150.00
				₱ 11,170.00

Estimated Charges **₱ 18,670.00**

ACU 6 1.0 HP Wall Mounted Inverter **KSG-IWF-10Wfy8K1M32**
 Estimated Pipe Length = 30 ft
 Estimated Royal Cord Length = 35 ft
Initial Charge ₱ 7,500.00

Includes:
 Labor
 10ft Copper Tube
 10ft Royal Cord
 Outdoor Bracket (Wall)
 Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 3/8"	20 ft	₱ 350.00/ft	₱ 7,000.00
Royal Cord (comm. wire)	2.mm2 x 4C	25 ft	₱ 100.00/ft	₱ 2,500.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	₱ 60.00/ft	₱ 300.00
Circuit Breaker waterproof	20A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	1 pc/s	₱ 350.00/pc	₱ 350.00
Full thread	3/8" x 10'	1 pc/s	₱ 150.00/pc	₱ 150.00
Metal Clamp	3"	3 pc/s	₱ 120.00/pc	₱ 360.00
PVC blue	3/4" x 10'	1 pc/s	₱ 150.00/pc	₱ 150.00
				₱ 11,810.00

Estimated Charges **₱ 19,310.00**

AREA 3	Area 4 sqm
--------	------------

ACU 7	1.0 HP Wall Mounted Inverter	KSG-IWF-10Wfy8K1M32	
	Estimated Pipe Length =	27 ft	
	Estimated Royal Cord Length =	32 ft	
	Initial Charge		P 7,500.00
	Includes:		
	Labor		
	10ft Copper Tube		
	10ft Royal Cord		
	Outdoor Bracket (Wall)		
	Consumables		
	Installation Materials		
	Description	Qty	Price per qty
	Copper Tube	Ø 1/4" x Ø 3/8"	17 ft P 350.00/ft
	Royal Cord (comm. wire)	2.mm2 x 4C	22 ft P 100.00/ft
	Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft P 60.00/ft
	Circuit Breaker waterproof	20A / 1Ph	1 pc/s P 1,000.00/pc
	Rubber Insulation	2 1/8" x 3/4" x 6'	2 pc/s P 350.00/pc
	Full thread	3/8" x 10'	1 pc/s P 150.00/pc
	Metal Clamp	3"	4 pc/s P 120.00/pc
	PVC blue	3/4" x 10'	1 pc/s P 150.00/pc
			P 10,930.00

Estimated Charges	P 18,430.00
--------------------------	--------------------

AREA 4	Area 4 sqm
--------	------------

ACU 8	1.0 HP Wall Mounted Inverter	KSG-IWF-10Wfy8K1M32	
	Estimated Pipe Length =	23 ft	
	Estimated Royal Cord Length =	28 ft	
	Initial Charge		P 7,500.00
	Includes:		
	Labor		
	10ft Copper Tube		
	10ft Royal Cord		
	Outdoor Bracket (Wall)		
	Consumables		
	Installation Materials		
	Description	Qty	Price per qty
	Copper Tube	Ø 1/4" x Ø 3/8"	13 ft P 350.00/ft
	Royal Cord (comm. wire)	2.mm2 x 4C	18 ft P 100.00/ft
	Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft P 60.00/ft
	Circuit Breaker waterproof	20A / 1Ph	1 pc/s P 1,000.00/pc
	Rubber Insulation	2 1/8" x 3/4" x 6'	1 pc/s P 350.00/pc
	Full thread	3/8" x 10'	1 pc/s P 150.00/pc
	Metal Clamp	3"	2 pc/s P 120.00/pc
	PVC blue	3/4" x 10'	1 pc/s P 150.00/pc
			P 8,540.00

Estimated Charges	P 16,040.00
--------------------------	--------------------

AREA 5	Area 47 sqm
--------	-------------

ACU 9	2.0 HP Wall Mounted Inverter	KSG-IWF-20Wfy8K1M32	
	Estimated Pipe Length =	33 ft	
	Estimated Royal Cord Length =	38 ft	
	Initial Charge		P 7,500.00
	Includes:		
	Labor		
	10ft Copper Tube		
	10ft Royal Cord		
	Outdoor Bracket (Wall)		
	Consumables		
	Installation Materials		
	Description	Qty	Price per qty
	Copper Tube	Ø 1/4" x Ø 1/2"	23 ft P 350.00/ft
	Royal Cord (comm. wire)	2.mm2 x 4C	28 ft P 100.00/ft
	Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft P 60.00/ft
	Circuit Breaker waterproof	20A / 1Ph	1 pc/s P 1,000.00/pc
	Rubber Insulation	2 1/8" x 3/4" x 6'	4 pc/s P 350.00/pc
	Full thread	3/8" x 10'	1 pc/s P 150.00/pc
	Metal Clamp	3"	6 pc/s P 120.00/pc
	PVC blue	3/4" x 10'	1 pc/s P 150.00/pc
			P 14,570.00

Estimated Charges	P 22,070.00
--------------------------	--------------------

ACU 10 2.0 HP Wall Mounted Inverter		KSG-IWF-20Wfy8K1M32		
Estimated Pipe Length	=	17 ft		
Estimated Royal Cord Length	=	22 ft		
Initial Charge				P 7,500.00
Includes:				
Labor				
10ft Copper Tube				
10ft Royal Cord				
Outdoor Bracket (Wall)				
Consumables				
Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 1/2"	7 ft	P 350.00/ft	P 2,450.00
Royal Cord (comm. wire)	2.mm2 x 4C	12 ft	P 100.00/ft	P 1,200.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	P 60.00/ft	P 300.00
Circuit Breaker waterproof	20A / 1Ph	1 pc/s	P 1,000.00/pc	P 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	1 pc/s	P 350.00/pc	P 350.00
Full thread	3/8" x 10'	1 pc/s	P 150.00/pc	P 150.00
Metal Clamp	3"	2 pc/s	P 120.00/pc	P 240.00
PVC blue	3/4" x 10'	1 pc/s	P 150.00/pc	P 150.00
				P 5,840.00
Estimated Charges		P 13,340.00		

AREA 6		Area 12. sqm		
ACU 11 1.0 HP Wall Mounted Inverter		KSG-IWF-10Wfy8K1M32		
Estimated Pipe Length	=	27 ft		
Estimated Royal Cord Length	=	32 ft		
Initial Charge				P 7,500.00
Includes:				
Labor				
10ft Copper Tube				
10ft Royal Cord				
Outdoor Bracket (Wall)				
Consumables				
Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 3/8"	17 ft	P 350.00/ft	P 5,950.00
Royal Cord (comm. wire)	2.mm2 x 4C	22 ft	P 100.00/ft	P 2,200.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	P 60.00/ft	P 300.00
Circuit Breaker waterproof	20A / 1Ph	1 pc/s	P 1,000.00/pc	P 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	2 pc/s	P 350.00/pc	P 700.00
Full thread	3/8" x 10'	1 pc/s	P 150.00/pc	P 150.00
Metal Clamp	3"	3 pc/s	P 120.00/pc	P 360.00
PVC blue	3/4" x 10'	1 pc/s	P 150.00/pc	P 150.00
				P 10,810.00
Estimated Charges		P 18,310.00		

AREA 7		Area 12 sqm		
ACU 12 1.0 HP Wall Mounted Inverter		KSG-IWF-10Wfy8K1M32		
Estimated Pipe Length	=	33 ft		
Estimated Royal Cord Length	=	38 ft		
Initial Charge				P 7,500.00
Includes:				
Labor				
10ft Copper Tube				
10ft Royal Cord				
Outdoor Bracket (Wall)				
Consumables				
Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 3/8"	23 ft	P 350.00/ft	P 8,050.00
Royal Cord (comm. wire)	2.mm2 x 4C	28 ft	P 100.00/ft	P 2,800.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	P 60.00/ft	P 300.00
Circuit Breaker waterproof	20A / 1Ph	1 pc/s	P 1,000.00/pc	P 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	4 pc/s	P 350.00/pc	P 1,400.00
Full thread	3/8" x 10'	1 pc/s	P 150.00/pc	P 150.00
Metal Clamp	3"	5 pc/s	P 120.00/pc	P 600.00
PVC blue	3/4" x 10'	1 pc/s	P 150.00/pc	P 150.00
				P 14,450.00
Estimated Charges		P 21,950.00		

Total Estimated Charges


P 242,660.00

Validity: This quotation is valid for a period of fifteen (15) days from the date thereof, subject to our confirmation thereafter.

Installation notes:

- 1 Air conditioning capacity and unit location based in floor plan only.
- 2 AC drain line will be tapped to the nearest drain provision provided by the customer's contractor.
- 3 Need for site visit and markings before installation.
- 4 Issuance of waiver in all areas due to undersize.
- 5 Coppertube expose inside the area.
- 6 Working days: Monday to Saturday, 8am- 5pm with parking. Need working permit.
- 7 Mechanical Plans, Permits, Electrical permits not included.
- 8 Deflectors, masonry, carpentry, chipping & plastering (finishing & restoration) are not included in the installation.
- 9 Air conditioning drain line and Electrical power supply (feeder line) **220v/ 60hz/ 1ph** should be provided by customer's contractor.
- 10 **Final charges will be based on actual installation.**


Prepared by:


Jeffrey Dadios
Field Surveyor

Customer Conformer:

Signature Over Printed Name

Reviewed by:


Engr. Kenneth Zamora
Service Supervisor Shop and
Field Operation

