



February 23, 2026

ICCT ANGONO CAMPUS  
MANILA EAST ROAD, SAN ROQUE, ANGONO RIZAL (FORMERLY LTO BLDG. NEAR BALAW-BALAW RESTAURANT)  
TEL#: 0905-4818513 / 0985-8576878

Dear Ma'am/Sir,

Kolin Marketing Inc., is extremely honored for your endorsement of Kolin brand and we are please to offer you with a special price/s for the following items.

A. EQUIPMENT & INSTALLATION

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
1	UNIT/S	MODEL: KS-IW15-MCAI1201M32 KOLIN WALL MOUNTED CERTUS A/ SERIES AIRCONDITIONER 12,880 Kj/h (1.5HP) FULL DC INVERTER W/ WIFI R-32	33,995.00	18,656.30	PHP	18,656.30
5	UNIT/S	MODEL: KS-IW20-MCAI1201M32 KOLIN WALL MOUNTED CERTUS A/ SERIES AIRCONDITIONER 19,000 Kj/h (2.0HP) FULL DC INVERTER W/ WIFI R-32	42,995.00	25,316.30	PHP	126,581.50
14	UNIT/S	MODEL: KS-IW25-MCAI1201M32 KOLIN WALL MOUNTED CERTUS A/ SERIES AIRCONDITIONER 23,800 Kj/h (2.5HP) FULL DC INVERTER W/ WIFI R-32	50,995.00	30,736.30	PHP	430,308.20
TOTAL UNIT COST					PHP	575,546.00
ESTIMATED COST OF INSTALLATION w/ 5% discount (please see attached) - NET -					PHP	559,110.00
TOTAL ESTIMATED COST OF THE PROJECT					PHP	1,134,656.00

TERMS OF PAYMENT:

FULL PAYMENT OF UNIT AND DELIVERY CHARGE. IF CHECK, SUBJECT FOR 3 DAYS CLEARING.

BANK DETAILS:

- \* Unit/s & Delivery: Account Name - KOLIN MARKETING INC. / Account# - 011808002307 (BDO-KALAYAAN)
- \* Installation: Will be provided by assigned installer.
- \*\* You may settle first payment for unit/s & delivery. Installation payment can be settled directly to installer after actual works.

WARRANTY:

FOR SPLIT TYPE : ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB , TEN (10) YEARS WARRANTY ON COMPRESSOR.

NOTES: PRICES ARE SUBJECT TO CHANGE WITHOUT PRIOR NOTICE.

PRICES IS VAT INCLUSIVE.

\*\* Cost of Installation is Package with the Unit(s), this cost cannot avail separately (cost will be based on actual works).

We thank you for giving opportunity to offer our product and services, hoping we receive your purchase order.  
If you need assistance, don't hesitate to call the under signed at 0917-807-8607 or email at kmi\_asst@kolinphil.com.ph

Very Truly Yours,

JANELLEN S. LIM  
KMI ASSISTANT

Noted by:  
  
MART ANTONIO NIEL R. FLORES  
KMI SUPERVISOR

Approved By:  
  
MS. EDITHA M. FLORES  
AVP - FINANCE

Conforme: \_\_\_\_\_  
SIGNATURE OVER PRINTED NAME

KMI-QUOTE-10-25-0760-rev2  
REG-26%/6.5K/7K



# JRA JERRICO

Refrigeration and Air-conditioning Services  
 B4, I9 Felixvill, Mangahan, Stc. Niño Bilibiran, Binangonan Rizal  
 Email: [jraairconditioning@gmail.com](mailto:jraairconditioning@gmail.com)  
 Contact Nos. 09267189004/09615215615

Customer Name:	ICCT ANGONO CAMPUS	Date:	October 14, 2025
Customer Address:	ICCT ANGONO CAMPUS MANILA EAST ROAD SAN ROQUE ANGONO RIZAL		

Qty	Unit Model	Unit Capacity/Type
1	KSM-IW15-WCT10M1M32	1.5HP Wall Mounted Inverter
5	KSM-IW20-WCT10M1M32	2.0HP Wall Mounted Inverter
14	KSM-IW25-WCT10M1M32	2.5HP Wall Mounted Inverter

Location/s:	GROUND FLOOR / VISISTOR LOUNGE	Area:	*19 sqm.
ACU #:	1	Unit Model:	KSM-IW20-WCT10M1M32
		Unit Capacity/Type:	2.0HP Wall Mounted Inverter

Estimated Pipe Length = 41 ft  
 Estimated Royal Cord Length = 46 ft

**Initial Charge**

- 10ft Copper tube
- 10ft Royal Cord
- Outdoor bracket Wall/Floor
- Consumables
- Testing and Commissioning

₱ 8,500.00 **7,500**

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	31 ft	₱ 350.00 /ft	₱ 10,850.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	36 ft	100.00 /ft	3,600.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	5 ft	60.00 /ft	300.00
Circuit Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
PVC Pipe	Ø3/4" x 10'	4 pc	150.00 /pc(s)	600.00
Estimated Charges				₱ 24,850.00

<b>Location/s:</b>	GROUND FLOOR /FACULTY		<b>Area:</b>	22.75 sqm.
<b>ACU #:</b>	2	<b>Unit Model:</b>	KSM-IW15-WCT10M1M32	<b>Unit Capacity/Type:</b> 1.5HP Wall Mounted Inverter

Estimated Pipe Length = 53 ft

Estimated Royal Cord Length = 58 ft

**Initial Charge** ₱ 7,500.00

- 10ft Copper tube
- 10ft Royal Cord
- Outdoor bracket Wall/Floor
- Consumables
- Testing and Commissioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	43 ft	₱ 350.00 /ft	₱ 15,050.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	48 ft	100.00 /ft	4,800.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	5 ft	60.00 /ft	300.00
Circuit Breaker Weather Proof	20Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
PVC Pipe	Ø3/4" x 10'	4 pc	150.00 /pc(s)	600.00
<b>Estimated Charges</b>				<b>₱ 29,250.00</b>

<b>Location/s:</b>	GROUND FLOOR /DCLC MULTI PURPOSE1		<b>Area:</b>	21.00 sqm.
<b>ACU #:</b>	3	<b>Unit Model:</b>	KSM-IW25-WCT10M1M32	<b>Unit Capacity/Type:</b> 2.5HP Wall Mounted Inverter

Estimated Pipe Length = 30 ft

Estimated Royal Cord Length = 35 ft

**Initial Charge** ₱ 8,500.00

- 10ft Copper tube
- 10ft Royal Cord
- Outdoor bracket Wall/Floor
- Consumables
- Testing and Commissioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	20 ft	₱ 350.00 /ft	₱ 7,000.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	25 ft	100.00 /ft	2,500.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	5 ft	60.00 /ft	300.00
Circuit Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
PVC Pipe	Ø3/4" x 10'	2 pc	150.00 /pc(s)	300.00
<b>Estimated Charges</b>				<b>₱ 19,600.00</b>

<b>Location/s:</b>	2ND FLOOR MEGA CLASSROOM 1	<b>Area:</b>	42.00 sqm.
<b>ACU #:</b>	4	<b>Unit Model:</b>	KSM-IW25-WCT10M1M32
			<b>Unit Capacity/Type:</b> 2.5HP Wall Mounted Inverter

Estimated Pipe Length = 51 ft

Estimated Royal Cord Length = 56 ft

**Initial Charge** ₱ 8,500.00

- 10ft Copper tube
- 10ft Royal Cord
- Outdoor bracket Wall/Floor
- Consumables
- Testing and Commissioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	41 ft	₱ 350.00 /ft	₱ 14,350.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	46 ft	100.00 /ft	4,600.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	5 ft	60.00 /ft	300.00
Circuit Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
PVC Pipe	Ø3/4" x 10'	4 pc	150.00 /pc(s)	600.00

Estimated Charges ₱ 29,350.00

<b>Location/s:</b>	2ND FLOOR MEGA CLASS ROOM 2	<b>Area:</b>	42.00 sqm.
<b>ACU #:</b>	5	<b>Unit Model:</b>	KSM-IW25-WCT10M1M32
			<b>Unit Capacity/Type:</b> 2.5HP Wall Mounted Inverter

Estimated Pipe Length = 46 ft

Estimated Royal Cord Length = 51 ft

**Initial Charge** ₱ 8,500.00

- 10ft Copper tube
- 10ft Royal Cord
- Outdoor bracket Wall/Floor
- Consumables
- Testing and Commissioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	36 ft	₱ 350.00 /ft	₱ 12,600.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	41 ft	100.00 /ft	4,100.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	5 ft	60.00 /ft	300.00
Circuit Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
PVC Pipe	Ø3/4" x 10'	3 pc	150.00 /pc(s)	450.00

Estimated Charges ₱ 26,950.00

Location/s:	2ND FLOOR CENTER ROOM	Area:	22.00 sqm.
ACU #:	6	Unit Model:	KSM-IW25-WCT10M1M32
		Unit Capacity/Type:	2.5HP Wall Mounted Inverter

Estimated Pipe Length = 53 ft

Estimated Royal Cord Length = 58 ft

Initial Charge P 8,500.00

- 10ft Copper tube
- 10ft Royal Cord
- Outdoor bracket Wall/Floor
- Consumables
- Testing and Commissioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	43 ft	P 350.00 /ft	P 15,050.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	48 ft	100.00 /ft	4,800.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	5 ft	60.00 /ft	300.00
Circuit Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
PVC Pipe	Ø3/4" x 10'	4 pc	150.00 /pc(s)	600.00

Estimated Charges P 30,250.00

Location/s:	2ND FLOOR CHEMISTRY/physics 1	Area:	33.75 sqm.
ACU #:	7	Unit Model:	KSM-IW20-WCT10M1M32
		Unit Capacity/Type:	2.0HP Wall Mounted Inverter

Estimated Pipe Length = 67 ft

Estimated Royal Cord Length = 72 ft

Initial Charge P 8,500.00 7,500

- 10ft Copper tube
- 10ft Royal Cord
- Outdoor bracket Wall/Floor
- Consumables
- Testing and Commissioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	57 ft	P 350.00 /ft	P 19,950.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	62 ft	100.00 /ft	6,200.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	5 ft	60.00 /ft	300.00
Circuit Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
PVC Pipe	Ø3/4" x 10'	6 pc	150.00 /pc(s)	900.00

Estimated Charges P 36,850.00

Location/s:	2ND FLOOR CHEMISTRY ROOM 2	Area:	33.75 sqm.
ACU #:	8	Unit Model:	KSM-IW20-WCT10M1M32
		Unit Capacity/Type:	2.0HP Wall Mounted Inverter

Estimated Pipe Length = 54 ft

Estimated Royal Cord Length = 59 ft

Initial Charge P 8,500.00 7,500

- 10ft Copper tube
- 10ft Royal Cord
- Outdoor bracket Wall/Floor
- Consumables
- Testing and Commissioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	44 ft	P 350.00 /ft	P 15,400.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	49 ft	100.00 /ft	4,900.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	5 ft	60.00 /ft	300.00
Circuit Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
PVC Pipe	Ø3/4" x 10'	4 pc	150.00 /pc(s)	600.00

Estimated Charges P 30,700.00

Location/s:	3RD FLOOR CLASS ROOM 3	Area:	21.00 sqm.
ACU #:	9	Unit Model:	KSM-IW25-WCT10M1M32 /
		Unit Capacity/Type:	2.5HP Wall Mounted Inverter

Estimated Pipe Length = 51 ft

Estimated Royal Cord Length = 56 ft

**Initial Charge** ₱ 8,500.00

- 10ft Copper tube
- 10ft Royal Cord
- Outdoor bracket Wall/Floor
- Consumables
- Testing and Commissioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	41 ft	₱ 350.00 /ft	₱ 14,350.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	46 ft	100.00 /ft	4,600.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	5 ft	60.00 /ft	300.00
Circuit Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
PVC Pipe	Ø3/4" x 10'	3 pc	150.00 /pc(s)	450.00

Estimated Charges ₱ 29,200.00

Location/s:	3RD FLOOR CLASS ROOM 4	Area:	19.50 sqm.
ACU #:	10	Unit Model:	KSM-IW25-WCT10M1M32 /
		Unit Capacity/Type:	2.5HP Wall Mounted Inverter

Estimated Pipe Length = 45 ft

Estimated Royal Cord Length = 50 ft

**Initial Charge** ₱ 8,500.00

- 10ft Copper tube
- 10ft Royal Cord
- Outdoor bracket Wall/Floor
- Consumables
- Testing and Commissioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	35 ft	₱ 350.00 /ft	₱ 12,250.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	40 ft	100.00 /ft	4,000.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	5 ft	60.00 /ft	300.00
Circuit Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
PVC Pipe	Ø3/4" x 10'	3 pc	150.00 /pc(s)	450.00

Estimated Charges ₱ 26,500.00

Location/s:	3RD FLOOR CLASS ROOM 5	Area:	23.80 sqm.
ACU #:	11	Unit Model:	KSM-IW25-WCT10M1M32 /
		Unit Capacity/Type:	2.5HP Wall Mounted Inverter

Estimated Pipe Length = 54 ft

Estimated Royal Cord Length = 59 ft

**Initial Charge** ₱ 8,500.00

- 10ft Copper tube
- 10ft Royal Cord
- Outdoor bracket Wall/Floor
- Consumables
- Testing and Commissioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	44 ft	₱ 350.00 /ft	₱ 15,400.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	49 ft	100.00 /ft	4,900.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	5 ft	60.00 /ft	300.00
Circuit Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
PVC Pipe	Ø3/4" x 10'	4 pc	150.00 /pc(s)	600.00

Estimated Charges ₱ 30,700.00

Location/s:	3RD FLOOR COMPUTER ROOM 1	Area:	33.75 sqm.
ACU #:	12	Unit Model:	KSM-IW20-WCT10M1M32
		Unit Capacity/Type:	2.0HP Wall Mounted Inverter

Estimated Pipe Length = 59 ft  
 Estimated Royal Cord Length = 64 ft

**Initial Charge**

- 10ft Copper tube
- 10ft Royal Cord
- Outdoor bracket Wall/Floor
- Consumables
- Testing and Commissioning

₱ 8,500.00

7,500

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	49 ft	₱ 350.00 /ft	₱ 17,150.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	54 ft	100.00 /ft	5,400.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	5 ft	60.00 /ft	300.00
Circuit Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
PVC Pipe	Ø3/4" x 10'	4 pc	150.00 /pc(s)	600.00
Estimated Charges				₱ 32,950.00

Location/s:	3RD FLOOR COMPUTER ROOM2	Area:	33.75 sqm.
ACU #:	13	Unit Model:	KSM-IW20-WCT10M1M32
		Unit Capacity/Type:	2.0HP Wall Mounted Inverter

Estimated Pipe Length = 64 ft  
 Estimated Royal Cord Length = 69 ft

**Initial Charge**

- 10ft Copper tube
- 10ft Royal Cord
- Outdoor bracket Wall/Floor
- Consumables
- Testing and Commissioning

₱ 8,500.00

7,500

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	54 ft	₱ 350.00 /ft	₱ 18,900.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	59 ft	100.00 /ft	5,900.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	5 ft	60.00 /ft	300.00
Circuit Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
PVC Pipe	Ø3/4" x 10'	5 pc	150.00 /pc(s)	750.00
Estimated Charges				₱ 35,350.00

Location/s:	4RTH FLOOR TEACHING HUB ROOM	Area:	21.60 sqm.
ACU #:	14	Unit Model:	KSM-IW25-WCT10M1M32
		Unit Capacity/Type:	2.5HP Wall Mounted Inverter

Estimated Pipe Length = 41 ft  
 Estimated Royal Cord Length = 46 ft

**Initial Charge**

- 10ft Copper tube
- 10ft Royal Cord
- Outdoor bracket Wall/Floor
- Consumables
- Testing and Commissioning

₱ 8,500.00

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	31 ft	₱ 350.00 /ft	₱ 10,850.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	36 ft	100.00 /ft	3,600.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	5 ft	60.00 /ft	300.00
Circuit Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
PVC Pipe	Ø3/4" x 10'	3 pc	150.00 /pc(s)	450.00
Estimated Charges				₱ 24,700.00

Location/s:	4RTH FLOOR CLASS ROOM 6	Area:	*19.2 sqm.
ACU #:	15	Unit Model:	KSM-IW25-WCT10M1M32
		Unit Capacity/Type:	2.5HP Wall Mounted Inverter

Estimated Pipe Length = 45 ft

Estimated Royal Cord Length = 50 ft

**Initial Charge** ₱ 8,500.00

- 10ft Copper tube
- 10ft Royal Cord
- Outdoor bracket Wall/Floor
- Consumables
- Testing and Commissioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	35 ft	₱ 350.00 /ft	₱ 12,250.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	40 ft	100.00 /ft	4,000.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	5 ft	60.00 /ft	300.00
Circuit Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
PVC Pipe	Ø3/4" x 10'	3 pc	150.00 /pc(s)	450.00

Estimated Charges ₱ 26,500.00

Location/s:	4RTH FLOOR CLASS ROOM 7	Area:	22.44 sqm.
ACU #:	16	Unit Model:	KSM-IW25-WCT10M1M32
		Unit Capacity/Type:	2.5HP Wall Mounted Inverter

Estimated Pipe Length = 51 ft

Estimated Royal Cord Length = 56 ft

**Initial Charge** ₱ 8,500.00

- 10ft Copper tube
- 10ft Royal Cord
- Outdoor bracket Wall/Floor
- Consumables
- Testing and Commissioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	41 ft	₱ 350.00 /ft	₱ 14,350.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	46 ft	100.00 /ft	4,600.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	5 ft	60.00 /ft	300.00
Circuit Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
PVC Pipe	Ø3/4" x 10'	4 pc	150.00 /pc(s)	600.00

Estimated Charges ₱ 29,350.00

Location/s:	4RTH FLOOR COMPUTER ROOM1	Area:	54.00 sqm.
ACU #:	17	Unit Model:	KSM-IW25-WCT10M1M32
		Unit Capacity/Type:	2.5HP Wall Mounted Inverter

Estimated Pipe Length = 60 ft

Estimated Royal Cord Length = 65 ft

**Initial Charge** ₱ 8,500.00

- 10ft Copper tube
- 10ft Royal Cord
- Outdoor bracket Wall/Floor
- Consumables
- Testing and Commissioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	50 ft	₱ 350.00 /ft	₱ 17,500.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	55 ft	100.00 /ft	5,500.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	5 ft	60.00 /ft	300.00
Circuit Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
PVC Pipe	Ø3/4" x 10'	5 pc	150.00 /pc(s)	750.00

Estimated Charges ₱ 33,550.00

Location/s:	4RTH FLOOR COMPUTER ROOM 2	Area:	54.00 sqm.
ACU #:	18	Unit Model:	KSM-IW25-WCT10M1M32
		Unit Capacity/Type:	2.5HP Wall Mounted Inverter

Estimated Pipe Length = 55 ft

Estimated Royal Cord Length = 60 ft

**Initial Charge** ₱ 8,500.00

- 10ft Copper tube
- 10ft Royal Cord
- Outdoor bracket Wall/Floor
- Consumables
- Testing and Commissioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	45 ft	₱ 350.00 /ft	₱ 15,750.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	50 ft	100.00 /ft	5,000.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	5 ft	60.00 /ft	300.00
Circuit Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
PVC Pipe	Ø3/4" x 10'	4 pc	150.00 /pc(s)	600.00
Estimated Charges				₱ 31,150.00

Location/s:	5TH FLOOR WORKING AREA	Area:	31.50 sqm.
ACU #:	19	Unit Model:	KSM-IW25-WCT10M1M32
		Unit Capacity/Type:	2.5HP Wall Mounted Inverter

Estimated Pipe Length = 95 ft

Estimated Royal Cord Length = 100 ft

**Initial Charge** ₱ 8,500.00

- 10ft Copper tube
- 10ft Royal Cord
- Outdoor bracket Wall/Floor
- Consumables
- Testing and Commissioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	85 ft	₱ 350.00 /ft	₱ 29,750.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	90 ft	100.00 /ft	9,000.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	5 ft	60.00 /ft	300.00
Circuit Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
PVC Pipe	Ø3/4" x 10'	8 pc	150.00 /pc(s)	1,200.00
Estimated Charges				₱ 49,750.00

Location/s:	5TH LIBRARY MEZZANINE	Area:	31.50 sqm.
ACU #:	20	Unit Model:	KSM-IW25-WCT10M1M32
		Unit Capacity/Type:	2.5HP Wall Mounted Inverter

Estimated Pipe Length = 23 ft

Estimated Royal Cord Length = 28 ft

**Initial Charge** ₱ 8,500.00

- 10ft Copper tube
- 10ft Royal Cord
- Outdoor bracket Wall/Floor
- Consumables
- Testing and Commissioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	13 ft	₱ 350.00 /ft	₱ 4,550.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	18 ft	100.00 /ft	1,800.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	5 ft	60.00 /ft	300.00
Circuit Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
PVC Pipe	Ø3/4" x 10'	1 pc	150.00 /pc(s)	150.00
Estimated Charges				₱ 16,300.00

Total Estimated Charges

₱ 593,800.00

**INSTALLATION NOTE:**

1. Mechanical Plans ,Permits,Electrical permit not included.
2. Deflector, Masonary, carpentry, chipping & plastering ,finishing & restoration are not included in the installation
3. Air conditioning drain line and electrical power supply should be provided by the customer's contractor.

**Installation Warranty**

One (1) Yr warranty for Parts & service

Three(3) Yrs warranty for PCB Only

10yrs warranty for compressor

**Mode of Payment**

50% Down payment before installation start

50% after work completion

Cash or Bank Transfer

**Bank Details: Metro Bank**

Account name: Jerico R. De vera

Account #: 3453345441418

Gcash account # 09060972751

Prepare by:   
Monaliza A. Pepito

  
Jerico R. De Vera:  
Owner

Total Estimated Charges: ₱ 593,800.00

Discount % 5%

**GRAND TOTAL ₱564,110.00**

*less ₱5,000.00 - 2.0HP initial charges*

**TOTAL: ₱ 559, 110.00**

CONFORME

Signature Over Printed Name

Date: \_\_\_\_\_