



February 3, 2026

MR. EDDIE GOBING
79 FIREFLY ST., VALLE VERDE 6, BRGY. UGONG, PASIG CITY
TEL#: 0977-7808507 / 0919-0795657 / (02) 8829-4919
Email: jamesgobing@outlook.com

Dear Ma'am/Sir,

Kolin Marketing Inc., is extremely honored for your endorsement of Kolin brand and we are please to offer you with a special price/s for the following items.

A. EQUIPMENT & INSTALLATION

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
2	UNIT/S	MODEL: KLM-IC40-AA1M32 KOLIN FLOOR/CEILING AIRCONDITIONER 37,980 Kj/h (3.0TR) DC INVERTER R-32	117,995.00	89,676.20	PHP	179,352.40
2	UNIT/S	MODEL: KLM-IS40-AA1M32 KOLIN CEILING CASSETTE AIRCONDITIONER 37,980 Kj/h (3.0TR) DC INVERTER R-32 SINGLE PHASE	119,995.00	91,196.20	PHP	182,392.40
4	UNIT/S	MODEL: KSG-IWF-25Wfy-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 25,560 Kj/h (2.5HP) FULL DC INVERTER W/ WIFI R-32	68,995.00	45,436.20	PHP	181,744.80
5	UNIT/S	MODEL: KSG-IWF-20Wfy-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 19,000 Kj/h (2.0HP) FULL DC INVERTER W/ WIFI R-32	59,595.00	38,292.20	PHP	191,461.00
3	UNIT/S	MODEL: KSG-IWF-15Wfy-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 12,960 Kj/h (1.5HP) FULL DC INVERTER W/ WIFI R-32	46,595.00	28,412.20	PHP	85,236.60
TOTAL UNIT COST					PHP	820,187.20
ESTIMATED COST OF INSTALLATION (please see attached)					PHP	749,360.00
TOTAL ESTIMATED COST OF THE PROJECT					PHP	1,569,547.20

TERMS OF PAYMENT:

FULL PAYMENT OF UNIT AND DELIVERY CHARGE. IF CHECK, SUBJECT FOR 3 DAYS CLEARING.

BANK DETAILS:

** You may settle first payment for unit/s & delivery. Installation payment can be settled directly to installer after actual works.

* Unit/s & Delivery: Account Name - KOLIN MARKETING INC. / Account# - 011808002307 (BDO-KALAYAAN)

* Installation: Will be provided by assigned installer.

WARRANTY:

FOR FLOOR/CEILING: ONE (1) YEAR FREE PARTS AND LABOR, FIVE (5) YEARS WARRANTY ON COMPRESSOR.

FOR CEILING CASSETTE (Inverter): ONE (1) YEAR FREE PARTS AND LABOR, FIVE (5) YEARS WARRANTY ON COMPRESSOR.

FOR SPLIT TYPE : ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB , TEN (10) YEARS WARRANTY ON COMPRESSOR.

NOTES: PRICES ARE SUBJECT TO CHANGE WITHOUT PRIOR NOTICE.

PRICES IS VAT INCLUSIVE.

** Cost of Installation is Package with the Unit(s), this cost cannot avail separately (Final charges will be based on actual works).

We thank you for giving opportunity to offer our product and services, hoping we receive your purchase order.

If you need assistance, don't hesitate to call the under signed at 0917-807-8607 or email at kmi_asst@kolinphil.com.ph

Very Truly Yours,

JANELLEN S. LIM
KMI-ASSISTANT

Noted by:
MART NATHANIEL R. FLORES
KMI-SUPERVISOR

Approved By:
MS. EDITHA M. FLORES
AVP - FINANCE

KMI-QUOTE-04-25-0276-rev3
DCG-24%/7K

Conforme: _____
SIGNATURE OVER PRINTED NAME

Kolin Marketing, Inc.

1854 Sta. Rita St., Guadalupe Nuevo, Makati City

Tel.: (632) 8852-6473

Fax: (632) 8852-2170 / (632) 8852-4792

www.kolinphil.com.ph / kolinphilippines



FEBRUARY 02, 2026

EDDIE GOBING

79 Firefly St. Valle Verde 6 Brgy Ugong, Pasig City

0977-7808507, 0919-0795657, (020)8829-4919

jamesgobing@outlook.com

cc: mcivalverde6@gmail.com

Recommended Models	Qty
KLM-IC60-AA1M32-I	2
KLM-IS40-AA1M32-I	2
KSG-IWF-25WFY-8K1M32	4
KSG-IWF-20WFY-8K1M32	5
KSG-IWF-15WFY-8K1M32	3

rev3

GROUND FLOOR

LANAI	Area = 50 sq.m
--------------	----------------

ACU 1	4.0hp Ceiling Cassette Inverter	KLM-IS40-AA1M32			
	Estimated Pipe Length	: 73	ft		
	Estimated Royal Cord Length	: 80	ft		
	Initial Charge			P	12,000.00
	Includes:				
	Labor				
	10ft Copper Tube				
	10ft Royal Cord				
	Other Consumables				
	Additional Charges	Description	Unit	Price Per Unit	Subtotal
	Copper Tube	3/8"x 5/8"	63 ft	P 400 / ft	P 25,200
	Royal Cord	2.mm2 x 4C	70 ft	P 100 / ft	P 7,000
	Royal Cord (ODU-Breaker)	5.5mm2 x 3C	7 ft	P 70 / ft	P 490
	Circuit Breaker(NEMA)	40A/ 1Ph	1 pc(s)	P 1,000 / pc	P 1,000
	Rubber Insulation	2 1/8"x3/4" x 6'	10 pc(s)	P 650 / pc	P 6,500
	Full Thread	3/8" x 10'	5 pc(s)	P 150 / pc	P 750
	Pipe hanger	3 inches	14 pc(s)	P 120 / pc	P 1,680
	Indoor Bracket	fabricated	1 pc(s)	P 1,500 / pc	P 1,500
	Outdoor Bracket(WALL)	fabricated	1 pc(s)	P 5,000 / pc	P 5,000
	Pvc (drainline)	blue- 1 inch	1 pc(s)	P 200 / pc	P 200
	PVC	Orange- 3 inch	6 pc(s)	P 350 / pc	P 2,100
	Chipping works	3" x 3" diameter	8 pc(s)	P 500 / pc	P 4,000
	Drain Hose	White -1/2"	7 ft	P 25 / ft	P 175
					55,595.00
	Estimated Charges			P	67,595.00

ACU 2	4.0hp Ceiling Cassette Inverter	KLM-IS40-AA1M32			
	Estimated Pipe Length	: 70	ft		
	Estimated Royal Cord Length	: 77	ft		
	Initial Charge			P	12,000.00
	Includes:				
	Labor				
	10ft Copper Tube				
	10ft Royal Cord				
	Other Consumables				
	Additional Charges	Description	Unit	Price Per Unit	Subtotal
	Copper Tube	3/8"x 5/8"	60 ft	P 400 / ft	P 24,000
	Royal Cord	2.mm2 x 4C	67 ft	P 100 / ft	P 6,700
	Royal Cord (ODU-Breaker)	5.5mm2 x 3C	7 ft	P 70 / ft	P 490
	Circuit Breaker(NEMA)	40A/ 1Ph	1 pc(s)	P 1,000 / pc	P 1,000
	Rubber Insulation	2 1/8"x3/4" x 6'	10 pc(s)	P 650 / pc	P 6,500
	Full Thread	3/8" x 10'	5 pc(s)	P 150 / pc	P 750
	Pipe hanger	3 inches	14 pc(s)	P 120 / pc	P 1,680
	Indoor Bracket	fabricated	1 pc(s)	P 1,500 / pc	P 1,500
	Outdoor Bracket(WALL)	fabricated	1 pc(s)	P 5,000 / pc	P 5,000
	Pvc (drainline)	blue- 1 inch	1 pc(s)	P 200 / pc	P 200
	PVC	Orange- 3 inch	6 pc(s)	P 350 / pc	P 2,100
	Chipping works	3" x 3" diameter	8 mtrs	P 500 / mtr	P 4,000
	Drain Hose	White -1/2"	7 ft	P 25 / ft	P 175
					54,095.00
	Estimated Charges			P	66,095.00

ANTEROOM Area ≈ 15 sq.m

ACU 3 1.5hp Wallmounted Inverter *KSG-IWF-15Wfy-8K1M32*

Estimated Pipe Length : 37 ft
 Estimated Royal Cord Length : 44 ft

Initial Charge P 7,500.00

Includes:
 Labor
 10ft Copper Tube
 10ft Royal Cord
 Outdoor Bracket (wall)
 Other Consumables

Additional Charges	Description	Unit	Price Per Unit	Subtotal
Copper Tube	1/4"x 3/8"	27 ft	P 350 / ft	P 9,450
Royal Cord	2.mm2 x 4C	34 ft	P 100 / ft	P 3,400
Royal Cord (ODU-Breaker)	3.5mm2 x 3C	7 ft	P 60 / ft	P 420
Circuit Breaker(NEMA)	20A/ 1Ph	1 pc(s)	P 1,000 / pc	P 1,000
Rubber Insulation	2 1/8"x3/4" x 6'	5 pc(s)	P 650 / pc	P 3,250
Full Thread	3/8" x 10'	2 pc(s)	P 150 / pc	P 300
Pipe hanger	3 inches	8 pc(s)	P 120 / pc	P 960
Pvc (drainline)	blue- 1 inch	1 pc(s)	P 200 / pc	P 200
Chipping works	3" x 3" diameter	6 mtrs	P 500 / mtr	P 3,000
Drain Hose	White -1/2"	7 ft	P 25 / ft	P 175
				22,155.00

Estimated Charges P 29,655.00

MASTER BEDROOM Area ≈ 22 sq.m

ACU 4 2.0hp Wallmounted Inverter *KSG-IWF-20Wfy-8K1M32*

Estimated Pipe Length : 27 ft
 Estimated Royal Cord Length : 32 ft

Initial Charge P 7,500.00

Includes:
 Labor
 10ft Copper Tube
 10ft Royal Cord
 Outdoor Bracket (wall)
 Other Consumables

Additional Charges	Description	Unit	Price Per Unit	Subtotal
Copper Tube	1/4"x 1/2"	17 ft	P 350 / ft	P 5,950
Royal Cord	2.mm2 x 4C	22 ft	P 100 / ft	P 2,200
Royal Cord (ODU-Breaker)	3.5mm2 x 3C	7 ft	P 60 / ft	P 420
Circuit Breaker(NEMA)	30A/ 1Ph	1 pc(s)	P 1,000 / pc	P 1,000
Rubber Insulation	2 1/8"x3/4" x 6'	4 pc(s)	P 650 / pc	P 2,600
Full Thread	3/8" x 10'	2 pc(s)	P 150 / pc	P 300
Pipe hanger	3 inches	8 pc(s)	P 120 / pc	P 960
Pvc (drainline)	blue- 1 inch	1 pc(s)	P 200 / pc	P 200
Chipping works	3" x 3" diameter	6 mtrs	P 500 / mtr	P 3,000
Drain Hose	White -1/2"	7 ft	P 25 / ft	P 175
				16,805.00

Estimated Charges P 24,305.00

DINING, BAR Area ≈ 59 sq.m

ACU 5 6.0hp Floor Ceiling Inverter *KLM-IC60-AA1M32-1*

Estimated Pipe Length : 66 ft
 Estimated Royal Cord Length : 73 ft

Initial Charge P 15,000.00

Includes:
 Labor
 10ft Copper Tube
 10ft Royal Cord
 Other Consumables

Additional Charges	Description	Unit	Price Per Unit	Subtotal
Copper Tube	3/8"x 5/8"	56 ft	P 400 / ft	P 22,400
Royal Cord	2.mm2 x 4C	63 ft	P 100 / ft	P 6,300
Royal Cord (ODU-Breaker)	5.5mm2 x 3C	7 ft	P 70 / ft	P 490
Circuit Breaker(NEMA)	60A/ 1Ph	1 pc(s)	P 1,000 / pc	P 1,000
Rubber Insulation	2 1/8"x3/4" x 6'	10 pc(s)	P 650 / pc	P 6,500
Full Thread	3/8" x 10'	5 pc(s)	P 150 / pc	P 750
Pipe hanger	3 inches	14 pc(s)	P 120 / pc	P 1,680
Indoor Bracket	fabricated	1 pc(s)	P 1,500 / pc	P 1,500
Outdoor Bracket(wall)	fabricated	1 pc(s)	P 5,000 / pc	P 5,000
Pvc (drainline)	blue- 1 inch	1 pc(s)	P 200 / pc	P 200
Chipping works	3" x 3" diameter	6 mtrs	P 500 / mtr	P 3,000
Drain Hose	White -1/2"	7 ft	P 25 / ft	P 175
				48,995.00

Estimated Charges P 63,995.00

LIVING Area ≈ 48 sq.m

ACU 6 6.0hp Floor Ceiling Inverter **KLM-IC60-AA1M32-1**
 Estimated Pipe Length : 60 ft
 Estimated Royal Cord Length : 67 ft
 Initial Charge P 15,000.00

- Includes:
 Labor
 10ft Copper Tube
 10ft Royal Cord
 Other Consumables

Additional Charges	Description	Unit	Price Per Unit	Subtotal
Copper Tube	3/8"x 5/8"	50 ft	P 400 / ft	P 20,000
Royal Cord	2.mm2 x 4C	57 ft	P 100 / ft	P 5,700
Royal Cord (ODU-Breaker)	5.5mm2 x 3C	7 ft	P 70 / ft	P 490
Circuit Breaker(NEMA)	60A/ 1Ph	1 pc(s)	P 1,000 / pc	P 1,000
Rubber Insulation	2 1/8"x3/4" x 6'	10 pc(s)	P 650 / pc	P 6,500
Full Thread	3/8" x 10'	5 pc(s)	P 150 / pc	P 750
Pipe hanger	3 inches	14 pc(s)	P 120 / pc	P 1,680
Indoor Bracket	fabricated	1 pc(s)	P 1,500 / pc	P 1,500
Outdoor Bracket(wall)	fabricated	1 pc(s)	P 5,000 / pc	P 5,000
Pvc (drainline)	blue- 1 inch	1 pc(s)	P 200 / pc	P 200
Chipping works	3" x 3" diameter	6 mtrs	P 500 / mtr	P 3,000
Drain Hose	White -1/2"	7 ft	P 25 / ft	P 175
				P 45,995.00

Estimated Charges **P 60,995.00**

MAIDS ROOM Area ≈ 17 sq.m

ACU 7 1.5hp Wallmounted Inverter **KSG-IWF-15Wfy-8K1M32**
 Estimated Pipe Length : 40 ft
 Estimated Royal Cord Length : 47 ft
 Initial Charge P 7,500.00

- Includes:
 Labor
 10ft Copper Tube
 10ft Royal Cord
 Outdoor Bracket (wall)
 Other Consumables

Additional Charges	Description	Unit	Price Per Unit	Subtotal
Copper Tube	1/4"x 3/8"	30 ft	P 350 / ft	P 10,500
Royal Cord	2.mm2 x 4C	37 ft	P 100 / ft	P 3,700
Royal Cord (ODU-Breaker)	3.5mm2 x 3C	7 ft	P 60 / ft	P 420
Circuit Breaker(NEMA)	20A/ 1Ph	1 pc(s)	P 1,000 / pc	P 1,000
Rubber Insulation	2 1/8"x3/4" x 6'	5 pc(s)	P 650 / pc	P 3,250
Full Thread	3/8" x 10'	2 pc(s)	P 150 / pc	P 300
Pipe hanger	3 inches	8 pc(s)	P 120 / pc	P 960
Pvc (drainline)	blue- 1 inch	1 pc(s)	P 200 / pc	P 200
Chipping works	3" x 3" diameter	6 mtrs	P 500 / mtr	P 3,000
Drain Hose	White -1/2"	7 ft	P 25 / ft	P 175
				P 23,505.00

Estimated Charges **P 31,005.00**

DRIVERS ROOM Area ≈ 12 sq.m

ACU 8 1.5hp Wallmounted Inverter **KSG-IWF-15Wfy-8K1M32**
 Estimated Pipe Length : 37 ft
 Estimated Royal Cord Length : 44 ft
 Initial Charge P 7,500.00

- Includes:
 Labor
 10ft Copper Tube
 10ft Royal Cord
 Outdoor Bracket (wall)
 Other Consumables

Additional Charges	Description	Unit	Price Per Unit	Subtotal
Copper Tube	1/4"x 3/8"	27 ft	P 350 / ft	P 9,450
Royal Cord	2.mm2 x 4C	34 ft	P 100 / ft	P 3,400
Royal Cord (ODU-Breaker)	3.5mm2 x 3C	7 ft	P 60 / ft	P 420
Circuit Breaker(NEMA)	20A/ 1Ph	1 pc(s)	P 1,000 / pc	P 1,000
Rubber Insulation	2 1/8"x3/4" x 6'	4 pc(s)	P 650 / pc	P 2,600
Full Thread	3/8" x 10'	2 pc(s)	P 150 / pc	P 300
Pipe hanger	3 inches	8 pc(s)	P 120 / pc	P 960
Pvc (drainline)	blue- 1 inch	1 pc(s)	P 200 / pc	P 200
Chipping works	3" x 3" diameter	6 mtrs	P 500 / mtr	P 3,000
Drain Hose	White -1/2"	7 ft	P 25 / ft	P 175
				P 21,505.00

Estimated Charges **P 29,005.00**

SECOND FLOOR**MASTER BEDROOM 2**

Area ≈ 24 sq.m

ACU 9 2.0hp Wallmounted Inverter**KSG-IWF-20Wfy-8K1M32**Estimated Pipe Length : 27 ft
Estimated Royal Cord Length : 34 ft

Initial Charge P 7,500.00

Includes:

Labor
10ft Copper Tube
10ft Royal Cord
Outdoor Bracket (wall)
Other Consumables

Additional Charges	Description	Unit	Price Per Unit	Subtotal
Copper Tube	1/4"x 1/2"	17 ft	P 350 / ft	P 5,950
Royal Cord	2.mm2 x 4C	24 ft	P 100 / ft	P 2,400
Royal Cord (ODU-Breaker)	3.5mm2 x 3C	7 ft	P 60 / ft	P 420
Circuit Breaker(NEMA)	30A/ 1Ph	1 pc(s)	P 1,000 / pc	P 1,000
Rubber Insulation	2 1/8"x3/4" x 6'	2 pc(s)	P 650 / pc	P 1,300
Full Thread	3/8" x 10'	1 pc(s)	P 150 / pc	P 150
Pipe hanger	3 inches	2 pc(s)	P 120 / pc	P 240
Pvc (drainline)	blue- 1 inch	1 pc(s)	P 200 / pc	P 200
Chipping works	3" x 3" diameter	6 mtrs	P 500 / mtr	P 3,000
Drain Hose	White -1/2"	7 ft	P 25 / ft	P 175 P
				<u>14,835.00</u>

Estimated Charges P 22,335.00**MASTER BEDROOM3**

Area ≈ 31 sq.m

ACU 10 2.5hp Wallmounted Inverter**KSG-IWF-25Wfy-8K1M32**Estimated Pipe Length : 43 ft
Estimated Royal Cord Length : 50 ft

Initial Charge P 8,500.00

Includes:

Labor
10ft Copper Tube
10ft Royal Cord
Outdoor Bracket
Other Consumables

Additional Charges	Description	Unit	Price Per Unit	Subtotal
Copper Tube	1/4"x 5/8"	33 ft	P 400 / ft	P 13,200
Royal Cord	2.mm2 x 4C	40 ft	P 100 / ft	P 4,000
Royal Cord (ODU-Breaker)	3.5mm2 x 3C	7 ft	P 60 / ft	P 420
Rubber Insulation	2 1/8"x3/4" x 6'	2 pc(s)	P 650 / pc	P 1,300
Full Thread	3/8" x 10'	2 pc(s)	P 150 / pc	P 300
Pipe hanger	3 inches	4 pc(s)	P 120 / pc	P 480
Circuit Breaker(NEMA)	30A/ 1Ph	1 pc(s)	P 1,000 / pc	P 1,000
Pvc (drainline)	blue- 1 inch	1 pc(s)	P 200 / pc	P 200
Chipping works	3" x 3" diameter	6 mtrs	P 500 / mtr	P 3,000
Drain Hose	White -1/2"	7 ft	P 25 / ft	P 175 P
				<u>24,075.00</u>

Estimated Charges P 32,575.00**ANTEROOM**

Area ≈ 20 sq.m

ACU 11 2.0hp Wallmounted Inverter**KSG-IWF-20Wfy-8K1M32**Estimated Pipe Length : 56 ft
Estimated Royal Cord Length : 61 ft

Initial Charge P 7,500.00

Includes:

Labor
10ft Copper Tube
10ft Royal Cord
Outdoor Bracket (wall)
Other Consumables

Additional Charges	Description	Unit	Price Per Unit	Subtotal
Copper Tube	1/4"x 1/2"	46 ft	P 350 / ft	P 16,100
Royal Cord	2.mm2 x 4C	51 ft	P 100 / ft	P 5,100
Royal Cord (ODU-Breaker)	3.5mm2 x 3C	7 ft	P 60 / ft	P 420
Circuit Breaker(NEMA)	30A/ 1Ph	1 pc(s)	P 1,000 / pc	P 1,000
Rubber Insulation	2 1/8"x3/4" x 6'	6 pc(s)	P 650 / pc	P 3,900
Full Thread	3/8" x 10'	2 pc(s)	P 150 / pc	P 300
Pipe hanger	3 inches	10 pc(s)	P 120 / pc	P 1,200
Pvc (drainline)	blue- 1 inch	1 pc(s)	P 200 / pc	P 200
Chipping works	3" x 3" diameter	6 mtrs	P 500 / mtr	P 3,000
Drain Hose	White -1/2"	7 ft	P 25 / ft	P 175 P
				<u>31,395.00</u>

Estimated Charges P 38,895.00**WALK IN CLOSET**

Area ≈ 29 sq.m

ACU 12 2.5hp Wallmounted Inverter **KSG-IWF-25WFY-8K1M32**
 Estimated Pipe Length : 63 ft
 Estimated Royal Cord Length : 70 ft
 Initial Charge P 8,500.00

Includes:
 Labor
 10ft Copper Tube
 10ft Royal Cord
 Outdoor Bracket
 Other Consumables

Additional Charges	Description	Unit	Price Per Unit	Subtotal
Copper Tube	1/4"x 5/8"	53 ft	P 400 / ft	P 21,200
Royal Cord	2.mm2 x 4C	60 ft	P 100 / ft	P 6,000
Royal Cord (ODU-Breaker)	5.5mm2 x 3C	7 ft	P 70 / ft	P 490
Rubber Insulation	2 1/8"x3/4" x 6'	10 pc(s)	P 650 / pc	P 6,500
Full Thread	3/8" x 10'	2 pc(s)	P 150 / pc	P 300
Pipe hanger	3 inches	14 pc(s)	P 120 / pc	P 1,680
Circuit Breaker(NEMA)	30A/ 1Ph	1 pc(s)	P 1,000 / pc	P 1,000
Pvc (drainline)	blue- 1 inch	1 pc(s)	P 200 / pc	P 200
Chipping works	3" x 3" diameter	6 mtrs	P 500 / mtr	P 3,000
Drain Hose	White -1/2"	7 ft	P 25 / ft	P 175
				P 40,545.00

Estimated Charges P 49,045.00

MASTER BEDROOM Area ≈ 29 sq.m

ACU 13 2.5hp Wallmounted Inverter **KSG-IWF-25WFY-8K1M32**
 Estimated Pipe Length : 82 ft
 Estimated Royal Cord Length : 89 ft
 Initial Charge P 8,500.00

Includes:
 Labor
 10ft Copper Tube
 10ft Royal Cord
 Outdoor Bracket
 Other Consumables

Additional Charges	Description	Unit	Price Per Unit	Subtotal
Copper Tube	1/4"x 5/8"	72 ft	P 400 / ft	P 28,800
Royal Cord	2.mm2 x 4C	79 ft	P 100 / ft	P 7,900
Royal Cord (ODU-Breaker)	3.5mm2 x 3C	7 ft	P 60 / ft	P 420
Rubber Insulation	2 1/8"x3/4" x 6'	12 pc(s)	P 650 / pc	P 7,800
Full Thread	3/8" x 10'	2 pc(s)	P 150 / pc	P 300
Pipe hanger	3 inches	16 pc(s)	P 120 / pc	P 1,920
Circuit Breaker(NEMA)	30A/ 1Ph	1 pc(s)	P 1,000 / pc	P 1,000
Pvc (drainline)	blue- 1 inch	1 pc(s)	P 200 / pc	P 200
Chipping works	3" x 3" diameter	6 mtrs	P 500 / mtr	P 3,000
Drain Hose	White -1/2"	7 ft	P 25 / ft	P 175
				P 51,515.00

Estimated Charges P 60,015.00

BEDROOM2 Area ≈ 25 sq.m

ACU 14 2.0hp Wallmounted Inverter **KSG-IWF-20WFY-8K1M32**
 Estimated Pipe Length : 82 ft
 Estimated Royal Cord Length : 87 ft
 Initial Charge P 7,500.00

Includes:
 Labor
 10ft Copper Tube
 10ft Royal Cord
 Outdoor Bracket (wall)
 Other Consumables

Additional Charges	Description	Unit	Price Per Unit	Subtotal
Copper Tube	1/4"x 1/2"	72 ft	P 400 / ft	P 28,800
Royal Cord	2.mm2 x 4C	77 ft	P 100 / ft	P 7,700
Royal Cord (ODU-Breaker)	3.5mm2 x 3C	7 ft	P 60 / ft	P 420
Circuit Breaker(NEMA)	30A/ 1Ph	1 pc(s)	P 1,000 / pc	P 1,000
Rubber Insulation	2 1/8"x3/4" x 6'	12 pc(s)	P 650 / pc	P 7,800
Full Thread	3/8" x 10'	2 pc(s)	P 150 / pc	P 300
Pipe hanger	3 inches	16 pc(s)	P 120 / pc	P 1,920
Pvc (drainline)	blue- 1 inch	1 pc(s)	P 200 / pc	P 200
Chipping works	3" x 3" diameter	6 mtrs	P 500 / mtr	P 3,000
Drain Hose	White -1/2"	7 ft	P 25 / ft	P 175
				P 51,315.00

Estimated Charges P 58,815.00

BEDROOM3 Area ≈ 26 sq.m

ACU 15 2.5hp Wallmounted Inverter **KSG-IWF-25Wfy-8K1M32**

Estimated Pipe Length : 79 ft
 Estimated Royal Cord Length : 84 ft
 Initial Charge P 8,500.00

Includes:
 Labor
 10ft Copper Tube
 10ft Royal Cord
 Outdoor Bracket (wall)
 Other Consumables

Additional Charges	Description	Unit	Price Per Unit	Subtotal
Copper Tube	1/4"x 5/8"	69 ft	P 400 / ft	P 27,600
Royal Cord	2.mm2 x 4C	74 ft	P 100 / ft	P 7,400
Royal Cord (ODU-Breaker)	3.5mm2 x 3C	7 ft	P 60 / ft	P 420
Circuit Breaker(NEMA)	30A/ 1Ph	1 pc(s)	P 1,000 / pc	P 1,000
Rubber Insulation	2 1/8"x3/4" x 6'	14 pc(s)	P 650 / pc	P 9,100
Full Thread	3/8" x 10'	2 pc(s)	P 150 / pc	P 300
Pipe hanger	3 inches	18 pc(s)	P 120 / pc	P 2,160
Scaffoldings	6sets	1	P 1,500	P 1,500
Pvc (drainline)	blue- 1 inch	1 pc(s)	P 200 / pc	P 200
Chipping works	3" x 3" diameter	6 mtrs	P 500 / mtr	P 3,000
Drain Hose	White -1/2"	7 ft	P 25 / ft	P 175
				P 52,855.00

Estimated Charges **P 61,355.00**

ANTEROOM2 Area ≈ 23 sq.m

ACU 16 2.0hp Wallmounted Inverter **KSG-IWF-20Wfy-8K1M32**

Estimated Pipe Length : 82 ft
 Estimated Royal Cord Length : 87 ft
 Initial Charge P 7,500.00

Includes:
 Labor
 10ft Copper Tube
 10ft Royal Cord
 Outdoor Bracket (wall)
 Other Consumables

Additional Charges	Description	Unit	Price Per Unit	Subtotal
Copper Tube	1/4"x 1/2"	72 ft	P 350 / ft	P 25,200
Royal Cord	2.mm2 x 4C	77 ft	P 100 / ft	P 7,700
Royal Cord (ODU-Breaker)	3.5mm2 x 3C	7 ft	P 60 / ft	P 420
Circuit Breaker(NEMA)	30A/ 1Ph	1 pc(s)	P 1,000 / pc	P 1,000
Rubber Insulation	2 1/8"x3/4" x 6'	10 pc(s)	P 650 / pc	P 6,500
Full Thread	3/8" x 10'	2 pc(s)	P 150 / pc	P 300
Pipe hanger	3 inches	14 pc(s)	P 120 / pc	P 1,680
Pvc (drainline)	blue- 1 inch	1 pc(s)	P 200 / pc	P 200
Chipping works	3" x 3" diameter	6 mtrs	P 500 / mtr	P 3,000
Drain Hose	White -1/2"	7 ft	P 25 / ft	P 175
				P 46,175.00

Estimated Charges **P 53,675.00**

Total Estimated Charges **P 749,360.00**

Validity: This quotation is valid for a period of fifteen (15) days from the date thereof, subject to our confirmation thereafter.

Note:

- 1 Location based in floor plan only. Recommendation for approval.
- 2 AC drain line will be tapped to the nearest drain provision provided by the customer's contractor.
- 3 Need for marking and site visit before installation.
- 4 We can do chipping works only, finishing and restoration of wall must be done by customer contractor.**
- 5 Working days: Monday to Saturday, 8am- 5pm with parking. Bring harness and rope.
- 6 Mechanical Plans, Permits, Electrical permits not included.
- 7 Defectors, masonry, carpentry, chipping & plastering (finishing & restoration) are not included in the installation.
- 8 Electrical power supply (feeder line) **230v/ 60hz/ 1ph**, is not included in the scope of work of Kolin.
- 9 **Final charges will be based on actual installation.**

Prepared by:

Jeoffrey Dadios
Field Surveyor

Customer Conformed:

Signature Over Printed Name

Reviewed by:

Engr. Adrian E. Nogoy
Project Engineer

02/02/2026

