



February 16, 2026

MR. MONTIEL DELOS SANTOS
CAVA ALFONSO EVENTS, SITIO HAWILIAN 2, BRGY. UPLI, ALFONSO CAVITE
TEL#: 0917-7771961

Dear Ma'am/Sir,

Kolin Marketing Inc., is extremely honored for your endorsement of Kolin brand and we are please to offer you with a special price/s for the following items.

A. EQUIPMENT & INSTALLATION - OPTION 1

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
7	UNIT/S	MODEL: KSG-IWF-10Wfy-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 11,484 Kj/h (1.0HP) FULL DC INVERTER W/ WIFI R-32	42,595.00	25,372.20	PHP	177,605.40
1	UNIT/S	MODEL: KSG-IWF-20Wfy-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 19,000 Kj/h (2.0HP) FULL DC INVERTER W/ WIFI R-32	59,595.00	38,292.20	PHP	38,292.20
1	UNIT/S	MODEL: KSG-IWF-30Wfy-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 29,500 Kj/h (3.0HP) FULL DC INVERTER W/ WIFI R-32	76,595.00	51,212.20	PHP	51,212.20
3	UNIT/S	MODEL: KLG-IF40-5G1M32 KOLIN FLOOR MOUNTED AIRCONDITIONER 37,980 Kj/h (3.0TR) FULL DC INVERTER R-32 SINGLE PHASE	113,195.00	79,028.20	PHP	237,084.60
10	UNIT/S	MODEL: KL-IF60-G6H1M32 KOLIN FLOOR MOUNTED AIRCONDITIONER 58,140 Kj/h (5.0TR) FULL DC INVERTER R32 SINGLE PHASE	165,995.00	112,156.20	PHP	1,121,562.00
TOTAL UNIT COST					PHP	1,625,756.40
ESTIMATED COST OF INSTALLATION (please see attached)					PHP	606,860.00
TOTAL ESTIMATED COST OF THE PROJECT					PHP	2,232,616.40

TERMS OF PAYMENT:

FULL PAYMENT OF UNIT AND DELIVERY CHARGE. IF CHECK, SUBJECT FOR 3 DAYS CLEARING.

BANK DETAILS:

* Unit/s: Account Name - KOLIN MARKETING INC. / Account# - 011808002307 (BDO-KALAYAAN)

* Installation: Will be provided by assigned installer.

** You may settle first payment for unit/s & delivery. Installation payment can be settled directly to installer after actual works.

WARRANTY:

FOR SPLIT TYPE : ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB , TEN (10) YEARS WARRANTY ON COMPRESSOR.

FOR FLOOR MOUNTED (Inverter): ONE (1) YEAR FREE PARTS AND LABOR, FIVE (5) YEARS WARRANTY ON COMPRESSOR.

NOTES: PRICES ARE SUBJECT TO CHANGE WITHOUT PRIOR NOTICE.

PRICES IS VAT INCLUSIVE.

** Cost of Installation is Package with the Unit(s), this cost cannot avail separately (cost will be based on actual works).

We thank you for giving opportunity to offer our product and services, hoping we receive your purchase order.

If you need assistance, don't hesitate to call the under signed at 0917-807-8607 or email at kmi_asst@kolinphil.com.ph

Very Truly Yours,

JANELLEN S. LIM
KMI-ASSISTANT

Noted By:

MART NATHANIEL R. FLORES
KMI-SUPERVISOR

KMI-QUOTE-02-26-0081
EMF-24%/7K/14K

Approved By:

MS. EDITH A M FLORES
AVP - FINANCE

Conforme

SIGNATURE OVER PRINTED NAME



Kolin Marketing, Inc.

1854 Sta. Rita St., Guadalupe Nuevo, Makati City

Tel.: (632) 8852-6473

Fax: (632) 8852-2170 / (632) 8852-4792

www.kolinphil.com.ph / kolinphilippines



AIRMASTER REFRIGERATION AND AIRCONDITIONING SERVICES

No. 158 San Jose Dasmariñas City Cavite *Contact Nos.: 0905 1554904 / 09184534431

Landline: (046) 424 3014

Customer Name:	MONTIER DELOS SANTOS	Date:	February 14, 2026
Customer Address:	CAVA ALFONSO EVENTS SITIO HAWILIAN 2, BRGY. UPLI ALFONSO CAVITE		

Qty	Unit Model	Unit Capacity/Type
7	KSG-IWF-10Wfy8K1M32	1.0HP Wall Mounted Inverter
1	KSG-IWF-20Wfy8K1M32	2.0HP Wall Mounted Inverter
1	KSG-IWF-30Wfy8K1M32	3.0HP Wall Mounted Inverter
3	KLg-IF40-5G1M32	4.0HP Floor Standing Inverter
10	KL-IF60-G6H1M32	6.0HP Floor Standing Inverter

Location/s:	DUPLEX ROOM 1	Area:	12.05 sqm.
ACU #:	1	Unit Model:	KSG-IWF-10Wfy8K1M32
		Unit Capacity/Type:	1.0HP Wall Mounted Inverter

Estimated Pipe Length	=	31	ft	
Estimated Royal Cord Length	=	36	ft	
Initial Charge				₱ 7,500.00
10ft Copper tube				
10ft Royal Cord				
Outdoor bracket Wall/Floor				
Consumables				
Testing and Commisioning				
Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	3/8"Ø x 1/4"Ø	21 ft	₱ 350.00 /ft	₱ 7,350.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	26 ft	100.00 /ft	2,600.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	* ft	60.00 /ft	
Circuir Breaker Weather Proof	20Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
Other works and materials	Fabrication of Outdoor Bracket	1 lot	₱ 2500.00 /lot	2,500.00
Estimated Charges				₱ 20,950.00

Location/s:	DUPLEX ROOM 2	Area:	13.88 sqm.		
ACU #:	2	Unit Model:	KSG-IWF-10WFY8K1M32	Unit Capacity/Type:	1.0HP Wall Mounted Inverter
Estimated Pipe Length = 30 ft Estimated Royal Cord Length = 35 ft Initial Charge ₱ 7,500.00 10ft Copper tube 10ft Royal Cord Outdoor bracket Wall/Floor Consumables Testing and Commissioning					
Installation Materials	Specification	Qty	Price per qty	Subtotal	
Insulated Copper tube	3/8"Ø x 1/4"Ø	20 ft	₱ 350.00 /ft	₱ 7,000.00	
Royal Cord (Comm wire)	2.0 sq.mm x 4c	25 ft	100.00 /ft	2,500.00	
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	* ft	60.00 /ft		
Circuit Breaker Weather Proof	20Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00	
Other works and materials	Fabrication of Outdoor Bracket	1 lot	₱ 2500.00 /lot	2,500.00	
Estimated Charges				₱ 20,500.00	

Location/s:	DUPLEX ROOM 3	Area:	13.42 sqm.		
ACU #:	3	Unit Model:	KSG-IWF-10WFY8K1M32	Unit Capacity/Type:	1.0HP Wall Mounted Inverter
Estimated Pipe Length = 33 ft Estimated Royal Cord Length = 38 ft Initial Charge ₱ 7,500.00 10ft Copper tube 10ft Royal Cord Outdoor bracket Wall/Floor Consumables Testing and Commissioning					
Installation Materials	Specification	Qty	Price per qty	Subtotal	
Insulated Copper tube	3/8"Ø x 1/4"Ø	23 ft	₱ 350.00 /ft	₱ 8,050.00	
Royal Cord (Comm wire)	2.0 sq.mm x 4c	28 ft	100.00 /ft	2,800.00	
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	* ft	60.00 /ft		
Circuit Breaker Weather Proof	20Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00	
Other works and materials	Fabrication of Outdoor Bracket	1 lot	₱ 2500.00 /lot	2,500.00	
Estimated Charges				₱ 21,850.00	

Location/s: DUPLEX DINING **Area:** 23.23 sqm.

ACU #: 4 **Unit Model:** KSG-IWF-20WFY8K1M32 **Unit Capacity/Type:** 2.0HP Wall Mounted Inverter

Estimated Pipe Length	=	38	ft	
Estimated Royal Cord Length	=	43	ft	
Initial Charge				₱ 8,500.00
10ft Copper tube				
10ft Royal Cord				
Outdoor bracket Wall/Floor				
Consumables				
Testing and Commisioning				
Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	28 ft	₱ 350.00 /ft	₱ 9,800.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	33 ft	100.00 /ft	3,300.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	* ft	60.00 /ft	
Circuir Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
Other works and materials	Fabrication of Outdoor Bracket	1 lot	₱ 2500.00 /lot	2,500.00
Estimated Charges				₱ 25,100.00

Location/s: BRIDAL 1ST FLOOR **Area:** 60.28 sqm.

ACU #: 5 **Unit Model:** KLG-IF40-5G1M32 **Unit Capacity/Type:** 4.0HP Floor Standing Inverter

Estimated Pipe Length	=	35	ft	
Estimated Royal Cord Length	=	40	ft	
Initial Charge				₱ 11,000.00
10ft Copper tube				
10ft Royal Cord				
Indoor bracket (floor)				
Consumables				
Testing and Commisioning				
Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	5/8"Ø x 3/8"Ø	25 ft	₱ 400.00 /ft	₱ 10,000.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	30 ft	100.00 /ft	3,000.00
Royal Cord (Power Supply)	(#10) 5.5 sqmm. x 3c	* ft	70.00 /ft	
Circuir Breaker Weather Proof	40Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
Other works and materials	Fabrication of Outdoor Bracket	1 lot	₱ 2500.00 /lot	2,500.00
Estimated Charges				₱ 27,500.00

Location/s: BRIDAL 2ND FLOOR **Area:** 29.79 sqm.

ACU #: 6 **Unit Model:** KSG-IWF-30WFY8K1M32 **Unit Capacity/Type:** 3.0HP Wall Mounted Inverter

Estimated Pipe Length = 33 ft
 Estimated Royal Cord Length = 38 ft
Initial Charge ₱ 8,500.00
 10ft Copper tube
 10ft Royal Cord
 Outdoor bracket Wall/Floor
 Consumables
 Testing and Commissioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	5/8"Ø x 1/4"Ø	23 ft	₱ 400.00 /ft	₱ 9,200.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	28 ft	100.00 /ft	2,800.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	* ft	60.00 /ft	
Circuit Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
Other works and materials	Fabrication of Outdoor Bracket	1 lot	₱ 2500.00 /lot	2,500.00
Estimated Charges				₱ 24,000.00

Location/s: BRIDAL ROOM 1 **Area:** 15.89 sqm.

ACU #: 7 **Unit Model:** KSG-IWF-10WFY8K1M32 **Unit Capacity/Type:** 1.0HP Wall Mounted Inverter

Estimated Pipe Length = 32 ft
 Estimated Royal Cord Length = 37 ft
Initial Charge ₱ 7,500.00
 10ft Copper tube
 10ft Royal Cord
 Outdoor bracket Wall/Floor
 Consumables
 Testing and Commissioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	3/8"Ø x 1/4"Ø	22 ft	₱ 350.00 /ft	₱ 7,700.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	27 ft	100.00 /ft	2,700.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	* ft	60.00 /ft	
Circuit Breaker Weather Proof	20Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
PVC Pipe	Ø 3/4' X 10'	4 pc	₱ 150.00 /set(s)	600.00
Other works and materials	Fabrication of Outdoor Bracket	1 lot	₱ 2500.00 /lot	2,500.00
Estimated Charges				₱ 22,000.00

Location/s: EVENTS HALL ACU #1 **Area:** 305.37 sqm.

ACU #: 8 **Unit Model:** KLG-IF40-5G1M32 **Unit Capacity/Type:** 4.0HP Floor Standing Inverter

Estimated Pipe Length = 74 ft
 Estimated Royal Cord Length = 79 ft
Initial Charge ₱ 11,000.00
 10ft Copper tube
 10ft Royal Cord
 Indoor bracket (floor)
 Consumables
 Testing and Commissioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	5/8"Ø x 3/8"Ø	64 ft	₱ 400.00 /ft	₱ 25,600.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	69 ft	100.00 /ft	6,900.00
Royal Cord (Power Supply)	(#10) 5.5 sqmm. x 3c	* ft	70.00 /ft	
Circuir Breaker Weather Proof	40Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
Other works and materials	L-Type Bracket	* lot	₱ /lot	
Estimated Charges				₱ 44,500.00

Location/s: EVENTS HALL ACU #2 **Area:** 305.37 sqm.

ACU #: 9 **Unit Model:** KLG-IF40-5G1M32 **Unit Capacity/Type:** 4.0HP Floor Standing Inverter

Estimated Pipe Length = 15 ft
 Estimated Royal Cord Length = 20 ft
Initial Charge ₱ 11,000.00
 10ft Copper tube
 10ft Royal Cord
 Indoor bracket (floor)
 Consumables
 Testing and Commissioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	5/8"Ø x 3/8"Ø	5 ft	₱ 400.00 /ft	₱ 2,000.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	10 ft	100.00 /ft	1,000.00
Royal Cord (Power Supply)	(#10) 5.5 sqmm. x 3c	* ft	70.00 /ft	
Circuir Breaker Weather Proof	40Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
Other works and materials	L-Type Bracket	* lot	₱ /lot	
Estimated Charges				₱ 15,000.00

Location/s: EVENTS HALL ACU #3 **Area:** 305.37 sqm.

ACU #: 10 **Unit Model:** KL-IF60-G6H1M32 **Unit Capacity/Type:** 6.0HP Floor Standing Inverter

Estimated Pipe Length = 83 ft
 Estimated Royal Cord Length = 88 ft
Initial Charge ₱ 14,000.00
 10ft Copper tube
 10ft Royal Cord
 Indoor bracket (floor)
 Consumables
 Testing and Commissioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	5/8"Ø x 3/8"Ø	73 ft	₱ 400.00 /ft	₱ 29,200.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	78 ft	100.00 /ft	7,800.00
Royal Cord (Power Supply)	(#10) 5.5 sqmm. x 3c	* ft	70.00 /ft	
Circuit Breaker Weather Proof	60Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
Other works and materials	L-Type Bracket	* lot	₱ /lot	
Estimated Charges				₱ 52,000.00

Location/s: EVENTS HALL ACU #4 **Area:** 305.37 sqm.

ACU #: 11 **Unit Model:** KL-IF60-G6H1M32 **Unit Capacity/Type:** 6.0HP Floor Standing Inverter

Estimated Pipe Length = 70 ft
 Estimated Royal Cord Length = 75 ft
Initial Charge ₱ 14,000.00
 10ft Copper tube
 10ft Royal Cord
 Indoor bracket (floor)
 Consumables
 Testing and Commissioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	5/8"Ø x 3/8"Ø	60 ft	₱ 400.00 /ft	₱ 24,000.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	65 ft	100.00 /ft	6,500.00
Royal Cord (Power Supply)	(#10) 5.5 sqmm. x 3c	* ft	70.00 /ft	
Circuit Breaker Weather Proof	60Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
Other works and materials	L-Type Bracket	* lot	₱ /lot	
Estimated Charges				₱ 45,500.00

Location/s: EVENTS HALL ACU #5 **Area:** 305.37 sqm.

ACU #: 12 **Unit Model:** KL-IF60-G6H1M32 **Unit Capacity/Type:** 6.0HP Floor Standing Inverter

Estimated Pipe Length	=	68	ft	
Estimated Royal Cord Length	=	73	ft	
Initial Charge				₱ 14,000.00
10ft Copper tube				
10ft Royal Cord				
Indoor bracket (floor)				
Consumables				
Testing and Commisioning				
Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	5/8"Ø x 3/8"Ø	58 ft	₱ 400.00 /ft	₱ 23,200.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	63 ft	100.00 /ft	6,300.00
Royal Cord (Power Supply)	(#10) 5.5 sqmm. x 3c	* ft	70.00 /ft	
Circuir Breaker Weather Proof	60Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
Other works and materials	L-Type Bracket	* lot	₱ /lot	
Estimated Charges				₱ 44,500.00

Location/s: EVENTS HALL ACU #6 **Area:** 305.37 sqm.

ACU #: 13 **Unit Model:** KL-IF60-G6H1M32 **Unit Capacity/Type:** 6.0HP Floor Standing Inverter

Estimated Pipe Length	=	56	ft	
Estimated Royal Cord Length	=	61	ft	
Initial Charge				₱ 14,000.00
10ft Copper tube				
10ft Royal Cord				
Indoor bracket (floor)				
Consumables				
Testing and Commisioning				
Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	5/8"Ø x 3/8"Ø	46 ft	₱ 400.00 /ft	₱ 18,400.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	51 ft	100.00 /ft	5,100.00
Royal Cord (Power Supply)	(#10) 5.5 sqmm. x 3c	* ft	70.00 /ft	
Circuir Breaker Weather Proof	60Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
Other works and materials	L-Type Bracket	* lot	₱ /lot	
Estimated Charges				₱ 38,500.00

Location/s:	EVENTS HALL GIRLS CR	Area:	sqm.		
ACU #:	14	Unit Model:	KSG-IWF-10WFY8K1M32	Unit Capacity/Type:	1.0HP Wall Mounted Inverter
Estimated Pipe Length	=	12	ft		
Estimated Royal Cord Length	=	17	ft		
Initial Charge					₱ 7,500.00
10ft Copper tube					
10ft Royal Cord					
Outdoor bracket Wall/Floor					
Consumables					
Testing and Commisioning					
Installation Materials		Specification	Qty	Price per qty	Subtotal
Insulated Copper tube		3/8"∅ x 1/4"∅	2 ft	₱ 350.00 /ft	₱ 700.00
Royal Cord (Comm wire)		2.0 sq.mm x 4c	7 ft	100.00 /ft	700.00
Royal Cord (Power Supply)		(#12) 3.5 sqmm. x 3c	* ft	60.00 /ft	
Circuir Breaker Weather Proof		20Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
Other works and materials		L-Type Outdoor Bracket	* lot	₱ /lot	
Estimated Charges					₱ 9,900.00

Location/s:	GIRLS CR	Area:	sqm.		
ACU #:	15	Unit Model:	KSG-IWF-10WFY8K1M32	Unit Capacity/Type:	1.0HP Wall Mounted Inverter
Estimated Pipe Length	=	10	ft		
Estimated Royal Cord Length	=	15	ft		
Initial Charge					₱ 7,500.00
10ft Copper tube					
10ft Royal Cord					
Outdoor bracket Wall/Floor					
Consumables					
Testing and Commisioning					
Installation Materials		Specification	Qty	Price per qty	Subtotal
Insulated Copper tube		3/8"∅ x 1/4"∅	0 ft	₱ 350.00 /ft	₱
Royal Cord (Comm wire)		2.0 sq.mm x 4c	5 ft	100.00 /ft	500.00
Royal Cord (Power Supply)		(#12) 3.5 sqmm. x 3c	* ft	60.00 /ft	
Circuir Breaker Weather Proof		20Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
Other works and materials		L-type Outdoor Bracket	* lot	₱ /lot	
Estimated Charges					₱ 9,000.00

Location/s:	MALE CR	Area:	sqm.	
ACU #:	16	Unit Model:	KSG-IWF-10Wfy8K1M32	
		Unit Capacity/Type:	1.0HP Wall Mounted Inverter	
Estimated Pipe Length	=	_____	ft	
Estimated Royal Cord Length	=	_____	ft	
Initial Charge			₱ 7,500.00	
10ft Copper tube 10ft Royal Cord Outdoor bracket Wall/Floor Consumables Testing and Commissioning				
Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	3/8"Ø x 1/4"Ø	_____	ft ₱ 350.00 /ft	₱ _____
Royal Cord (Comm wire)	2.0 sq.mm x 4c	_____	ft 100.00 /ft	_____
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	* _____	ft 60.00 /ft	_____
Circuit Breaker Weather Proof	20Amps / 1Ph	1	pc 1,000.00 /pc	1,000.00
Other works and materials	Fabrication of Outdoor Bracket	1	lot ₱ 2500.00 /lot	2,500.00
Estimated Charges				₱ 11,000.00

Location/s:	1ST FLOOR ACU #1	Area:	263.00 sqm.	
ACU #:	17	Unit Model:	KL-IF60-G6H1M32	
		Unit Capacity/Type:	6.0HP Floor Standing Inverter	
Estimated Pipe Length	=	50	ft	
Estimated Royal Cord Length	=	55	ft	
Initial Charge			₱ 14,000.00	
10ft Copper tube 10ft Royal Cord Indoor bracket (floor) Consumables Testing and Commissioning				
Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	5/8"Ø x 3/8"Ø	40	ft ₱ 400.00 /ft	₱ 16,000.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	45	ft 100.00 /ft	4,500.00
Royal Cord (Power Supply)	(#10) 5.5 sqmm. x 3c	* _____	ft 70.00 /ft	_____
Circuit Breaker Weather Proof	60Amps / 1Ph	1	pc 1,000.00 /pc	1,000.00
Other works and materials	Fabrication of Outdoor Bracket	1	lot ₱ 2500.00 /lot	2,500.00
Estimated Charges				₱ 38,000.00

Location/s: 1ST FLOOR ACU #2 Area: 263.00 sqm.

ACU #: 18 Unit Model: KL-IF60-G6H1M32 Unit Capacity/Type: 6.0HP Floor Standing Inverter

Estimated Pipe Length	=	15	ft		
Estimated Royal Cord Length	=	20	ft		
Initial Charge					₱ 14,000.00
10ft Copper tube					
10ft Royal Cord					
Indoor bracket (floor)					
Consumables					
Testing and Commissioning					
Installation Materials	Specification	Qty	Price per qty	Subtotal	
Insulated Copper tube	5/8"∅ x 3/8"∅	5 ft	₱ 400.00 /ft	₱ 2,000.00	
Royal Cord (Comm wire)	2.0 sq.mm x 4c	10 ft	100.00 /ft	1,000.00	
Royal Cord (Power Supply)	(#10) 5.5 sqmm. x 3c	* ft	70.00 /ft		
Circuit Breaker Weather Proof	60Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00	
Other works and materials	Fabrication of Outdoor Bracket	1 lot	₱ 2500.00 /lot	2,500.00	
Estimated Charges					₱ 20,500.00

Location/s: 1ST FLOOR ACU #3 Area: 263.00 sqm.

ACU #: 19 Unit Model: KL-IF60-G6H1M32 Unit Capacity/Type: 6.0HP Floor Standing Inverter

Estimated Pipe Length	=	51	ft		
Estimated Royal Cord Length	=	56	ft		
Initial Charge					₱ 14,000.00
10ft Copper tube					
10ft Royal Cord					
Indoor bracket (floor)					
Consumables					
Testing and Commissioning					
Installation Materials	Specification	Qty	Price per qty	Subtotal	
Insulated Copper tube	5/8"∅ x 3/8"∅	41 ft	₱ 400.00 /ft	₱ 16,400.00	
Royal Cord (Comm wire)	2.0 sq.mm x 4c	46 ft	100.00 /ft	4,600.00	
Royal Cord (Power Supply)	(#10) 5.5 sqmm. x 3c	* ft	70.00 /ft		
Circuit Breaker Weather Proof	60Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00	
Other works and materials	Floor Type Bracket	* lot	₱ /lot		
Estimated Charges					₱ 36,000.00

Location/s: 1ST FLOOR ACU #4 Area: 263.00 sqm.

ACU #: 20 Unit Model: KL-IF60-G6H1M32 Unit Capacity/Type: 6.0HP Floor Standing Inverter

Estimated Pipe Length	=	70	ft		
Estimated Royal Cord Length	=	75	ft		
Initial Charge					₱ 14,000.00
10ft Copper tube					
10ft Royal Cord					
Indoor bracket (floor)					
Consumables					
Testing and Commissioning					
Installation Materials	Specification	Qty	Price per qty	Subtotal	
Insulated Copper tube	5/8"∅ x 3/8"∅	60 ft	₱ 400.00 /ft	₱ 24,000.00	
Royal Cord (Comm wire)	2.0 sq.mm x 4c	65 ft	100.00 /ft	6,500.00	
Royal Cord (Power Supply)	(#10) 5.5 sqmm. x 3c	* ft	70.00 /ft		
Circuit Breaker Weather Proof	60Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00	
Other works and materials	Floor Type Bracket	* lot	₱ /lot		
Estimated Charges					₱ 45,500.00

Location/s: 2ND FLOOR Area: 168.00 sqm.

ACU #: 21 Unit Model: KL-IF60-G6H1M32 Unit Capacity/Type: 6.0HP Floor Standing Inverter

Estimated Pipe Length	=	40	ft		
Estimated Royal Cord Length	=	45	ft		
Initial Charge					₱ 14,000.00
10ft Copper tube					
10ft Royal Cord					
Indoor bracket (floor)					
Consumables					
Testing and Commissioning					
Installation Materials	Specification	Qty	Price per qty	Subtotal	
Insulated Copper tube	5/8"∅ x 3/8"∅	30 ft	₱ 400.00 /ft	₱ 12,000.00	
Royal Cord (Comm wire)	2.0 sq.mm x 4c	35 ft	100.00 /ft	3,500.00	
Royal Cord (Power Supply)	(#10) 5.5 sqmm. x 3c	* ft	70.00 /ft		
Circuit Breaker Weather Proof	60Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00	
Other works and materials	Fabrication of Outdoor Bracket	1 lot	₱ 2500.00 /lot	2,500.00	
Estimated Charges					₱ 33,000.00

Location/s: 2ND FLOOR ADDITIONAL UNIT Area: 168.00 sqm.

ACU #: 22 Unit Model: KL-IF60-G6H1M32 Unit Capacity/Type: 6.0HP Floor Standing Inverter

Estimated Pipe Length = 42 ft
 Estimated Royal Cord Length = 47 ft

Initial Charge ₱ 14,000.00

10ft Copper tube
 10ft Royal Cord
 Indoor bracket (floor)
 Consumables
 Testing and Commisioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	5/8"Ø x 3/8"Ø	32 ft	₱ 400.00 /ft	₱ 12,800.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	37 ft	100.00 /ft	3,700.00
Royal Cord (Power Supply)	(#10) 5.5 sqmm. x 3c	* ft	70.00 /ft	
Circuir Breaker Weather Proof	60Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
Other works and materials	Fabrication of Outdoor Bracket	1 lot	₱ 2500.00 /lot	2,500.00
Estimated Charges				₱ 34,000.00

Total Estimated Charges ₱ 638,800.00

INSTALLATION NOTE:

1. Mechanical plans, permit, electrical permit not included.
2. Deflector, masonry, carpentry, chipping & plastering, finishing & restoration are not included in the installation.
3. Air conditioning drain line and electrical power supply should be provided by the customer's contractor.

TERMS OF PAYMENT:

- 50% down payment before installation start
- 50% after work completion

BANK DETAILS: METROBANK

METROBANK ACCOUNT NAME: AIRMASTER REFRIGERATION AND AIRCONDITIONING SERVICE

METROBANK ACCOUNT NO: 354-3-35423994-0

PREPARED BY:

Myra A. Guillermo
MYRA A. GUILLERMO

APPROVED BY:

Wilson B. Arquillo
WILSON B. ARQUILLO

Total Estimated Charges:	₱ 638,800.00
Less 5% discount:	₱ 31,940.00
GRAND TOTAL:	₱ 606,860.00 //

CONFORME

Signature Over Printed Name

Date: _____

REVIEWED BY:

Engr. Adrian Nogoy
02/14/2026
ENGR. ADRIAN NOGOY
PROJECT ENGINEER-KPII