

MS. MILDRED UY
UY RESIDENCES, RSG COMPOUND, SITIO BAYUCAN DRIVE, BRGY. SAMPALOC TANAY RIZAL
TEL#: 0917-8361790

Dear Ma'am/Sir,

Kolin Marketing Inc., is extremely honored for your endorsement of Kolin brand and we are please to offer you with a special price/s for the following items.

A. EQUIPMENT & INSTALLATION

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED		AMOUNT
1	UNIT/S	MODEL: KLG-IF40-5G1M32	113,195.00	79,028.20	PHP	79,028.20
		KOLIN FLOOR MOUNTED AIRCONDITIONER				
		37,980 Kj/h (3.0TR) FULL DC INVERTER R-32 SINGLE PHASE				
2	UNIT/S	MODEL: KSM-IW25-WCT10M1M32	49,995.00	33,996.20	PHP	67,992.40
		KOLIN WALL MOUNTED CERTUS AIRCONDITIONER				
		23,210 Kj/h (2.5HP) REGULAR INVERTER W/ WIFI R-32				
1	UNIT/S	MODEL: KSM-IW20-WCT10M1M32	41,995.00	27,916.20	РНР	27,916.20
		KOLIN WALL MOUNTED CERTUS SERIES AIRCONDITIONER				
		18,990 Kj/h (2.0HP) REGULAR INVERTER W/ WIFI R-32				
1	UNIT/S	MODEL: KSM-IW15-WCT10M1M32	32,995.00	21,076.20	PHP	21,076.20
		KOLIN WALL MOUNTED CERTUS SERIES AIRCONDITIONER				
		12,660 Kj/h (1.5HP) REGULAR INVERTER W/ WIFI R-32				
TOTAL UNIT COST					PHP	/ 196,013.00
ESTIMATED COST OF INSTALLATION (please see attached)					PHP	, 102,038.00
OTHERS: DELIVERY CHARGE					PHP	f 600.00
TOTAL ESTIMATED COST OF THE PROJECT					PHP	298,651.00

TERMS OF PAYMENT:

FULL PAYMENT OF UNIT AND DELIVERY CHARGE. IF CHECK, SUBJECT FOR 3 DAYS CLEARING.

WARRANTY:

FOR SPLIT TYPE: ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB, TEN (10) YEARS WARRANTY ON COMPRESSOR. FOR WINDOW TYPE: ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB, TEN (10) YEARS WARRANTY ON COMPRESSOR.

NOTES: PRICES ARE SUBJECT TO CHANGE WITHOUT PRIOR NOTICE.

PRICES IS VAT INCLUSIVE.

- ** Cost of Installation is Package with the Unit(s), this cost cannot avail separately (cost will be based on actual).
- *** You may settle first payment for unit/s & delivery. Installation payment can be settled directly to installer after actual works.

We thank you for giving opportunity to offer our product and services, hoping we receive your purchase order.

If you need assistance, don't hesitate to call the under signed at 0917-807-8607 or email at kmi_asst@kolinphil.com.ph

Very Truly Yours,

JANELLEN S. MM KMI-ASSISTANT

Noted by:

MART NATHANIEL R. PLORES
KMI-SUPERVISOR

KMI-QUOTE-07-25-0539 ADR-24%/7K/4K Approved By:

MS. EDITHA M. FLORE

Conforme:

SIGNATURE OVER PRINTED NAME

Kolin Marketing, Inc.

1854 Sta. Rita St., Guadalupe Nuevo, Makati City

Tel.: (632) 8852-6473

Fax: (632) 8852-2170 / (632) 8852-4792 www.kolinphil.com.ph / kolinphilippines





JRA JERRICO

Refrigeration and Air-conditioning Services B4, 19 Felixvill, Mangahan, Sto. Niño Bilibiran, Binangonan Rizal

Email: iraairconditioning@gmail.com Contact Nos. 09267189004/09615215615

Attn:Ma'am Mildred Uy

Uy Residences RSG.Compound Sitio Bayucan Drive Brgy.Sampaloc Tanay Rizal 09178361790

Date: July 16,2025

Brand Kolin

FCU 1

2.5HP Wall Mounted

Event Area Total pipe Length

 $= 42 \, \text{ft.}$ = 47 ft

Estimated Royal Cord

Installations charge

Includes:

Labor 10 ft.copper tube 10ft,Royal Cord Consumables

Installations Materials Copper Tube Royal cord (com. wire) Royal cord (ACCU-BREAKER)

Pvc Blue Drain hose White QTY 5 UNITS

Qty

Description

% x 1/4

3/4 x 10

2mm x 4c

3.5mm x 3c

Area 81scm.

₱ 8,500.00

175.00

Price per qty Subtotal

400.00/ft 12,800.00 32 ft. 37 ft. 100.00/ft. 3,700.00 5ft. 60.00/ft 300.00 150.00/pc 900.00 6pcs. 7ft. 25/ft

P 17,875.00

Estimated CHARGES

₱ 26,375.00

FCU₂

2.5HP Wall Mounted

Event Area Total pipe Length

= 40 ft.

Estimated Royal Cord = 45ft.

Installations charge

Includes:

Labor 10 ft.copper tube

10ft.Royal Cord Consumables

Installations Materials Copper Tube Royal cord (com. wire) Royal cord (ACCU-BREAKER)

Pvc Blue Drain hose White Description 5/8 x 1/4

2mm x 4c 3.5mm x 3c 3/4 x 10 1/2

Qty 30 ft. 35 ft. 5ft 6pcs. 7ft.

Area 81sqm.

Price per qty 400.00/ft 100.00/ft. 60.00/ft 150.00/pc

25/ft.

12,000.00 3.500.00 300.00 900.00 175.00

Subtotal

₱ 8,500.00

P 16,875.00

Estimated CHARGES

₱ 25,375.00

FCU3 3.0TR \

Event Area

Area 81sqm.

Total pipe Length Estimated Royal Cord = 53 ft.

Installations charge

 $= 58 \, \text{ft.}$

P 11,000.00

Includes:

Labor

10 ft.copper tube 10ft.Royal Cord

Consumables

Installations Materials Copper Tube Royal cord (com. wire) Royal cord (ACCU-BREAKER)

2mm x 4c Pvc Blue Drain hose White

3.5mm x 3c 3/4 x 10 1/2

Description

5/s x 3/8

Qty 43 ft. 48ft. 5ft. 6pcs.

100.00/ft. 60.00/ft 150.00/pc 7ft. 25/ft.

Price per qty

400.00/ft

17,200.00 4,800.00 300.00 900.00 175.00

Subtotal

P 28,375.00

Estimated CHARGES

₱ 39,375.00

Gym Area

2.0HP Wall Mounted

Event Area Total pipe Length

= 10 ft. = 15 ft.

Estimated Royal Cord Installations charge

Includes:

Labor

10 ft.copper tube

10ft.Royal Cord Consumables Installations Materials

Copper Tube Royal cord (com. wire) Royal cord (ACCU-BREAKER) Pvc Blue

Drain hose White

Area 19sqm.

₱7,500.00

Description Price per qty Subtotal Qty 1/2 x 1/4 10 ft. 2mm x 4c 100.00/ft. 500.00 5ft. 3.5mm x 3c 60.00/ft 300.00 5ft. 3/4 x 10 1pcs. 150.00/pc 150.00 1/2 7ft. 25/ft. 175.00

P 1,125.00

Estimated CHARGES

₱ 8,625.00

OFFICE ROOM 1.5HP Wall Mounted Event Area

Area 16sqm.

Total pipe Length Estimated Royal Cord

= 10 ft. = 15 ft.

Installations charge

₽7,500.00

Includes:

Labor 10 ft.copper tube

10ft.Royal Cord

Consumables

Installations Materials Copper Tube Royal cord (com. wire) Royal cord (ACCU-BREAKER) Pvc Blue
 Description
 Qty

 % x 1/4
 10 ft.

 2mm x 4c
 5 ft.

 3.5mm x 3c
 5ft.

 ¾ x 10
 6pcs.

7ft.

Price per qty 100.00/ft. 60.00/ft 150.00/pc 25/ft.

500.00 300.00 150.00 175.00

Subtotal

₱ 1,125.00

Estimated Charges

Drain hose White

₱ 8,625.00

TOTAL ESTIMATAED CHARGE

P 108,375.00

Circuit Breaker weatherproof 5pcs(1000/pcs) 5x1000 = 5,000.00

1/2

1.a.2.5hp (30amps) 2 units

2.b. 3TR 9 40amps) 1 unit

3.c. 2.0hp (30amps) 1 unit

4.d.1.5hp (20amps) 1 unit

Estimated Total Charge

P 113,375.00

(Less Discount of 10% on Actual Total) = ₱ 113,375.00 x 10% = 11,337.50

₱ 113,375 - 11,337 = 102,038.00

Total Charge

P 102,038.00

Installation note:

- 1.. Mechanical Plans ,Permits,Electrical permit not included.
- 2.Deflector,Masonary,carpentry,chipping & plastering ,finishing & restoration are not included in the installation
- 3.Air conditioning drain line and electrical power supply should be provided by the customer's contractor.

Installation Warranty

One (1) Yr warranty for Parts & service 10yrs warranty for compressor

Mode of Payment Cash or Bank Transfer after installation

3453345441418

For installation payment method Cash or Bank Transfer Bank Details: Metro Bank Account name: Jerico R. De vera

Prepare by CONFORME

Monaliza A. Pepito

Signature Over Printed Name

Jerico R. De Vera Date:

Owner

Account #: