



March 13, 2025

MR. MILO RAMIREZ
AB 313 LAPU-LAPU ST., GALLERIA DE MAGALLANES, MAKATI CITY
TEL#: 0917-5221199

Dear Ma'am/Sir,

Kolin Marketing Inc., is extremely honored for your endorsement of Kolin brand and we are please to offer you with a special price/s for the following items.

A. EQUIPMENT & INSTALLATION

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
1	UNIT/S	MODEL: KSM-IW20-WCT10M1M32 KOLIN WALL MOUNTED CERTUS SERIES AIRCONDITIONER 18,990 Kj/h (2.0HP) REGULAR INVERTER R-32	41,995.00	27,916.20	PHP	27,916.20
TOTAL UNIT COST					PHP	27,916.20
ESTIMATED COST OF INSTALLATION (please see attached)					PHP	14,050.00
OTHERS: DELIVERY CHARGE					PHP	600.00
TOTAL ESTIMATED COST OF THE PROJECT					PHP	42,566.20

TERMS OF PAYMENT:

FULL PAYMENT OF UNIT AND DELIVERY CHARGE. IF CHECK, SUBJECT FOR 3 DAYS CLEARING.

WARRANTY:

FOR SPLIT TYPE : ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB , TEN (10) YEARS WARRANTY ON COMPRESSOR.

NOTES: PRICES ARE SUBJECT TO CHANGE WITHOUT PRIOR NOTICE.

PRICES IS VAT INCLUSIVE.

**** Cost of Installation is Package with the Unit(s), this cost cannot avail separately.**

We thank you for giving opportunity to offer our product and services, hoping we receive your purchase order.

If you need assistance, don't hesitate to call the under signed at 0917-807-8607 or email at kmi_asst@kolinphil.com.ph

Very Truly Yours,

JANELLEN S. LIM
KMI-ASSISTANT

Noted by:

MARTIN HAMIL R. FLORES
KMI-SUPERVISOR

Approved By:

MS. EDITHA M. FLORES
AVP - FINANCE

KMI-QUOTE-03-25-0184-rev1
REG-24%/4K

Conforme:

SIGNATURE OVER PRINTED NAME

Kolin Marketing, Inc.
1854 Sta. Rita St., Guadalupe Nuevo, Makati City
Tel.: (632) 8852-6473
Fax: (632) 8852-2170 / (632) 8852-4792
www.kolinphil.com.ph / kolinphilippines



March 7, 2025
 MILO RAMIREZ
 AB 313 Lapu-Lapu St. Galleria de Magallanes Makati City
 0917-5221199

MASTER BEDROOM Area 30 sqm

ACU 2 2.0 HP Wall Mounted Inverter KSM-1W20-WCT10M1M32 10'
 Estimated Pipe Length = 15 ft
 Estimated Royal Cord Length = 20 ft
 Initial Charge ₱ 7,500.00

Includes:
 Labor
 10ft Copper Tube
 10ft Royal Cord
 Outdoor Bracket (Wall)
 Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 1/2"	5 ft	₱ 350.00/ft	₱ 1,750.00
Royal Cord (comm. wire)	2 mm2 x 4C	10 ft	₱ 100.00/ft	₱ 1,000.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	₱ 60.00/ft	₱ 300.00
Circuit Breaker waterproof	30A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Dismantle	1.5HP Wall Mounted	1 set	₱ 2,500.00/set	₱ 2,500.00
				₱ 6,550.00

Estimated Charges ₱ 14,050.00



Validity: This quotation is valid for a period of fifteen (15) days from the date thereof, subject to our confirmation thereafter.

Installation notes:

- 1 Location of indoor and outdoor units were agreed by the customer and Kolin's surveyor
- 2 AC drain line will be tapped to the nearest drain provision provided by the customer's contractor
- 3 Need for site visit before installation
- 4 New Hole for Indoor area for MASTER BEDROOM ACU2
- 5 Working days: Monday to Saturday, 8am- 5pm with parking Need working permit
- 6 Mechanical Plans, Permits, Electrical permits not included
- 7 Deflectors, masonry, carpentry, chipping & plastering (finishing & restoration) are not included in the installation
- 8 Air conditioning drain line and Electrical power supply (feeder line) **220v/ 60hz/ 1ph** should be provided by customer's contractor
- 9 Final charges will be based on actual installation.

Prepared by
Jeffrey Dadios
 Field Surveyor

Reviewed by
Engr. Kenneth Zamora
 Service Supervisor Shop and Field Operation

Customer Conformer
 Signature Over Printed Name