



March 17, 2025

MR./MS. CARMEN & TINY PERFECTO
26B, KEW GARDEN CORNER THIRD ST., ST. IGNATIUS VILLAGE, QUEZON CITY
TEL#: 0969-3277827

Dear Ma'am/Sir,

Kolin Marketing Inc., is extremely honored for your endorsement of Kolin brand and we are please to offer you with a special price/s for the following items.

A. EQUIPMENT & INSTALLATION

** OPTION 2

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
1	UNIT/S	MODEL: KL-IF60-G6H1M32 KOLIN FLOOR MOUNTED AIRCONDITIONER 58,140 Kj/h (5.0TR) FULL DC INVERTER R32 SINGLE PHASE	165,995.00	126,156.20	PHP	126,156.20
1	UNIT/S	MODEL: KSM-IW15-WCT10M1M32 KOLIN WALL MOUNTED CERTUS SERIES AIRCONDITIONER 12,660 Kj/h (1.5HP) REGULAR INVERTER R-32	32,995.00	21,076.20	PHP	21,076.20
1	UNIT/S	MODEL: KA-200MCARINV32 KOLIN WINDOW TYPE CREO SERIES AIRCONDITIONER 19,800 Kj/h (2.0HP) FULL DC INVERTER R-32 WITH REMOTE (WxDxH) 26"x30.7"x16.8"	36,995.00	26,916.20	PHP	26,916.20
1	UNIT/S	MODEL: KA-150MCARINV32 KOLIN WINDOW TYPE CREO SERIES AIRCONDITIONER 12,800 Kj/h (1.5HP) FULL DC INVERTER R-32 WITH REMOTE (WxDxH) 17.7"x26.6"x13.8"	27,995.00	20,276.20	PHP	20,276.20
1	UNIT/S	MODEL: KA-100MCARINV32 KOLIN WINDOW TYPE CREO SERIES AIRCONDITIONER 9,700 Kj/h (1.0HP) FULL DC INVERTER R-32 WITH REMOTE (WxDxH) 17.7"x26.6"x13.8"	24,995.00	18,196.20	PHP	18,196.20
TOTAL UNIT COST					PHP	212,621.00
ESTIMATED COST OF INSTALLATION (please see attached)					PHP	46,150.00
OTHERS: DELIVERY CHARGE					PHP	600.00
TOTAL ESTIMATED COST OF THE PROJECT					PHP	259,371.00

TERMS OF PAYMENT:

FULL PAYMENT OF UNIT AND DELIVERY CHARGE. IF CHECK, SUBJECT FOR 3 DAYS CLEARING.

WARRANTY:

FOR FLOOR MOUNTED: ONE (1) YEAR FREE PARTS AND LABOR, FIVE (5) YEARS WARRANTY ON COMPRESSOR.
FOR SPLIT TYPE: ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB, TEN (10) YEARS WARRANTY ON COMPRESSOR.
FOR WINDOW TYPE: ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB, TEN (10) YEARS WARRANTY ON COMPRESSOR.

NOTES: PRICES ARE SUBJECT TO CHANGE WITHOUT PRIOR NOTICE.

PRICES IS VAT INCLUSIVE.

** Cost of Installation is Package with the Unit(s), this cost cannot avail separately (cost will be based on actual).

We thank you for giving opportunity to offer our product and services, hoping we receive your purchase order.

If you need assistance, don't hesitate to call the under signed at 0917-807-8607 or email at kmi_asst@kolinphil.com.ph

Very Truly Yours,

JANELLEN S. LIM
KMI-ASSISTANT

Noted by:

MART NATHANIEL FLORES
KMI-SUPERVISOR

Approved By:

MS. EDITHA M. FLORES
AVP - FINANCE

KMI-QUOTE-03-25-0206
REG-24%/4K/1.2K/1K/800

Conforme: _____
SIGNATURE OVER PRINTED NAME

Kolin Marketing, Inc.
1854 Sta. Rita St., Guadalupe Nuevo, Makati City
Tel.: (632) 8852-6473
Fax: (632) 8852-2170 / (632) 8852-4792
www.kolinphil.com.ph / kolinphilippines



MARCH 14, 2025

Carmen /Tiny Perfecto

26B, Kew Garden corner Third St. St Ignatius Village, Quezon City

0969-3277827

MODEL	QUANTITY	
KL-IF70-5G1M32	1	KL-IF70-5G1M32
KSM-IW15-WCT10M1M32	1	
KAG-200MCARINV32	1	
KAG-150MCARINV32	1	
KAG-100MCARINV32	1	

OPTION2

GROUND FLOOR

LIVING/DINING/KITCHEN	Area ≈ 44 sq.m
------------------------------	----------------

ACU 1	6.0hp Floor mounted Inverter	KL-IF70-5G1M32 (KL-IF70-5G1M32)					
	Estimated Pipe Length :	10	ft				
	Estimated Royal Cord Length :	15	ft				
	Initial Charge					P	14,000.00
	Includes:						
	Labor						
	10ft Copper Tube						
	10ft Royal Cord						
	Indoor Bracket						
	Other Consumables						
	Additional Charges	Description	Unit	Price Per Unit		Subtotal	
	Royal Cord	2.mm2 x 4C	5 ft	P 100.00 / ft	P	500.00	
	Royal Cord (ODU-Breaker)	5.5mm2 x 3C	5 ft	P 70.00 / ft	P	350.00	
	Circuit Breaker(NEMA)	60A/ 1Ph	1 pc(s)	P 1,000.00 / pc	P	1,000.00	
	Outdoor Bracket(wall)	Fabricated	1 pc(s)	P 5,000.00 / pc	P	5,000.00	
	PVC(Drainline)	Blue 3/4"	1 pc(s)	P 150.00 / pc	P	150.00	P 7,000.00

Estimated Charges	P 21,000.00
--------------------------	--------------------

GUEST ROOM	Area ≈ 9 sq.m
-------------------	---------------

ACU2	1.0hp Windowtype Inverter	KA-100MCARINV32					
	Initial charge					P	1,200.00
	Angle Bracket					P	600.00
	Estimated charges					P	1,800.00

2ND FLOOR

MARTIN ROOM	Area ≈ 14 sq.m
--------------------	----------------

ACU3	1.5hp Windowtype Inverter	KA-150MCARINV32					
	Initial charge					P	1,200.00
	Angle Bracket					P	600.00
	Estimated charges					P	1,800.00

TINY ROOM	Area ≈ 15 sq.m
------------------	----------------

ACU 4	1.5 hp Wallmounted Inverter	KSM-IW15-WCT10M1M32					
	Estimated Pipe Length :	30	ft				
	Estimated Royal Cord Length :	35	ft				
	Initial Charge					P	7,500.00
	Includes:						
	Labor						
	10ft Copper Tube						
	10ft Royal Cord						
	Outdoor Bracket(floor)						
	Other Consumables						
	Additional Charges	Description	Unit	Price Per Unit		Subtotal	
	Copper Tube	1/4"x 1/2"	20 ft	P 400.00 / ft	P	8,000.00	
	Royal Cord	2.mm2 x 4C	25 ft	P 100.00 / ft	P	2,500.00	
	Royal Cord (ODU-Breaker)	3.5mm2 x 3C	5 ft	P 60.00 / ft	P	300.00	
	Circuit Breaker(NEMA)	30A/ 1Ph	1 pc(s)	P 1,000.00 / pc	P	1,000.00	
	PVC(Drainline)	Blue 3/4"	3 pc(s)	P 150.00 / pc	P	450.00	P 12,250.00

Estimated Charges	P 19,750.00
--------------------------	--------------------

ATTICK

MASTER BEDROOM			Area ≈ 24 sq.m
ACU5	2.0hp Windowtype Inverter	KA-200MCARINV32	
	Initial charge	P	1,200.00
	Angle Bracket	P	600.00
Estimated charges			P 1,800.00
Total Estimated Charges			P 46,150.00

Validity: This quotation is valid for a period of fifteen (15) days from the date thereof, subject to our confirmation thereafter.

Note:

- 1 Location of indoor and outdoor units were agreed by the customer and Kolin's surveyor.
- 2 AC drain line will be tapped to the nearest drain provision provided by the customer's contractor.
- 3 Customer need to Larger the hole existing of ACU2.GUESTROOM, make a hole of ACU3 Martin room.
- 4 Coppertube and drainline expose in th area.
- 5 KA-100MCARINV and KA-150MCARINV Dimension: W x D x H, = 450.5 X 675 x 350 mm. (17.7 x 26.6 x 13.8 inches)
- 6 KA-200MCARINV Dimension: W x D x H, = 660 X 780 x 428 mm. (26 x 30.7 x 16.8 inches)
- 7 Working days: Monday to Saturday, 8am- 5pm with parking.
- 8 Mechanical Plans, Permits, Electrical permits not included.
- 9 Deflectors, masonry, carpentry, chipping & plastering (finishing & restoration) are not included in the installation.
- 10 Electrical power supply (feeder line) **220v/ 60hz/ 1ph** , is not included in the scope of work of Kolin.
Transfer power Supply to new location.
- 11 **Final charges will be based on actual installation.**

Prepared by:

Jeoffrey Dadios

Field Surveyor

Customer Conformance:

Signature Over Printed Name

Reviewed by:

Engr. Kenneth Zamora

Service Supervisor

Field and Shop Operation

