

March 19, 2026

MS. CANDICE CORRAL
 UNIT 4602 & 4603, CONNOR CONDOMINIUM, GREENHILLS CLUB FILIPINO ST., GREENHILLS CENTER, SAN JUAN CITY
 TEL#: 0917-6870523 / 0908-8109466

Dear Ma'am/Sir,

Kolin Marketing Inc., is extremely honored for your endorsement of Kolin brand and we are please to offer you with a special price/s for the following items.

A. EQUIPMENT & INSTALLATION

*** OPTION 1 ***

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
1	UNIT/S	MODEL: KS-IW20-MCAI1201M32 KOLIN WALL MOUNTED CERTUS A/ SERIES AIRCONDITIONER 19,000 KJ/h (2.0HP) FULL DC INVERTER W/ WIFI R-32	42,995.00	26,176.20	PHP	26,176.20
3	UNIT/S	MODEL: KS-IW15-MCAI1201M32 KOLIN WALL MOUNTED CERTUS A/ SERIES AIRCONDITIONER 12,880 KJ/h (1.5HP) FULL DC INVERTER W/ WIFI R-32	33,995.00	19,336.20	PHP	58,008.60
TOTAL UNIT COST					PHP	84,184.80
ESTIMATED COST OF INSTALLATION (please see attached)					PHP	121,580.00
OTHERS: DELIVERY CHARGE					PHP	600.00
TOTAL ESTIMATED COST OF THE PROJECT					PHP	206,364.80

*** OPTION 2 ***

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
1	UNIT/S	MODEL: KSG-IWF-20Wfy-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 19,000 KJ/h (2.0HP) FULL DC INVERTER W/ WIFI R-32	60,595.00	39,052.20	PHP	39,052.20
3	UNIT/S	MODEL: KSG-IWF-15Wfy-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 12,960 KJ/h (1.5HP) FULL DC INVERTER W/ WIFI R-32	47,595.00	29,172.20	PHP	87,516.60
TOTAL UNIT COST					PHP	126,568.80
ESTIMATED COST OF INSTALLATION (please see attached)					PHP	121,580.00
OTHERS: DELIVERY CHARGE					PHP	600.00
TOTAL ESTIMATED COST OF THE PROJECT					PHP	248,748.80

TERMS OF PAYMENT:

FULL PAYMENT OF UNIT AND DELIVERY CHARGE. IF CHECK, SUBJECT FOR 3 DAYS CLEARING.

BANK DETAILS:

- * Unit/s & Delivery: Account Name - KOLIN MARKETING INC. / Account# - 011808002307 (BDO-KALAYAAN)
- * Installation: Will be provided by assigned installer.
- ** *You may settle first payment for unit/s & delivery. Installation payment can be settled directly to installer after actual works.*

WARRANTY:


FOR SPLIT TYPE : ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB , TEN (10) YEARS WARRANTY ON COMPRESSOR.

NOTES: PRICES ARE SUBJECT TO CHANGE WITHOUT PRIOR NOTICE.


- PRICES IS VAT INCLUSIVE.
- ** *Cost of Installation is Package with the Unit(s), this cost cannot avail separately (cost will be based on actual works).*

We thank you for giving opportunity to offer our product and services, hoping we receive your purchase order.
 If you need assistance, don't hesitate to call the under signed at 0917-807-8607 or email at kmi_asst@kolinphil.com.ph
 ** *Need to sign waiver agreement due to under capacity of unit choice.*

Very Truly Yours,


 JANELLEN S. LIM
 KMI-ASSISTANT

Noted By:


 MARTINATHANIEL R. FLORES
 KMI-SUPERVISOR

Approved by:


 MS. EDITHA M. FLORES
 AVP - FINANCE

KMI-QUOTE-03-26-0147.3
 MMC-24%/7K

Conforme: _____
 SIGNATURE OVER PRINTED NAME



March 19, 2026
 Candice Corral
 Unit 4602 and 4603 Connor Condominium Greenhills Club Filipino St. Greenhills Center San Juan City
 0917-6870523, 0908-8109466

MODEL	Qty
KS-IW20-MCAI1201M32	1
KS-IW15-MCAI1201M32	3

MASTER BEDROOM Area 16 sqm

ACU 1 1.5 HP Wall Mounted Inverter *KS-IW15-MCAI1201M32*
 Estimated Pipe Length = 53 ft
 Estimated Royal Cord Length = 58 ft
 Initial Charge ₱ 7,500.00

Includes:
 Labor
 10ft Copper Tube
 10ft Royal Cord
 Outdoor Bracket (Floor)
 Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 3/8"	43 ft	₱ 350.00/ft	₱ 15,050.00
Royal Cord (comm. wire)	2 mm2 x 4C	48 ft	₱ 100.00/ft	₱ 4,800.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	7 ft	₱ 60.00/ft	₱ 420.00
Rubber Insulation	2 1/8" x 3/4" x 6'	10 pc/s	₱ 650.00/pc	₱ 6,500.00
Drain Hose	White -1/2"	7 ft	₱ 25.00/ft	₱ 175.00
				₱ 26,945.00

Estimated Charges ₱ 34,445.00

BEDROOM2 Area 12 sqm

ACU 2 1.5 HP Wall Mounted Inverter *KS-IW15-MCAI1201M32*
 Estimated Pipe Length = 46 ft
 Estimated Royal Cord Length = 51 ft
 Initial Charge ₱ 7,500.00

Includes:
 Labor
 10ft Copper Tube
 10ft Royal Cord
 Outdoor Bracket (Floor)
 Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 3/8"	36 ft	₱ 350.00/ft	₱ 12,600.00
Royal Cord (comm. wire)	2 mm2 x 4C	41 ft	₱ 100.00/ft	₱ 4,100.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	7 ft	₱ 60.00/ft	₱ 420.00
Rubber Insulation	2 1/8" x 3/4" x 6'	7 pc/s	₱ 650.00/pc	₱ 4,550.00
Drain pump		1 pc/s	₱ 2,900.00/pc	₱ 2,900.00
Drain pump hose		5 ft	₱ 10.00/ft	₱ 50.00
Drain Hose	White -1/2"	7 ft	₱ 25.00/ft	₱ 175.00
				₱ 24,795.00

Estimated Charges ₱ 32,295.00

LIVING, DINING, KITCHEN Area 30 sqm

ACU 3 2.0 HP Wall Mounted Inverter *KS-IW20-MCAI1201M32*
 Estimated Pipe Length = 33 ft
 Estimated Royal Cord Length = 38 ft
 Initial Charge ₱ 7,500.00

Includes:
 Labor
 10ft Copper Tube
 10ft Royal Cord
 Outdoor Bracket (Floor)
 Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	1/4" x 1/2"	23 ft	₱ 350.00/ft	₱ 8,050.00
Royal Cord (comm. wire)	2 mm2 x 4C	28 ft	₱ 100.00/ft	₱ 2,800.00
Royal Cord (ACCU-Breaker)	3.5mm x 3C	7 ft	₱ 60.00/ft	₱ 420.00
Rubber Insulation	2 1/8" x 3/4" x 6'	3 pc/s	₱ 650.00/pc	₱ 1,950.00
Drain pump		1 pc/s	₱ 2,900.00/pc	₱ 2,900.00
Drain pump hose		5 ft	₱ 10.00/ft	₱ 50.00
Drain Hose	White -1/2"	7 ft	₱ 25.00/ft	₱ 175.00
				₱ 16,345.00

Estimated Charges ₱ 23,845.00


UNIT 4603		Area	20 sqm
ACU 4	1.5 HP Wall Mounted Inverter Estimated Pipe Length = 46 ft Estimated Royal Cord Length = 51 ft Initial Charge	KS-IW15-MCA1201M32	₱ 7,500.00
	Includes: Labor 10ft Copper Tube 10ft Royal Cord Outdoor Bracket (Floor) Consumables		
Installation Materials	Description	Qty	Price per qty
Copper Tube	1/4" x 3/8"	36 ft	₱ 350.00/ft
Royal Cord (comm. wire)	2. mm2 x 4C	41 ft	₱ 100.00/ft
Royal Cord (ACCU-Breaker)	3.5mm x 3C	7 ft	₱ 60.00/ft
Rubber Insulation	2 1/8" x 3/4" x 6'	5 pc/s	₱ 650.00/pc
Drain pump		1 pc/s	₱ 2,900.00/pc
Drain pump hose		5 ft	₱ 10.00/ft
Drain Hose	White -1/2"	7 ft	₱ 25.00/ft
			₱ 23,495.00
Estimated Charges			₱ 30,995.00
Total Estimated Charges			₱ 121,580.00

Validity: This quotation is valid for a period of fifteen (15) days from the date thereof, subject to our confirmation thereafter.

Installation notes:

- 1 Location of indoor and outdoor units were agreed by the customer and Kolin's surveyor.
- 2 AC drain line will be tapped to the nearest drain provision provided by the customer's contractor.
- 3 This quotation is not yet final, for clarification modify, and for approval of bldg admin.
- 4 Units need a drain pump due to a high level of drainage line, except MASTER BEDROOM of 4602.
- 5 Need for marking and site visit before installation with installer.
- 7 Working days: Monday to Saturday, 8am- 5pm with parking. Need working permit.
- 8 Mechanical Plans, Permits, Electrical permits not included.
- 9 Deflectors, masonry, carpentry, chipping & plastering (finishing & restoration) are not included in the installation.
- 10 Air conditioning drain line and Electrical power supply (feeder line) **230v/ 60hz/ 1ph**, should be provided by customer's contractor. Each unit separate power supply.
- 11 Final charges will be based on actual installation.


Prepared by:


Jeffrey Dadios
Field Surveyor

Customer Conformed:

Signature Over Printed Name

Reviewed by:


03/19/2026
Engr. Adrian E. Nogoy
Project Engineer

March 19, 2026

CANDICE CORRAL

Unit 4602 and 4603 Connor Condominium Greenhills Club Filipino St. Greenhills Center San Juan City

Contact: 0917-6870523, 0908-8109466

Email

Please be informed that the air-conditioner you intend to purchase is under capacity as compared to the following unit that we proposed:

Area	Kolin's Recommendation	Customer's Choice	Remarks
LIVING,DINING,KITCHEN	KS-IW25-MCAI12O1M32	KS-IW20-MCAI12O1M32	Calculated 2.4hp under by 0.4 hp
UNIT 4603	KS-IW20-MCAI12O1M32	KS-IW15-MCAI12O1M32	Calculated 1.8hp under by 0.3 hp

Since the unit of your choice is under capacity, it is probable that you may experience the following;

1. Capacity of the unit to cool the area will take longer or it will not cool the area at all that may lead to your dissatisfaction with the cooling performance of our unit.
2. Power consumption will be higher due to frequent running of compressor for not reaching the desired temperature within the normal parameter.
3. Useful life of compressor will be shortened due to excessive running beyond the normal run cycle.


Considering the above conditions, we regret to inform you that we cannot guarantee the efficient performance of unit. Also, **One (1) year warranty for parts (compressor-10year).**

For your guidance and information


Prepared by:

Jeffrey Dadios
Surveyor

Approved by:


Mr. Alvin de Rivera
Service Manager

Noted by:


Engr. Adrian E. Nogoy
Project Engineer

Customer Conforme:

Signature Over Printed Name