



March 5, 2026

MS. NANCY ANG
U-40L WEST TOWER TWIN OAKS PLACE, SHAW BLVD. MANDALUYONG CITY
TEL#: 0917-8318868

Dear Ma'am/Sir,

Kolin Marketing Inc. is extremely honored for your endorsement of Kolin brand and we are please to offer you with a special price/s for the following items.

A. EQUIPMENT & INSTALLATION

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
1	UNIT/S	MODEL: KVM-30VAH1M-O KOLIN VERSAMATCH SERIES AIRCONDITIONER 24,485 kJ/h (3.0HP) OUTDOOR UNIT INVERTER R32	61,495.00	46,736.20	PHP	46,736.20
2	UNIT/S	MODEL: KVM-15IWAH-I KOLIN VERSAMATCH SERIES AIRCONDITIONER INVERTER 12,660 kJ/h (1.5HP) WALL MOUNTED INDOOR UNIT R32	13,495.00	10,256.20	PHP	20,512.40
1	UNIT/S	MODEL: KSG-IWF-30Wfy-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 29,500 KJ/h (3.0HP) FULL DC INVERTER W/ WIFI R-32	78,095.00	52,352.20	PHP	52,352.20
TOTAL UNIT COST					PHP	119,600.80
ESTIMATED COST OF INSTALLATION (please see attached)					PHP	64,800.00
TOTAL ESTIMATED COST OF THE PROJECT					PHP	184,400.80

TERMS OF PAYMENT:

FULL PAYMENT OF UNIT AND DELIVERY CHARGE. IF CHECK, SUBJECT FOR 3 DAYS CLEARING.

BANK DETAILS:

- ** You may settle first payment for unit/s & delivery. Installation payment can be settled directly to installer after actual works.
- * Unit/s & Delivery: Account Name - KOLIN MARKETING INC. / Account# - 011808002307 (BDO-KALAYAAN)
- * Installation: Will be provided by assigned installer.

WARRANTY:

FOR VERSAMATCH: ONE (1) YEAR FREE PARTS AND LABOR, FIVE (5) YEARS WARRANTY ON COMPRESSOR.
FOR SPLIT TYPE : ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB , TEN (10) YEARS WARRANTY ON COMPRESSOR.

NOTES: PRICES ARE SUBJECT TO CHANGE WITHOUT PRIOR NOTICE.

PRICES IS VAT INCLUSIVE.
** Cost of Installation is Package with the Unit(s), this cost cannot avail separately (cost will be based on actual works).

We thank you for giving opportunity to offer our product and services, hoping we receive your purchase order.

If you need assistance, don't hesitate to call the under signed at 0917-807-8607 or email at kmi_asst@kolinphil.com.ph

Very Truly Yours,

JANELLEN S. LIM
KMI-ASSISTANT

Noted by:
MARTIN FLORES
KMI-SUPERVISOR

Approved By:

MS. EDITHA M. FLORES
AVP - FINANCE

Conforme:

SIGNATURE OVER PRINTED NAME

KMI-QUOTE-03-26-0115
REG-24%/7K



Kolin Marketing, Inc.

1854 Sta. Rita St., Guadalupe Nuevo, Makati City
Tel.: (632) 8852-6473
Fax: (632) 8852-2170 / (632) 8852-4792
www.kolinphil.com.ph / kolinphilippines

March 3, 2026

Nancy Ang

U-40L West Tower Twin Oaks Place Shaw blvd. Mandaluyong City
Cel No. : 0917-8318868

Please find below the quotation for the installation.

Model	Qty
KVM - 30VAH1M - O	1
KVM - 15IWAH - I	2
KSG-IWF-30WFY-8K1M32	1

Living, Dining and Kitchen

ACU 1

**WALL MOUNTED INVERTER
KSG-IWF-30WFY-9K1M32**

Estimated Pipe Length ≈ 40
Estimated Wire Length ≈ 47

Initial Charge

Includes:

10ft Copper Tube
10ft Royal Cord
Other Consumables

P 8,500.00

Additional charge

		Unit	Price per unit	Total price
Copper Tube	(5/8" x 1/4")	30 ft	P 400.00 / ft	P 12,000.00
Royal Cord	(2.0 mm ² , 4c)	37 ft	P 100.00 / ft	P 3,700.00
Royal Cord	(3.5 mm ² , 3c)	5 ft	P 60.00 / ft	P 300.00
Circuit Breaker	(30A)	1 pc/s	P 1,000.00 / pc/s	P 1,000.00
Outdoor Bracket		1 pc/s	P 2,500.00 / pc/s	P 2,500.00
PVC Pipe	(3/4")	2 pc/s	P 150.00 / pc/s	P 300.00
				<u>P 19,800.00</u>

ESTIMATED CHARGES

P 28,300.00

Master Bedroom**VERSAMATCH****First Pair****KVM-30VAH1M - O & KVM - 15IWAH - I**

Estimated Pipe Length ≈ 26

Estimated Wire Length ≈ 33

Initial Charge

P 8,500.00

Includes:

10ft Copper Tube

10ft Royal Cord

Labor

Other Consumables

Additional charge

		Unit	Price per unit	Total price
Copper Tube	(1/4" x 3/8")	16 ft	P 350.00 / ft	P 5,600.00
Royal Cord	(2mm ² , 4c)	23 ft	P 100.00 / ft	P 2,300.00
Royal Cord	(3.5 mm ² , 4c)	7 ft	P 100.00 / ft	P 700.00
Outdoor Bracket	Floor Bracket	1 pc/s	P 2,500.00 / pc/s	P 2,500.00
PVC Pipe	(3/4")	5 pc/s	P 150.00 / pc/s	P 750.00
Drain Hose		4 ft	P 25.00 / ft	P 100.00
				<u>P 11,950.00</u>

ESTIMATED CHARGES

P 20,450.00

SUCCEEDING UNIT**Bedroom 1****KVM - 10IWAH - I**

Estimated Pipe Length ≈ 15

Estimated Wire Length ≈ 22

Installation Charge:

P 8,500.00

		Unit	Price per unit	Total price
Copper Tube	(1/4" x 3/8")	5 ft	P 350.00 / ft	P 1,750.00
Royal Cord	(2mm ² , 4c)	12 ft	P 100.00 / ft	P 1,200.00
Drain Hose		4 ft	P 25.00 / ft	P 100.00
				<u>P 3,050.00</u>

ESTIMATED CHARGES

P 11,550.00

Dismantle of Existing Aircon unit

P 4,500.00

Total Estimated Charge for the Installation**P 64,800.00**

Note:

1. Location of indoor and outdoor unit were agreed by customer and RKH surveyor .
2. Masonry and carpentry (plastering and finishing or retouch) are not included in the installation.
3. Electrical power supply (feeder line) not included in scope of work of KOLIN.
4. Not Included Mobilization (If Night Work).
5. Restoration Works will provide/Shoulder by Customer.
6. Need Additional Electrical Supply for Additional Aircon unit (Customer will provide), Need Electrician.
7. Final charges will be based on actual installation.

Prepared By. :