



November 13, 2025

MR. DARYL ONG
MARIPOSA ST. CORNER MILFLORES ST., GENEVA GARDENS SUBD., BRGY. NORTH FAIRVIEW, QUEZON CITY
ATTN: MR. ROBY SABULAO
TEL#: 0949-4443169 / 0970-7793699

Dear Ma'am/Sir,

Kolin Marketing Inc., is extremely honored for your endorsement of Kolin brand and we are please to offer you with a special price/s for the following items.

A. EQUIPMENT & INSTALLATION - revision

* OPTION 1 *

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
3	UNIT/S	MODEL: KS-IW15-MCA11201M32 KOLIN WALL MOUNTED CERTUS A/ SERIES AIRCONDITIONER 12,880 Kj/h (1.5HP) FULL DC INVERTER W/ WIFI R-32	33,995.00	19,336.20	PHP	58,008.60
3	UNIT/S	MODEL: KS-IW25-MCA11201M32 KOLIN WALL MOUNTED CERTUS A/ SERIES AIRCONDITIONER 23,800 Kj/h (2.5HP) FULL DC INVERTER W/ WIFI R-32	50,995.00	31,756.20	PHP	95,268.60
2	UNIT/S	MODEL: KS-IW20-MCA11201M32 KOLIN WALL MOUNTED CERTUS A/ SERIES AIRCONDITIONER 19,000 Kj/h (2.0HP) FULL DC INVERTER W/ WIFI R-32	42,995.00	26,176.20	PHP	52,352.40
2	UNIT/S	MODEL: KLG-IF40-5G1M32 KOLIN FLOOR MOUNTED AIRCONDITIONER 37,980 Kj/h (3.0TR) FULL DC INVERTER R-32 SINGLE PHASE	113,195.00	79,028.20	PHP	158,056.40
1	UNIT/S	MODEL: KS-IW10-MCA11201M32 KOLIN WALL MOUNTED CERTUS A/ SERIES AIRCONDITIONER 9,800 Kj/h (1.0HP) FULL DC INVERTER W/ WIFI R-32	30,995.00	17,056.20	PHP	17,056.20
TOTAL UNIT COST					PHP	380,742.20
ESTIMATED COST OF INSTALLATION (please see attached)					PHP	210,050.00
OTHERS: DELIVERY CHARGE					PHP	600.00
TOTAL ESTIMATED COST OF THE PROJECT					PHP	591,392.20

TERMS OF PAYMENT:

FULL PAYMENT OF UNIT AND DELIVERY CHARGE. IF CHECK, SUBJECT FOR 3 DAYS CLEARING.

BANK DETAILS:

* Unit/s & Delivery: Account Name - KOLIN MARKETING INC. / Account# - 011808002307 (BDO-KALAYAAN)

* Installation: Will be provided by assigned installer.

** You may settle first payment for unit/s & delivery. Installation payment can be settled directly to installer after actual works.

WARRANTY:

FOR SPLIT TYPE : ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB , TEN (10) YEARS WARRANTY ON COMPRESSOR.

FOR FLOOR MOUNTED (Inverter): ONE (1) YEAR FREE PARTS AND LABOR, FIVE (5) YEARS WARRANTY ON COMPRESSOR.

NOTES: PRICES ARE SUBJECT TO CHANGE WITHOUT PRIOR NOTICE.

PRICES IS VAT INCLUSIVE.

** Cost of Installation is Package with the Unit(s), this cost cannot avail separately (cost will be based on actual works).

We thank you for giving opportunity to offer our product and services, hoping we receive your purchase order.

If you need assistance, don't hesitate to call the under signed at 0917-807-8607 or email at kmi_asst@kolinphil.com.ph

Very Truly Yours,

JANELLEN S. LIM
KMI-ASSISTANT

Noted By:
MARTHA DANIEL R. FLORES
KMI-SUPERVISOR

Approved By:

MS. EDITHA M. FLORES
AVP - FINANCE

Conforme:

SIGNATURE OVER PRINTED NAME

KMI-QUOTE-10-25-0763-rev
REG-24% 6/5/7K

Kolin Marketing, Inc.

1854 Sta. Rita St., Guadalupe Nuevo, Makati City

Tel.: (632) 8852-6473

Fax: (632) 8852-2170 / (632) 8852-4792

www.kolinphil.com.ph / kolinphilippines



GODSPEED REFRIGERATION AND AIRCONDITIONING SERVICES

Customer Name:	DARYL ONG	Date:	OCTOBER 15 2025
Customer Address:	MARIPOSA ST. COR. MILFLORES GENEVA GARDEN NORTH FAIRVIEW QC		

Qty	Unit Model	Unit Capacity/Type
3	KSG-IWF-15Wfy8K1M32	1.5HP Wall Mounted Inverter
3	KSG-IWF-25Wfy8K1M32	2.5HP Wall Mounted Inverter
2	KSG-IWF-20Wfy8K1M32	2.0HP Wall Mounted Inverter
2	KLg-IF40-5G1M32	4.0HP Floor Standing Inverter
1	KSG-IWF-10Wfy8K1M32	1.0HP Wall Mounted Inverter

Location/s:	ENTRANCE / MAIN DOOR	Area:	12.00 sqm.
-------------	----------------------	-------	------------

ACU #:	1	Unit Model:	KSM-IW15-WCT10M1M32	Unit Capacity/Type:	1.5HP Wall Mounted Inverter
--------	---	-------------	---------------------	---------------------	-----------------------------

Estimated Pipe Length = 12 ft

Estimated Royal Cord Length = 17 ft

Initial Charge ₱ 7,500.00

10ft Copper tube

10ft Royal Cord

Outdoor bracket Wall/Floor

Consumables

Testing and Commisioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	2 ft	₱ 350.00 /ft	₱ 700.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	7 ft	100.00 /ft	700.00
Circuir Breaker Weather Proof	20Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
PVC Pipe	Ø3/4" x 10'	1 pc	150.00 /pc(s)	150.00

Estimated Charges ₱ 10,050.00

Location/s:	GUEST ROOM	Area:	14.00	sqm.
--------------------	-------------------	--------------	--------------	-------------

ACU #:	2	Unit Model:	KSM-IW15-WCT10M1M32	Unit Capacity/Type:	1.5HP Wall Mounted Inverter
---------------	----------	--------------------	----------------------------	----------------------------	------------------------------------

Estimated Pipe Length = 20 ft

Estimated Royal Cord Length = 25 ft

Initial Charge ₱ 7,500.00

10ft Copper tube

10ft Royal Cord

Outdoor bracket Wall/Floor

Consumables

Testing and Commisioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	10 ft	₱ 350.00 /ft	₱ 3,500.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	15 ft	100.00 /ft	1,500.00
Circuir Breaker Weather Proof	20Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
PVC Pipe	Ø3/4" x 10'	1 pc	150.00 /pc(s)	150.00

Estimated Charges ₱ 13,650.00

Location/s:	MUSIC ROOM	Area:	30.00	sqm.
--------------------	-------------------	--------------	--------------	-------------

ACU #:	3	Unit Model:	KSG-IWF-25WFY8K1M32	Unit Capacity/Type:	2.5HP Wall Mounted Inverter
---------------	----------	--------------------	----------------------------	----------------------------	------------------------------------

Estimated Pipe Length = 22 ft

Estimated Royal Cord Length = 27 ft

Initial Charge ₱ 8,500.00

10ft Copper tube

10ft Royal Cord

Outdoor bracket Wall/Floor

Consumables

Testing and Commisioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	5/8"Ø x 1/4"Ø	12 ft	₱ 400.00 /ft	₱ 4,800.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	17 ft	100.00 /ft	1,700.00
Circuir Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
PVC Pipe	Ø3/4" x 10'	1 pc	150.00 /pc(s)	150.00

Estimated Charges ₱ 16,150.00

Location/s:		DINING ROOM		Area:	37.00	sqm.
ACU #:	4	Unit Model:	KLG-IF40-5G1M32		Unit Capacity/Type:	4.0HP Floor Standing Inverter
<div>Estimated Pipe Length = 30 ft</div> <div>Estimated Royal Cord Length = 35 ft</div> <div>Initial Charge ₱ 11,000.00</div> <div>10ft Copper tube</div> <div>10ft Royal Cord</div> <div>Indoor bracket (floor)</div> <div>Consumables</div> <div>Testing and Commisioning</div>						
Installation Materials		Specification	Qty	Price per qty	Subtotal	
Insulated Copper tube		5/8"Ø x 3/8"Ø	20 ft	₱ 400.00 /ft	₱ 8,000.00	
Royal Cord (Comm wire)		2.0 sq.mm x 4c	25 ft	100.00 /ft	2,500.00	
Circuir Breaker Weather Proof		40Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00	
PVC Pipe		Ø3/4" x 10'	1 pc	150.00 /pc(s)	150.00	
Estimated Charges					₱ 22,650.00	

Location/s:		WIC		Area:	21.00	sqm.
ACU #:	5	Unit Model:	KSG-IWF-20Wfy8K1M32		Unit Capacity/Type:	2.0HP Wall Mounted Inverter
<div>Estimated Pipe Length = 29 ft</div> <div>Estimated Royal Cord Length = 34 ft</div> <div>Initial Charge ₱ 8,500.00</div> <div>10ft Copper tube</div> <div>10ft Royal Cord</div> <div>Outdoor bracket Wall/Floor</div> <div>Consumables</div> <div>Testing and Commisioning</div>						
Installation Materials		Specification		Qty	Price per qty	Subtotal
Insulated Copper tube		1/2"Ø x 1/4"Ø		19 ft	₱ 350.00 /ft	₱ 6,650.00
Royal Cord (Comm wire)		2.0 sq.mm x 4c		24 ft	100.00 /ft	2,400.00
Circuir Breaker Weather Proof		30Amps / 1Ph		1 pc	1,000.00 /pc	1,000.00
PVC Pipe		Ø3/4" x 10'		1 pc	150.00 /pc(s)	150.00
Estimated Charges						₱ 18,700.00

Location/s:	MATERS BEDROOM	Area:	49.00	sqm.
-------------	----------------	-------	-------	------

ACU #:	6	Unit Model:	KLG-IF40-5G1M32	Unit Capacity/Type:	4.0HP Floor Standing Inverter
--------	---	-------------	-----------------	---------------------	-------------------------------

Estimated Pipe Length = 43 ft

Estimated Royal Cord Length = 48 ft

Initial Charge ₱ 11,000.00

10ft Copper tube

10ft Royal Cord

Indoor bracket (floor)

Consumables

Testing and Commisioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	5/8"Ø x 3/8"Ø	33 ft	₱ 400.00 /ft	₱ 13,200.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	38 ft	100.00 /ft	3,800.00
Circuit Breaker Weather Proof	40Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
PVC Pipe	Ø3/4" x 10'	1 pc	150.00 /pc(s)	150.00

Estimated Charges ₱ 29,150.00

Location/s:	BEDROOM 1	Area:	19.50	sqm.
-------------	-----------	-------	-------	------

ACU #:	7	Unit Model:	KSG-IWF-20WFY8K1M32	Unit Capacity/Type:	2.0HP Wall Mounted Inverter
--------	---	-------------	---------------------	---------------------	-----------------------------

Estimated Pipe Length = 43 ft

Estimated Royal Cord Length = 48 ft

Initial Charge ₱ 8,500.00

10ft Copper tube

10ft Royal Cord

Outdoor bracket Wall/Floor

Consumables

Testing and Commisioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	33 ft	₱ 350.00 /ft	₱ 11,550.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	38 ft	100.00 /ft	3,800.00
Circuit Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
PVC Pipe	Ø3/4" x 10'	1 pc	150.00 /pc(s)	150.00

Estimated Charges ₱ 25,000.00

AIRCONDITIONING SERVICES
SPEED BELIEFATION AND

Location/s:	BEDROOM 2	Area:	15.00	sqm.
--------------------	------------------	--------------	--------------	-------------

ACU #:	8	Unit Model:	KSG-IWF-15WFY8K1M32	Unit Capacity/Type:	1.5HP Wall Mounted Inverter
---------------	----------	--------------------	----------------------------	----------------------------	------------------------------------

Estimated Pipe Length = 29 ft

Estimated Royal Cord Length = 34 ft

Initial Charge ₱ 7,500.00

10ft Copper tube

10ft Royal Cord

Outdoor bracket Wall/Floor

Consumables

Testing and Commisioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	3/8"Ø x 1/4"Ø	19 ft	₱ 350.00 /ft	₱ 6,650.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	24 ft	100.00 /ft	2,400.00
Circuir Breaker Weather Proof	20Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
PVC Pipe	Ø3/4" x 10'	1 pc	150.00 /pc(s)	150.00

Estimated Charges ₱ 17,700.00

Location/s:	MAIDS ROOM	Area:	9.00	sqm.
--------------------	-------------------	--------------	-------------	-------------

ACU #:	9	Unit Model:	KSG-IWF-10WFY8K1M32	Unit Capacity/Type:	1.0HP Wall Mounted Inverter
---------------	----------	--------------------	----------------------------	----------------------------	------------------------------------

Estimated Pipe Length = 30 ft

Estimated Royal Cord Length = 35 ft

Initial Charge ₱ 7,500.00

10ft Copper tube

10ft Royal Cord

Outdoor bracket Wall/Floor

Consumables

Testing and Commisioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	3/8"Ø x 1/4"Ø	20 ft	₱ 350.00 /ft	₱ 7,000.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	25 ft	100.00 /ft	2,500.00
Circuir Breaker Weather Proof	20Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00

Estimated Charges ₱ 18,000.00

Location/s:	LIVINGROOM	Area:	44.00	sqm.
--------------------	------------	--------------	-------	------

ACU #:	10	Unit Model:	KSG-IWF-25Wfy8K1M32	Unit Capacity/Type:	2.5HP Wall Mounted Inverter
---------------	----	--------------------	---------------------	----------------------------	-----------------------------

Estimated Pipe Length = 28 ft

Estimated Royal Cord Length = 33 ft

Initial Charge ₱ 8,500.00

10ft Copper tube

10ft Royal Cord

Outdoor bracket Wall/Floor

Consumables

Testing and Commisioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	5/8"Ø x 1/4"Ø	18 ft	₱ 400.00 /ft	₱ 7,200.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	23 ft	100.00 /ft	2,300.00
Circuir Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00

Estimated Charges ₱ 19,000.00

Location/s:	LIVINGROOM 2ND	Area:	44.00	sqm.
--------------------	----------------	--------------	-------	------

ACU #:	11	Unit Model:	KSG-IWF-25Wfy8K1M32	Unit Capacity/Type:	2.5HP Wall Mounted Inverter
---------------	----	--------------------	---------------------	----------------------------	-----------------------------

Estimated Pipe Length = 30 ft

Estimated Royal Cord Length = 35 ft

Initial Charge ₱ 8,500.00

10ft Copper tube

10ft Royal Cord

Outdoor bracket Wall/Floor

Consumables

Testing and Commisioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	5/8"Ø x 1/4"Ø	20 ft	₱ 400.00 /ft	₱ 8,000.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	25 ft	100.00 /ft	2,500.00
Circuir Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00

Estimated Charges ₱ 20,000.00

AIRCONDITIONING SERVICES
GOODSPEED REPAIRS AND

NOTATION

Mounting/Installation of FCU and ACCU to designated and approved location.
lay-out of new refrigerant copper piping with rubber insulation.
lay-out of communication control wire with electrical pipe conduit.
installation of consumable materials such as nuts, clamps, bolts, tapes, drain pipes
to complete installation works.
Flushing and Leak testing of entire unit using nitrogen gas.
Vacuuming of entire system using vacuum pump to free the system from moisture and air.
Charging of freon if needed, test run, observation and commissioning of unit.
Mobilization and demobilization.
Start-up checklist documentation of unit to be submitted to supplier for warranty purposes.


Mode of Payment :

- * 50% - Down payment
- * 30% - Progress billing
- * 20% - Upon Completion

BDO CHECKING ACCOUNT : 013798000969

GODSPEED REFRIGERATION AND AIRCONDITIONING SERVICES

Conform Prepared By:


Bonnevie Chan Ruiz

ADMIN

OWNER/ REPRESENTATIVE