



November 18, 2025

MR. DARYL ONG
MARIPOSA ST. CORNER MILFLORES ST., GENEVA GARDENS SUBD., BRGY. NORTH FAIRVIEW, QUEZON CITY
ATTN: MR. ROBY SABULAO
TEL#: 0949-4443169 / 0970-7793699

Dear Ma'am/Sir,

Kolin Marketing Inc., is extremely honored for your endorsement of Kolin brand and we are please to offer you with a special price/s for the following items.

A. EQUIPMENT & INSTALLATION - revision 2

* OPTION 2 *

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
4	UNIT/S	MODEL: KSG-IWF-15WFF-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 12,960 Kj/h (1.5HP) FULL DC INVERTER W/ WIFI R-32	46,595.00	27,946.25	PHP	111,785.00
4	UNIT/S	MODEL: KSG-IWF-20WFF-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 19,000 Kj/h (2.0HP) FULL DC INVERTER W/ WIFI R-32	59,595.00	37,696.25	PHP	150,785.00
1	UNIT/S	MODEL: KSG-IWF-25WFF-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 25,560 Kj/h (2.5HP) FULL DC INVERTER W/ WIFI R-32	68,995.00	44,746.25	PHP	44,746.25
3	UNIT/S	MODEL: KSG-IWF-30WFF-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 29,500 Kj/h (3.0HP) FULL DC INVERTER W/ WIFI R-32	76,595.00	50,446.25	PHP	151,338.75
TOTAL UNIT COST					PHP	458,655.00
ESTIMATED COST OF INSTALLATION (please see attached)					PHP	224,800.00
TOTAL ESTIMATED COST OF THE PROJECT					PHP	683,455.00

TERMS OF PAYMENT:

FULL PAYMENT OF UNIT AND DELIVERY CHARGE. IF CHECK, SUBJECT FOR 3 DAYS CLEARING.

BANK DETAILS:

* Unit/s & Delivery: Account Name - KOLIN MARKETING INC. / Account# - 011808002307 (BDO-KALAYAAN)

* Installation: Will be provided by assigned installer.

** You may settle first payment for unit/s & delivery. Installation payment can be settled directly to installer after actual works.

WARRANTY:

FOR SPLIT TYPE : ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB , TEN (10) YEARS WARRANTY ON COMPRESSOR.

NOTES: PRICES ARE SUBJECT TO CHANGE WITHOUT PRIOR NOTICE.

PRICES IS VAT INCLUSIVE.

** Cost of Installation is Package with the Unit(s), this cost cannot avail separately (cost will be based on actual works).

We thank you for giving opportunity to offer our product and services, hoping we receive your purchase order.

If you need assistance, don't hesitate to call the under signed at 0917-807-8607 or email at kmi_asst@kolinphil.com.ph

Very Truly Yours,

JANELLEN S. LIM
KMI-ASSISTANT

Noted By:
MART NATHANIEL R. FLORES
KMI-SUPERVISOR

Approved By:
MS. EDITHA M. FLORES
AVP - FINANCE

Conforme:

SIGNATURE OVER PRINTED NAME

KMI-QUOTE-10-25-0763-rev2
JCY-25%/7K





GODSPEED REFRIGERATION AND AIRCONDITIONING SERVICES

Customer Name:	DARYL ONG	Date:	OCTOBER 15 2025
Customer Address:	MARIPOSA ST. COR. MILFLORES GENEVA GARDEN NORTH FAIRVIEW QC		

Qty	Unit Model	Unit Capacity/Type
4	KSG-IWF-15Wfy8K1M32	1.5HP Wall Mounted Inverter
4	KSG-IWF-20Wfy8K1M32	2.0HP Wall Mounted Inverter
1	KSG-IWF-25Wfy8K1M32	2.5HP Wall Mounted Inverter
3	KSG-IWF-30Wfy8K1M32	3.0HP Wall Mounted Inverter
12 UNITS		

Location/s:	ENTRANCE / MAIN DOOR		Area:	12.00		
ACU #:		Unit Model:	KSM-IW15-WCT10M1M32		Unit Capacity/Type:	1.5HP Wall Mounted Inverter

Estimated Pipe Length = 12 ft

Estimated Royal Cord Length = 17 ft

Initial Charge

₱ 7,500.00

10ft Copper tube

10ft Royal Cord

Outdoor bracket Wall/Floor

Consumables

Testing and Commisioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	2 ft	₱ 350.00 /ft	₱ 700.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	7 ft	100.00 /ft	700.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	* ft	60.00 /ft	
Circuit Breaker Weather Proof	20Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
Outdoor Unit Bracket Type	Fabricated floor	* set	62,500.00 /set	
Indoor Unit Bracket Type		* set	/set	
WAC Angle Bracket		* set	/set	
PVC Pipe	Ø3/4" x 10'	1 pc	150.00 /pc(s)	150.00
Leak Test existing copper tube	*	* set	/set(s)	
Dismantle existing unit	*	* unit	/unit	
Chipping works		* mtr	500.00 /mtr	
Other works and materials	*	* lot	₱ * /lot	
Estimated Charges				₱ 10,050.00

Location/s:	GUEST ROOM			Area:	14.00		
ACU #:		Unit Model:	KSM-IW15-WCT10M1M32		Unit Capacity/Type:	1.5HP Wall Mounted Inverter	

Estimated Pipe Length	=	20	ft	
Estimated Royal Cord Length	=	25	ft	
Initial Charge				₱ 7,500.00
10ft Copper tube				
10ft Royal Cord				
Outdoor bracket Wall/Floor				
Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	10 ft	₱ 350.00 /ft	₱ 3,500.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	15 ft	100.00 /ft	1,500.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	* ft	60.00 /ft	
Circuit Breaker Weather Proof	20Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
Outdoor Unit Bracket Type	Fabricated floor	* set	62,500.00 /set	
Indoor Unit Bracket Type		* set	/set	
WAC Angle Bracket		* set	/set	
PVC Pipe	Ø3/4" x 10'	1 pc	150.00 /pc(s)	150.00
Leak Test existing copper tube	*	* set	/set(s)	
Dismantle existing unit	*	* unit	/unit	
Chipping works		* mtr	500.00 /mtr	
Other works and materials	*	* lot	₱ * /lot	
Estimated Charges				₱ 13,650.00

Location/s:	MUSIC ROOM			Area:	30.00	sqm.
ACU #:		Unit Model:	KSG-IWF-25WFY8K1M32		Unit Capacity/Type:	2.5HP Wall Mounted Inverter

Estimated Pipe Length	=	22	ft	
Estimated Royal Cord Length	=	27	ft	
Initial Charge				₱ 8,500.00
10ft Copper tube				
10ft Royal Cord				
Outdoor bracket Wall/Floor				
Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	5/8"Ø x 1/4"Ø	12 ft	₱ 400.00 /ft	₱ 4,800.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	17 ft	100.00 /ft	1,700.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	* ft	60.00 /ft	
Circuit Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
Outdoor Unit Bracket Type	Fabricated floor	* set	62,500.00 /set	
Indoor Unit Bracket Type	*	* set	/set	
WAC Angle Bracket		* set	/set	
PVC Pipe	Ø3/4" x 10'	1 pc	150.00 /pc(s)	150.00
Leak Test existing copper tube	*	* set	/set(s)	
Dismantle existing unit	*	* unit	/unit	
Chipping works		* mtr	500.00 /mtr	
Other works and materials	*	* lot	₱ * /lot	
Estimated Charges				₱ 16,150.00

Location/s:	DINING ROOM	Area:	37.00	sqm.
-------------	-------------	-------	-------	------

ACU #:		Unit Model:	KSG-IWF-30WFY8K1M32	Unit Capacity/Type:	3.0HP Wall Mounted Inverter
--------	--	-------------	---------------------	---------------------	-----------------------------

Estimated Pipe Length = 30 ft

Estimated Royal Cord Length = 35 ft

Initial Charge ₱ 8,500.00

10ft Copper tube

10ft Royal Cord

Outdoor bracket Wall/Floor

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	5/8"Ø x 1/4"Ø	20 ft	₱ 400.00 /ft	₱ 8,000.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	25 ft	100.00 /ft	2,500.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	* ft	60.00 /ft	
Circuit Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
Outdoor Unit Bracket Type	Fabricated floor	* set	62,500.00 /set	
Indoor Unit Bracket Type	*	* set	/set	
WAC Angle Bracket		* set	/set	
PVC Pipe	Ø3/4" x 10'	1 pc	150.00 /pc(s)	150.00
Leak Test existing copper tube	*	* set	/set(s)	
Dismantle existing unit	*	* unit	/unit	
Chipping works		* mtr	500.00 /mtr	
Other works and materials	*	* lot	₱ * /lot	

Estimated Charges ₱ 20,150.00

Location/s:	WIC	Area:	21.00	sqm.
-------------	-----	-------	-------	------

ACU #:		Unit Model:	KSG-IWF-20WFY8K1M32	Unit Capacity/Type:	2.0HP Wall Mounted Inverter
--------	--	-------------	---------------------	---------------------	-----------------------------

Estimated Pipe Length = 29 ft

Estimated Royal Cord Length = 34 ft

Initial Charge ₱ 8,500.00

10ft Copper tube

10ft Royal Cord

Outdoor bracket Wall/Floor

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	19 ft	₱ 350.00 /ft	₱ 6,650.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	24 ft	100.00 /ft	2,400.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	* ft	60.00 /ft	
Circuit Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
Outdoor Unit Bracket Type	Fabricated floor	* set	62,500.00 /set	
Indoor Unit Bracket Type	*	* set	/set	
WAC Angle Bracket		* set	/set	
PVC Pipe	Ø3/4" x 10'	1 pc	150.00 /pc(s)	150.00
Leak Test existing copper tube	*	* set	/set(s)	
Dismantle existing unit	*	* unit	/unit	
Chipping works		* mtr	500.00 /mtr	
Other works and materials	*	* lot	₱ * /lot	

Estimated Charges ₱ 18,700.00

Location/s:	MATERS BEDROOM		Area:	49.00	sqm.	
ACU #:		Unit Model:	KSG-IWF-20Wfy8K1M32		Unit Capacity/Type:	2.0HP Wall Mounted Inverter

Estimated Pipe Length	=	43	ft	
Estimated Royal Cord Length	=	48	ft	
Initial Charge				₱ 8,500.00
10ft Copper tube				
10ft Royal Cord				
Outdoor bracket Wall/Floor				
Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	33 ft	₱ 350.00 /ft	₱ 11,550.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	38 ft	100.00 /ft	3,800.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	* ft	60.00 /ft	
Circuit Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
Outdoor Unit Bracket Type	Fabricated floor	* set	62,500.00 /set	
Indoor Unit Bracket Type	*	* set	/set	
WAC Angle Bracket		* set	/set	
PVC Pipe	Ø3/4" x 10'	1 pc	150.00 /pc(s)	150.00
Leak Test existing copper tube	*	* set	/set(s)	
Dismantle existing unit	*	* unit	/unit	
Chipping works		* mtr	500.00 /mtr	
Other works and materials	*	* lot	₱ * /lot	
Estimated Charges				₱ 25,000.00

Location/s:	MATERS BEDROOM 2	Area:	49.00	sqm.	
ACU #:		Unit Model:	KSG-IWF-20Wfy8K1M32	Unit Capacity/Type:	2.0HP Wall Mounted Inverter

Estimated Pipe Length	=	35	ft	
Estimated Royal Cord Length	=	40	ft	
Initial Charge				₱ 8,500.00
10ft Copper tube				
10ft Royal Cord				
Outdoor bracket Wall/Floor				
Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	25 ft	₱ 350.00 /ft	₱ 8,750.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	30 ft	100.00 /ft	3,000.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	* ft	60.00 /ft	
Circuit Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
Outdoor Unit Bracket Type	Fabricated floor	* set	62,500.00 /set	
Indoor Unit Bracket Type	*	* set	/set	
WAC Angle Bracket		* set	/set	
PVC Pipe	Ø3/4" x 10'	1 pc	150.00 /pc(s)	150.00
Leak Test existing copper tube	*	* set	/set(s)	
Dismantle existing unit	*	* unit	/unit	
Chipping works		* mtr	500.00 /mtr	
Other works and materials	*	* lot	₱ * /lot	
Estimated Charges				₱ 21,400.00

Location/s:	BEDROOM 1			Area:	19.50	sqm.
ACU #:		Unit Model:	KSG-IWF-20WY8K1M32		Unit Capacity/Type:	2.0HP Wall Mounted Inverter

Estimated Pipe Length = 43 ft

Estimated Royal Cord Length = 48 ft

Initial Charge ₱ 8,500.00

10ft Copper tube

10ft Royal Cord

Outdoor bracket Wall/Floor

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	1/2"Ø x 1/4"Ø	33 ft	₱ 350.00 /ft	₱ 11,550.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	38 ft	100.00 /ft	3,800.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	* ft	60.00 /ft	
Circuit Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
Outdoor Unit Bracket Type	Fabricated floor	* set	62,500.00 /set	
Indoor Unit Bracket Type	*	* set	/set	
WAC Angle Bracket		* set	/set	
PVC Pipe	Ø3/4" x 10'	1 pc	150.00 /pc(s)	150.00
Leak Test existing copper tube	*	* set	/set(s)	
Dismantle existing unit	*	* unit	/unit	
Chipping works		* mtr	500.00 /mtr	
Other works and materials	*	* lot	₱ * /lot	
Estimated Charges				₱ 25,000.00

Location/s:	BEDROOM 2		Area:	15.00	sqm.
ACU #:		Unit Model:	KSG-IWF-15WF8K1M32	Unit Capacity/Type:	1.5HP Wall Mounted Inverter

Estimated Pipe Length = 29 ft

Estimated Royal Cord Length = 34 ft

Initial Charge ₱ 7,500.00

10ft Copper tube

10ft Royal Cord

Outdoor bracket Wall/Floor

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	3/8"Ø x 1/4"Ø	19 ft	₱ 350.00 /ft	₱ 6,650.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	24 ft	100.00 /ft	2,400.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	* ft	60.00 /ft	
Circuit Breaker Weather Proof	20Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
Outdoor Unit Bracket Type	Fabricated floor	* set	62,500.00 /set	
Indoor Unit Bracket Type	*	* set	/set	
WAC Angle Bracket		* set	/set	
PVC Pipe	Ø3/4" x 10'	1 pc	150.00 /pc(s)	150.00
Leak Test existing copper tube	*	* set	/set(s)	
Dismantle existing unit	*	* unit	/unit	
Chipping works		* mtr	500.00 /mtr	
Other works and materials	*	* lot	₱ * /lot	
Estimated Charges				₱ 17,700.00

Location/s:	MAIDS ROOM		Area:	9.00	sqm.			
ACU #:		Unit Model:	KSG-IWF-15WFY8K1M32		Unit Capacity/Type:	1.5HP Wall Mounted Inverter		

Estimated Pipe Length = 30 ft
Estimated Royal Cord Length = 35 ft

Initial Charge ₱ 7,500.00

10ft Copper tube
10ft Royal Cord
Outdoor bracket Wall/Floor

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	3/8"Ø x 1/4"Ø	20 ft	₱ 350.00 /ft	₱ 7,000.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	25 ft	100.00 /ft	2,500.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	* ft	60.00 /ft	
Circuit Breaker Weather Proof	20Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
Outdoor Unit Bracket Type	Fabricated floor	* set	62,500.00 /set	
Indoor Unit Bracket Type	*	* set	/set	
WAC Angle Bracket		* set	/set	
PVC Pipe	Ø3/4" x 10'	1 pc	/pc(s)	
Leak Test existing copper tube	*	* set	/set(s)	
Dismantle existing unit	*	* unit	/unit	
Chipping works		* mtr	500.00 /mtr	
Other works and materials	*	* lot	₱ * /lot	

Estimated Charges ₱ 18,000.00

Location/s:	LIVINGROOM		Area:	44.00	sqm.	
ACU #:		Unit Model:	KSG-IWF-30WY8K1M32		Unit Capacity/Type:	3.0HP Wall Mounted Inverter

Estimated Pipe Length = 28 ft
Estimated Royal Cord Length = 33 ft

Initial Charge ₱ 8,500.00

10ft Copper tube
10ft Royal Cord
Outdoor bracket Wall/Floor

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	5/8"Ø x 1/4"Ø	18 ft	₱ 400.00 /ft	₱ 7,200.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	23 ft	100.00 /ft	2,300.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	* ft	60.00 /ft	
Circuit Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
Outdoor Unit Bracket Type	Fabricated floor	* set	62,500.00 /set	
Indoor Unit Bracket Type	*	* set	/set	
WAC Angle Bracket		* set	/set	
PVC Pipe	Ø3/4" x 10'	1 pc	/pc(s)	
Leak Test existing copper tube	*	* set	/set(s)	
Dismantle existing unit	*	* unit	/unit	
Chipping works		* mtr	500.00 /mtr	
Other works and materials	*	* lot	₱ * /lot	

Estimated Charges ₱ 19,000.00

Location/s:	LIVINGROOM 2ND		Area:	44.00	sqm.	
ACU #:		Unit Model:	KSG-IWF-30Wfy8K1M32		Unit Capacity/Type:	3.0HP Wall Mounted Inverter

Estimated Pipe Length	=	30	ft	
Estimated Royal Cord Length	=	35	ft	
Initial Charge				₱ 8,500.00
10ft Copper tube				
10ft Royal Cord				
Outdoor bracket Wall/Floor				
Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	5/8"Ø x 1/4"Ø	20 ft	₱ 400.00 /ft	₱ 8,000.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	25 ft	100.00 /ft	2,500.00
Royal Cord (Power Supply)	(#12) 3.5 sqmm. x 3c	* ft	60.00 /ft	
Circuit Breaker Weather Proof	30Amps / 1Ph	1 pc	1,000.00 /pc	1,000.00
Outdoor Unit Bracket Type	Fabricated floor	* set	62,500.00 /set	
Indoor Unit Bracket Type	*	* set	/set	
WAC Angle Bracket		* set	/set	
PVC Pipe	Ø3/4" x 10'	1 pc	/pc(s)	
Leak Test existing copper tube	*	* set	/set(s)	
Dismantle existing unit	*	* unit	/unit	
Chipping works		* mtr	500.00 /mtr	
Other works and materials	*	* lot	₱ * /lot	
Estimated Charges				₱ 20,000.00

Total Estimated Charges	₱ 224,800.00
--------------------------------	---------------------