



September 10, 2025

GUEVARRA'S METRO EAST
(INFRONT OF) ROBINSON'S METRO EAST, MARCOS HI-WAY, PASIG CITY
TEL#: 0919-0987598

Dear Ma'am/Sir,

Kolin Marketing Inc., is extremely honored for your endorsement of Kolin brand and we are please to offer you with a special price/s for the following items.

A. EQUIPMENT & INSTALLATION **OPTION 1**

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
8	UNIT/S	MODEL: KL-IF60-G6H1M32 KOLIN FLOOR MOUNTED AIRCONDITIONER 58,140 Kj/h (5.0TR) FULL DC INVERTER R32 SINGLE PHASE	165,995.00	112,156.20	PHP	897,249.60
2	UNIT/S	MODEL: KLG-IF40-5G1M32 KOLIN FLOOR MOUNTED AIRCONDITIONER 37,980 Kj/h (3.0TR) FULL DC INVERTER R-32 SINGLE PHASE	113,195.00	79,028.20	PHP	158,056.40
2	UNIT/S	MODEL: KSG-IWF-30WFF-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 29,500 Kj/h (3.0HP) FULL DC INVERTER W/ WIFI R-32	76,595.00	51,212.20	PHP	102,424.40
4	UNIT/S	MODEL: KSG-IWF-25WFF-8K1M32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 25,560 Kj/h (2.5HP) FULL DC INVERTER W/ WIFI R-32	68,995.00	45,436.20	PHP	181,744.80
TOTAL UNIT COST					PHP	1,339,475.20
ESTIMATED COST OF INSTALLATION (please see attached)					PHP	805,800.00
TOTAL ESTIMATED COST OF THE PROJECT					PHP	2,145,275.20

TERMS OF PAYMENT:

FULL PAYMENT OF UNIT AND DELIVERY CHARGE. IF CHECK, SUBJECT FOR 3 DAYS CLEARING.

WARRANTY:

FOR FLOOR MOUNTED (Inverter): ONE (1) YEAR FREE PARTS AND LABOR, FIVE (5) YEARS WARRANTY ON COMPRESSOR.

FOR SPLIT TYPE : ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB , TEN (10) YEARS WARRANTY ON COMPRESSOR.

NOTES: PRICES ARE SUBJECT TO CHANGE WITHOUT PRIOR NOTICE.

PRICES IS VAT INCLUSIVE.

**** Cost of Installation is Package with the Unit(s), this cost cannot avail separately (cost will be based on actual works).**

***** You may settle first payment for unit/s & delivery. Installation payment can be settled directly to installer after actual works.**

We thank you for giving opportunity to offer our product and services, hoping we receive your purchase order.

If you need assistance, don't hesitate to call the under signed at 0917-807-8607 or email at kmi_asst@kolinphil.com.ph

Very Truly Yours,

JANELLEN S. LIM
KMI-ASSISTANT

Noted by:

MART NATHANIEL R. FLORES
KMI-SUPERVISOR

Approved By:

MS. EDITHA M. FLORES
AVP - FINANCE

Conforme:

SIGNATURE OVER PRINTED NAME

KMI-QUOTE-09-25-0676
REG-24%/14K/7K

Kolin Marketing, Inc.

1854 Sta. Rita St., Guadalupe Nuevo, Makati City

Tel.: (632) 8852-6473

Fax: (632) 8852-2170 / (632) 8852-4792

www.kolinphil.com.ph / kolinphilippines

SEPTEMBER 09, 2025
 ROBINSON METROEAST
 Robinson Metro East, Marcos Hiway, Brgy Marikina Infanta Highway Pasig City
 0919-0987598

MODEL	Qty
KL-IF60-G6H1M32	8
KLG-IF40-5G1M32	2
KSG-IWF-30WFY8K1M32	2
KSG-IWF-25WFY8K1M32	4

GROUND FLOOR

Location	Area	318 sqm
----------	------	---------

ACU 1	7.0 HP Floor Standing Inverter	KL-IF60-G6H1M32	
	Estimated Pipe Length = 86 ft		
	Estimated Royal Cord Length = 93 ft		
	Initial Charge		₱ 14,000.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Indoor Bracket (Floor)

Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 3/8" x Ø 5/8"	76 ft	₱ 400.00/ft	₱ 30,400.00
Royal Cord (comm. wire)	2.mm2 x 4C	83 ft	₱ 100.00/ft	₱ 8,300.00
Royal Cord (ACCU-Breaker)	5.5mm x 3c	5 ft	₱ 70.00/ft	₱ 350.00
Circuit Breaker waterproof	60A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	12 pc/s	₱ 350.00/pc	₱ 4,200.00
Full thread	3/8" x 10'	2 pc/s	₱ 150.00/pc	₱ 300.00
Metal Clamp	3"	16 pc/s	₱ 120.00/pc	₱ 1,920.00
Outdoor bracket	Fabricated wall	1 pc/s	₱ 5,000.00/pc	₱ 5,000.00
PVC blue	3/4" x 10'	3 pc/s	₱ 150.00/pc	₱ 450.00
				₱ 51,920.00

Estimated Charges	₱ 65,920.00
-------------------	-------------

ACU 2	7.0 HP Floor Standing Inverter	KL-IF60-G6H1M32	
	Estimated Pipe Length = 50 ft		
	Estimated Royal Cord Length = 57 ft		
	Initial Charge		₱ 14,000.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Indoor Bracket (Floor)

Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 3/8" x Ø 5/8"	40 ft	₱ 400.00/ft	₱ 16,000.00
Royal Cord (comm. wire)	2.mm2 x 4C	47 ft	₱ 100.00/ft	₱ 4,700.00
Royal Cord (ACCU-Breaker)	5.5mm x 3c	7 ft	₱ 70.00/ft	₱ 490.00
Circuit Breaker waterproof	60A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	7 pc/s	₱ 350.00/pc	₱ 2,450.00
Full thread	3/8" x 10'	2 pc/s	₱ 150.00/pc	₱ 300.00
Metal Clamp	3"	11 pc/s	₱ 120.00/pc	₱ 1,320.00
Outdoor bracket	Fabricated wall	1 pc/s	₱ 5,000.00/pc	₱ 5,000.00
PVC blue	3/4" x 10'	3 pc/s	₱ 150.00/pc	₱ 450.00
				₱ 31,710.00

Estimated Charges	₱ 45,710.00
-------------------	-------------

ACU 3	7.0 HP Floor Standing Inverter	KL-IF60-G6H1M32
-------	--------------------------------	-----------------

Estimated Pipe Length = 73 ft

Estimated Royal Cord Length = 80 ft

Initial Charge

₱ 14,000.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Indoor Bracket (Floor)

Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 3/8" x Ø 5/8"	63 ft	₱ 400.00/ft	₱ 25,200.00
Royal Cord (comm. wire)	2.mm2 x 4C	70 ft	₱ 100.00/ft	₱ 7,000.00
Royal Cord (ACCU-Breaker)	5.5mm x 3c	7 ft	₱ 70.00/ft	₱ 490.00
Circuit Breaker waterproof	60A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	11 pc/s	₱ 350.00/pc	₱ 3,850.00
Full thread	3/8" x 10'	2 pc/s	₱ 150.00/pc	₱ 300.00
Metal Clamp	3"	15 pc/s	₱ 120.00/pc	₱ 1,800.00
Outdoor bracket	Fabricated wall	1 pc/s	₱ 5,000.00/pc	₱ 5,000.00
PVC blue	3/4" x 10'	3 pc/s	₱ 150.00/pc	₱ 450.00
				₱ 45,090.00

Estimated Charges

₱ 59,090.00

ACU 4 7.0 HP Floor Standing Inverter

KL-IF60-G6H1M32

Estimated Pipe Length = 96 ft

Estimated Royal Cord Length = 103 ft

Initial Charge

₱ 14,000.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Indoor Bracket (Floor)

Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 3/8" x Ø 5/8"	86 ft	₱ 400.00/ft	₱ 34,400.00
Royal Cord (comm. wire)	2.mm2 x 4C	93 ft	₱ 100.00/ft	₱ 9,300.00
Royal Cord (ACCU-Breaker)	5.5mm x 3c	7 ft	₱ 70.00/ft	₱ 490.00
Circuit Breaker waterproof	60A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	14 pc/s	₱ 350.00/pc	₱ 4,900.00
Full thread	3/8" x 10'	2 pc/s	₱ 150.00/pc	₱ 300.00
Metal Clamp	3"	18 pc/s	₱ 120.00/pc	₱ 2,160.00
Outdoor bracket	Fabricated wall	1 pc/s	₱ 5,000.00/pc	₱ 5,000.00
PVC blue	3/4" x 10'	3 pc/s	₱ 150.00/pc	₱ 450.00
				₱ 58,000.00

Estimated Charges

₱ 72,000.00

ACU 5 7.0 HP Floor Standing Inverter**KL-IF60-G6H1M32**

Estimated Pipe Length = 69 ft

Estimated Royal Cord Length = 76 ft

Initial Charge

₱ 14,000.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Indoor Bracket (Floor)

Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 3/8" x Ø 5/8"	59 ft	₱ 400.00/ft	₱ 23,600.00
Royal Cord (comm. wire)	2.mm2 x 4C	66 ft	₱ 100.00/ft	₱ 6,600.00
Royal Cord (ACCU-Breaker)	5.5mm x 3c	7 ft	₱ 70.00/ft	₱ 490.00
Circuit Breaker waterproof	60A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	10 pc/s	₱ 350.00/pc	₱ 3,500.00
Full thread	3/8" x 10'	2 pc/s	₱ 150.00/pc	₱ 300.00
Metal Clamp	3"	14 pc/s	₱ 120.00/pc	₱ 1,680.00
Outdoor bracket	Fabricated wall	1 pc/s	₱ 5,000.00/pc	₱ 5,000.00
PVC blue	3/4" x 10'	3 pc/s	₱ 150.00/pc	₱ 450.00
				₱ 42,620.00

Estimated Charges	₱ 56,620.00
--------------------------	--------------------

ACU 6 7.0 HP Floor Standing Inverter**KL-IF60-G6H1M32**

Estimated Pipe Length = 69 ft

Estimated Royal Cord Length = 76 ft

Initial Charge

₱ 14,000.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Indoor Bracket (Floor)

Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 3/8" x Ø 5/8"	59 ft	₱ 400.00/ft	₱ 23,600.00
Royal Cord (comm. wire)	2.mm2 x 4C	66 ft	₱ 100.00/ft	₱ 6,600.00
Royal Cord (ACCU-Breaker)	5.5mm x 3c	7 ft	₱ 70.00/ft	₱ 490.00
Circuit Breaker waterproof	60A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	10 pc/s	₱ 350.00/pc	₱ 3,500.00
Full thread	3/8" x 10'	2 pc/s	₱ 150.00/pc	₱ 300.00
Metal Clamp	3"	14 pc/s	₱ 120.00/pc	₱ 1,680.00
Outdoor bracket	Fabricated wall	1 pc/s	₱ 5,000.00/pc	₱ 5,000.00
PVC blue	3/4" x 10'	3 pc/s	₱ 150.00/pc	₱ 450.00
				₱ 42,620.00

Estimated Charges	₱ 56,620.00
--------------------------	--------------------

ACU 7 7.0 HP Floor Standing Inverter**KL-IF60-G6H1M32**

Estimated Pipe Length = 37 ft

Estimated Royal Cord Length = 44 ft

Initial Charge

₱ 14,000.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Indoor Bracket (Floor)

Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 3/8" x Ø 5/8"	27 ft	₱ 400.00/ft	₱ 10,800.00
Royal Cord (comm. wire)	2.mm2 x 4C	34 ft	₱ 100.00/ft	₱ 3,400.00
Royal Cord (ACCU-Breaker)	5.5mm x 3c	7 ft	₱ 70.00/ft	₱ 490.00
Circuit Breaker waterproof	60A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	5 pc/s	₱ 350.00/pc	₱ 1,750.00
Full thread	3/8" x 10'	2 pc/s	₱ 150.00/pc	₱ 300.00
Metal Clamp	3"	9 pc/s	₱ 120.00/pc	₱ 1,080.00
Outdoor bracket	Fabricated wall	1 pc/s	₱ 5,000.00/pc	₱ 5,000.00
PVC blue	3/4" x 10'	3 pc/s	₱ 150.00/pc	₱ 450.00
				₱ 24,270.00

Estimated Charges**₱ 38,270.00****ACU 8 7.0 HP Floor Standing Inverter****KL-IF60-G6H1M32**

Estimated Pipe Length = 53 ft

Estimated Royal Cord Length = 60 ft

Initial Charge

₱ 14,000.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Indoor Bracket (Floor)

Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 3/8" x Ø 5/8"	43 ft	₱ 400.00/ft	₱ 17,200.00
Royal Cord (comm. wire)	2.mm2 x 4C	50 ft	₱ 100.00/ft	₱ 5,000.00
Royal Cord (ACCU-Breaker)	5.5mm x 3c	7 ft	₱ 70.00/ft	₱ 490.00
Circuit Breaker waterproof	60A / 1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	7 pc/s	₱ 350.00/pc	₱ 2,450.00
Full thread	3/8" x 10'	2 pc/s	₱ 150.00/pc	₱ 300.00
Metal Clamp	3"	11 pc/s	₱ 120.00/pc	₱ 1,320.00
Outdoor bracket	Fabricated wall	1 pc/s	₱ 5,000.00/pc	₱ 5,000.00
PVC blue	3/4" x 10'	3 pc/s	₱ 150.00/pc	₱ 450.00
				₱ 33,210.00

Estimated Charges**₱ 47,210.00**

2ND FLOOR**DINING A**

Area 70 sqm

ACU 9 4.0 HP Floor Standing Inverter**KLG-IF40-5G1M32**

Estimated Pipe Length = 82 ft

Estimated Royal Cord Length = 89 ft

Initial Charge

₱ 11,000.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Indoor Bracket (Floor)

Consumables

Installation Materials

Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 3/8" x Ø 5/8"	72 ft ₱ 400.00/ft	₱ 28,800.00
Royal Cord (comm. wire)	2.mm2 x 4C	79 ft ₱ 100.00/ft	₱ 7,900.00
Royal Cord (ACCU-Breaker)	5.5mm x 3c	7 ft ₱ 70.00/ft	₱ 490.00
Circuit Breaker waterproof	40A / 1Ph	1 pc/s ₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	12 pc/s ₱ 350.00/pc	₱ 4,200.00
Full thread	3/8" x 10'	2 pc/s ₱ 150.00/pc	₱ 300.00
Metal Clamp	3"	16 pc/s ₱ 120.00/pc	₱ 1,920.00
Outdoor bracket	Fabricated wall	1 pc/s ₱ 5,000.00/pc	₱ 5,000.00
PVC blue	3/4" x 10'	3 pc/s ₱ 150.00/pc	₱ 450.00
			₱ 50,060.00

Estimated Charges

₱ 61,060.00

ACU 10 4.0 HP Floor Standing Inverter**KLG-IF40-5G1M32**

Estimated Pipe Length = 43 ft

Estimated Royal Cord Length = 50 ft

Initial Charge

₱ 11,000.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Indoor Bracket (Floor)

Consumables

Installation Materials

Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 3/8" x Ø 5/8"	33 ft ₱ 400.00/ft	₱ 13,200.00
Royal Cord (comm. wire)	2.mm2 x 4C	40 ft ₱ 100.00/ft	₱ 4,000.00
Royal Cord (ACCU-Breaker)	5.5mm x 3c	7 ft ₱ 70.00/ft	₱ 490.00
Circuit Breaker waterproof	40A / 1Ph	1 pc/s ₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	6 pc/s ₱ 350.00/pc	₱ 2,100.00
Full thread	3/8" x 10'	2 pc/s ₱ 150.00/pc	₱ 300.00
Metal Clamp	3"	10 pc/s ₱ 120.00/pc	₱ 1,200.00
Outdoor bracket	Fabricated wall	1 pc/s ₱ 5,000.00/pc	₱ 5,000.00
PVC blue	3/4" x 10'	3 pc/s ₱ 150.00/pc	₱ 450.00
			₱ 27,740.00

Estimated Charges

₱ 38,740.00

DINING B	Area	44 sqm
-----------------	------	--------

ACU 11 2.5 HP Wall Mounted Inverter *KSG-IWF-25Wfy8K1M32*

Estimated Pipe Length = 60 ft

Estimated Royal Cord Length = 65 ft

Initial Charge ₱ 8,500.00

Includes:

Labor
10ft Copper Tube
10ft Royal Cord
Outdoor Bracket (Wall)
Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 5/8"	50 ft	₱ 400.00/ft	₱ 20,000.00
Royal Cord (comm. wire)	2.mm2 x 4C	55 ft	₱ 100.00/ft	₱ 5,500.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	₱ 60.00/ft	₱ 300.00
Circuit Breaker waterproof	30A/1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	8 pc/s	₱ 350.00/pc	₱ 2,800.00
Full thread	3/8" x 10'	2 pc/s	₱ 150.00/pc	₱ 300.00
Metal Clamp	3"	12 pc/s	₱ 120.00/pc	₱ 1,440.00
PVC blue	3/4" x 10'	3 pc/s	₱ 150.00/pc	₱ 450.00
				₱ 31,790.00

Estimated Charges	₱ 40,290.00
--------------------------	--------------------

ACU 12 2.5 HP Wall Mounted Inverter *KSG-IWF-25Wfy8K1M32*

Estimated Pipe Length = 65 ft

Estimated Royal Cord Length = 70 ft

Initial Charge ₱ 8,500.00

Includes:

Labor
10ft Copper Tube
10ft Royal Cord
Outdoor Bracket (Wall)
Consumables

Installation Materials	Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 5/8"	55 ft	₱ 400.00/ft	₱ 22,000.00
Royal Cord (comm. wire)	2.mm2 x 4C	60 ft	₱ 100.00/ft	₱ 6,000.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft	₱ 60.00/ft	₱ 300.00
Circuit Breaker waterproof	30A/1Ph	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	8 pc/s	₱ 350.00/pc	₱ 2,800.00
Full thread	3/8" x 10'	2 pc/s	₱ 150.00/pc	₱ 300.00
Metal Clamp	3"	12 pc/s	₱ 120.00/pc	₱ 1,440.00
PVC blue	3/4" x 10'	3 pc/s	₱ 150.00/pc	₱ 450.00
				₱ 34,290.00

Estimated Charges	₱ 42,790.00
--------------------------	--------------------

DINING C	Area	47 sqm
-----------------	------	--------

ACU 13 3.0 HP Wall Mounted Inverter
KSG-IWF-30Wfy8K1M32

Estimated Pipe Length = 60 ft

Estimated Royal Cord Length = 65 ft

Initial Charge

₱ 8,500.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Outdoor Bracket (Wall)

Consumables

Installation Materials

Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 5/8"	50 ft ₱ 400.00/ft	₱ 20,000.00
Royal Cord (comm. wire)	2.mm2 x 4C	55 ft ₱ 100.00/ft	₱ 5,500.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft ₱ 60.00/ft	₱ 300.00
Circuit Breaker waterproof	30A/1Ph	1 pc/s ₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	8 pc/s ₱ 350.00/pc	₱ 2,800.00
Full thread	3/8" x 10'	2 pc/s ₱ 150.00/pc	₱ 300.00
Metal Clamp	3"	12 pc/s ₱ 120.00/pc	₱ 1,440.00
PVC blue	3/4" x 10'	3 pc/s ₱ 150.00/pc	₱ 450.00
			₱ 31,790.00

Estimated Charges

₱ 40,290.00

ACU 14 3.0 HP Wall Mounted Inverter
KSG-IWF-30Wfy8K1M32

Estimated Pipe Length = 76 ft

Estimated Royal Cord Length = 81 ft

Initial Charge

₱ 8,500.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Outdoor Bracket (Wall)

Consumables

Installation Materials

Description	Qty	Price per qty	Subtotal
Copper Tube	Ø 1/4" x Ø 5/8"	66 ft ₱ 400.00/ft	₱ 26,400.00
Royal Cord (comm. wire)	2.mm2 x 4C	71 ft ₱ 100.00/ft	₱ 7,100.00
Royal Cord (ACCU-Breaker)	3.5mm x 3c	5 ft ₱ 60.00/ft	₱ 300.00
Circuit Breaker waterproof	30A/1Ph	1 pc/s ₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	2 1/8" x 3/4" x 6'	10 pc/s ₱ 350.00/pc	₱ 3,500.00
Full thread	3/8" x 10'	2 pc/s ₱ 150.00/pc	₱ 300.00
Metal Clamp	3"	14 pc/s ₱ 120.00/pc	₱ 1,680.00
PVC blue	3/4" x 10'	3 pc/s ₱ 150.00/pc	₱ 450.00
			₱ 40,730.00

Estimated Charges

₱ 49,230.00

DINING D	Area	40 sqm
-----------------	------	--------

ACU 15 2.5 HP Wall Mounted Inverter
KSG-IWF-25Wfy8K1M32

Estimated Pipe Length = 66 ft

Estimated Royal Cord Length = 71 ft

Initial Charge

₱ 8,500.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Outdoor Bracket (Wall)

Consumables

Installation Materials

Description	Qty	Price per qty	Subtotal
Copper Tube	56 ft	₱ 400.00/ft	₱ 22,400.00
Royal Cord (comm. wire)	61 ft	₱ 100.00/ft	₱ 6,100.00
Royal Cord (ACCU-Breaker)	5 ft	₱ 60.00/ft	₱ 300.00
Circuit Breaker waterproof	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	10 pc/s	₱ 350.00/pc	₱ 3,500.00
Full thread	2 pc/s	₱ 150.00/pc	₱ 300.00
Metal Clamp	14 pc/s	₱ 120.00/pc	₱ 1,680.00
PVC blue	3 pc/s	₱ 150.00/pc	₱ 450.00
			₱ 35,730.00

Estimated Charges

₱ 44,230.00

ACU 16 2.5 HP Wall Mounted Inverter
KSG-IWF-25Wfy8K1M32

Estimated Pipe Length = 73 ft

Estimated Royal Cord Length = 78 ft

Initial Charge

₱ 8,500.00

Includes:

Labor

10ft Copper Tube

10ft Royal Cord

Outdoor Bracket (Wall)

Consumables

Installation Materials

Description	Qty	Price per qty	Subtotal
Copper Tube	63 ft	₱ 400.00/ft	₱ 25,200.00
Royal Cord (comm. wire)	68 ft	₱ 100.00/ft	₱ 6,800.00
Royal Cord (ACCU-Breaker)	5 ft	₱ 60.00/ft	₱ 300.00
Circuit Breaker waterproof	1 pc/s	₱ 1,000.00/pc	₱ 1,000.00
Rubber Insulation	10 pc/s	₱ 350.00/pc	₱ 3,500.00
Full thread	2 pc/s	₱ 150.00/pc	₱ 300.00
Metal Clamp	14 pc/s	₱ 120.00/pc	₱ 1,680.00
PVC blue	3 pc/s	₱ 150.00/pc	₱ 450.00
			₱ 39,230.00

Estimated Charges

₱ 47,730.00

Validity: This quotation is valid for a period of fifteen (15) days from the date thereof, subject to our confirmation thereafter.

Installation notes:

- 1 Location based in floor plan only.
- 2 AC drain line will be tapped to the nearest drain provision provided by the customer's contractor.
- 3 Need for marking and site visit before installation.
- 4 Coppertube expose inside the area.
- 5 Working days: Monday to Saturday, 8am- 5pm with parking. Need working permit.
- 6 Mechanical Plans, Permits, Electrical permits not included.
- 7 Deflectors, masonry, carpentry, chipping & plastering (finishing & restoration) are not included in the installation.
- 8 Air conditioning drain line and Electrical power supply (feeder line) **220v/ 60hz/ 1ph** , should be provided by customer's contractor.
- 9 Final charges will be based on actual installation.


Prepared by:


Jeffrey Dadios
Field Surveyor

Customer Conformer:

Signature Over Printed Name

Reviewed by:


Engr. Kenneth Zamora
Service Supervisor Shop and
Field Operation

