

RIVERDALE CONFECTIONERY INDUSTRY INC.
BLDG 3B, CCBI COMPD. AGUINALDO HI-WAY, ANABU 1, IMUS CAVITE
ATTN: MR. ELMER COBERO
TEL#: 0917-8993488 / 0947-4154791

Dear Ma'am/Sir,

Kolin Marketing Inc., is extremely honored for your endorsement of Kolin brand and we are please to offer you with a special price/s for the following items.

A. EQUIPMENT & INSTALLATION

* OPTION 1 *

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
1	UNIT/S	MODEL: KSM-IW20-WCT10M1M32 KOLIN WALL MOUNTED CERTUS SERIES AIRCONDITIONER 18,990 KJ/h (2.0HP) REGULAR INVERTER W/ WIFI R-32	41,995.00	27,916.20	PHP	27,916.20
2	UNIT/S	MODEL: KSM-IW25-WCT10M1M32 KOLIN WALL MOUNTED CERTUS AIRCONDITIONER 23,210 KJ/h (2.5HP) REGULAR INVERTER W/ WIFI R-32	49,995.00	33,996.20	PHP	67,992.40
TOTAL UNIT COST					PHP	95,908.60
ESTIMATED COST OF INSTALLATION (please see attached)					PHP	60,850.00
OTHERS: DELIVERY CHARGE					PHP	600.00
TOTAL ESTIMATED COST OF THE PROJECT					PHP	157,358.60

* OPTION 2 *

QTY	U/M	MODEL / DESCRIPTION	SRP	DISCOUNTED PRICE		AMOUNT
1	UNIT/S	MODEL: KSG-IWF-20WFF-8KIM32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 19,000 KJ/h (2.0HP) FULL DC INVERTER W/ WIFI R-32	59,595.00	38,292.20	PHP	38,292.20
2	UNIT/S	MODEL: KSG-IWF-25WFF-8KIM32 KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER 25,560 KJ/h (2.5HP) FULL DC INVERTER W/ WIFI R-32	68,995.00	45,436.20	PHP	90,872.40
TOTAL UNIT COST					PHP	129,164.60
ESTIMATED COST OF INSTALLATION (please see attached)					PHP	60,850.00
OTHERS: DELIVERY CHARGE					PHP	600.00
TOTAL ESTIMATED COST OF THE PROJECT					PHP	190,614.60

TERMS OF PAYMENT:

FULL PAYMENT OF UNIT AND DELIVERY CHARGE. IF CHECK, SUBJECT FOR 3 DAYS CLEARING.

WARRANTY:

FOR WINDOW TYPE: ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB, TEN (10) YEARS WARRANTY ON COMPRESSOR.

NOTES: PRICES ARE SUBJECT TO CHANGE WITHOUT PRIOR NOTICE.

PRICES IS VAT INCLUSIVE.

** Cost of Installation is Package with the Unit(s), this cost cannot avail separately (cost will be based on actual works).

*** You may settle first payment for unit/s & delivery. Installation payment can be settled directly to installer after actual works.

We thank you for giving opportunity to offer our product and services, hoping we receive your purchase order.

If you need assistance, don't hesitate to call the under signed at 0917-807-8607 or email at kmi_asst@kolinphil.com.ph

Very Truly Yours,

JANELLEN S. LIM
KMI-ASSISTANT

Noted by:

MARY NATHANIEL R. FLORES
KMI-SUPERVISOR

Approved By:

MS. EDITHA M. FLORES
AVP - FINANCE

KMI-QUOTE-09-25-0654
REG-24%/4K/7K

Conforme:

SIGNATURE OVER PRINTED NAME

Kolin Marketing, Inc.

1854 Sta. Rita St., Guadalupe Nuevo, Makati City

Tel.: (632) 8852-6473

Fax: (632) 8852-2170 / (632) 8852-4792

www.kolinphil.com.ph / kolinphilippines





ON-COOL

AIRCONDITIONING SERVICES

keep everything on and cool

Customer Name:	RIVERDALE CONFECTIONERY INDUSTRY INC.	Date:	AUGUST 29,2025
Customer Address:	BLDG.3B CBI COMPOUND KM.23 AGUINALDO HIGHWAY BRGY.ANABU 1-D IMUS CAVITE		

Qty	Unit Model	Unit Capacity/Type
1	KSG-IWF-20WFF8K1M32	2.0HP Wall Mounted Inverter
1	KSG-IWF-25WFF8K1M32	2.5HP Wall Mounted Inverter
1	KSG-IWF-25WFF8K1M32	2.5HP Wall Mounted Inverter

Location/s:	QC OFFICE	Area:	13.43	sqm.
-------------	-----------	-------	-------	------

ACU #:	1	Unit Model:	KSG-IWF-20WFF8K1M32	Unit Capacity/Type:	2.0HP Wall Mounted Inverter
--------	---	-------------	---------------------	---------------------	-----------------------------

Estimated Pipe Length = 10 ft

Estimated Royal Cord Length = 15 ft

Initial Charge ₱ 8,500.00

10ft Copper tube
10ft Royal Cord
Outdoor bracket Wall/Floor
Consumables
Testing and Commissioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Royal Cord (Comm wire)	2.0 sq.mm x 4c	5 ft	100.00 /ft	500.00
Dismantle existing unit	2.0HP Wall Mounted Reg	1 unit	2,500.00 /unit	2,500.00

Estimated Charges ₱ 11,500.00

Location/s:	DATA CODING AREA	Area:	28.80	sqm.
-------------	------------------	-------	-------	------

ACU #:		Unit Model:	KSM-IW25-WCT10M1M32	Unit Capacity/Type:	2.5HP Wall Mounted Inverter
--------	--	-------------	---------------------	---------------------	-----------------------------

Estimated Pipe Length = 10 ft

Estimated Royal Cord Length = 15 ft

Initial Charge ₱ 8,500.00

10ft Copper tube
10ft Royal Cord
Outdoor bracket Wall/Floor
Consumables
Testing and Commissioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Royal Cord (Comm wire)	2.0 sq.mm x 4c	5 ft	100.00 /ft	500.00
Dismantle existing unit	2.0HP Wall Mounted Inv	1 unit	2,500.00 /unit	2,500.00

Estimated Charges ₱ 11,500.00

Location/s:	ENGINEERING DEP'T.	Area:	13.43	sqm.
-------------	--------------------	-------	-------	------

ACU #:	1	Unit Model:	KSG-IWF-25Wfy8K1M32	Unit Capacity/Type:	2.5HP Wall Mounted Inverter
--------	---	-------------	---------------------	---------------------	-----------------------------

Estimated Pipe Length = 60 ft

Estimated Royal Cord Length = 65 ft

Initial Charge ₱ 8,500.00

10ft Copper tube

10ft Royal Cord

Outdoor bracket Wall/Floor

Consumables

Testing and Commissioning

Installation Materials	Specification	Qty	Price per qty	Subtotal
Insulated Copper tube	5/8"Ø x 1/4"Ø	50 ft	₱ 400.00 /ft	₱ 20,000.00
Royal Cord (Comm wire)	2.0 sq.mm x 4c	55 ft	100.00 /ft	5,500.00
Other works and materials	3/4 Additional thickness(Rubber Insulation)	10 lot	₱ 350.00 /lot	3,500.00
	Excess Drain Line	7 ft	₱ 50.00 /ft	350.00

Estimated Charges ₱ 37,850.00

Total Estimated Charges ₱ **60,850.00**

NOTES: Prices are subject to change without prior notice.

Copper Tubing / Piping Length is subject to its actual site measurement.

SCOPE OF WORK	PROJECT EXCLUSIONS
A. Supply of Labor for the Installation	1.) Circuit Breaker
B. Materials Lists	2.) Electrical Feeder Line (Power Supply)
✓ Copper Tube Piping ✓ Royal Cord Communication	3.) Masonry Works including Chipping and Embedding, Carpentry, Painting and Restoration works.
✓ Rubber Insulation ✓ Drain Line Pipe	4.) Mechanical Floor Plan, Building Admin Permit, Working Permit, Government Permit
✓ Polyethylene Tape ✓ Standard Bracket	5.) Dismantling of Old Units
C. Consumables	6.) Special Bracket
✓ Torx Screw ✓ Bolts & Nuts ✓ Nitrogen	
✓ Expansion Bolts ✓ Electrical Tape ✓ Freon (if needed)	
D. Leak Testing and Vacuuming	
E. Start-Up and Commissioning	

GENERAL TERMS & CONDITIONS

Warranty Standard manufacturer's warranty upon purchase on the AC unit. Mode of Payment Cash and/or Bank Transfer

One (1) year warranty for the AC Installation Labor

BDO / 012320121907

Terms of Payment 70% downpayment and full payment upon project completion

ON-COOL Airconditioning Services

PREPARED BY


RAMIL U. MACARIO
 Signature over Printed Name

CLIENT CONFORM

Should the foregoing meet your kind approval, once signed this will serve as Service Contract Agreement or Purchase Order.

Signature over Printed Name /

AUX
AIR CONDITIONER

kol in

AMERICAN HOME
appliances

TOSOT

OX
AIR CONDITIONER

DAIKIN

koppel

GREE