



September 26, 2025

THE GREENHOUSE  
TOURISM RD., BRGY. CATANGNAN, GENERAL LUNA, SURIGAO DEL NORTE

Dear Ma'am/Sir,

Kolin Marketing Inc., is extremely honored for your endorsement of Kolin brand and we are please to offer you with a special price/s for the following items.

A. EQUIPMENT & INSTALLATION - OPTION 2

| QTY                                                  | U/M    | MODEL / DESCRIPTION                                                                                                               | SRP        | DISCOUNTED PRICE |     | AMOUNT       |
|------------------------------------------------------|--------|-----------------------------------------------------------------------------------------------------------------------------------|------------|------------------|-----|--------------|
| 4                                                    | UNIT/S | MODEL: KSG-IWF-10WFF-8K1M32<br>KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER<br>11,484 Kj/h (1.0HP) FULL DC INVERTER W/ WIFI R-32 | 42,595.00  | 24,520.30        | PHP | 98,081.20    |
| 1                                                    | UNIT/S | MODEL: KSG-IWF-15WFF-8K1M32<br>KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER<br>12,960 Kj/h (1.5HP) FULL DC INVERTER W/ WIFI R-32 | 46,595.00  | 27,480.30        | PHP | 27,480.30    |
| 25                                                   | UNIT/S | MODEL: KSG-IWF-20WFF-8K1M32<br>KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER<br>19,000 Kj/h (2.0HP) FULL DC INVERTER W/ WIFI R-32 | 59,595.00  | 37,100.30        | PHP | 927,507.50   |
| 1                                                    | UNIT/S | MODEL: KSG-IWF-25WFF-8K1M32<br>KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER<br>25,560 Kj/h (2.5HP) FULL DC INVERTER W/ WIFI R-32 | 68,995.00  | 44,056.30        | PHP | 44,056.30    |
| 13                                                   | UNIT/S | MODEL: KSG-IWF-30WFF-8K1M32<br>KOLIN WALL MOUNTED PRIMUS GOLD AIRCONDITIONER<br>29,500 Kj/h (3.0HP) FULL DC INVERTER W/ WIFI R-32 | 76,595.00  | 49,680.30        | PHP | 645,843.90   |
| 1                                                    | UNIT/S | MODEL: KLG-IF40-5G1M32<br>KOLIN FLOOR MOUNTED AIRCONDITIONER<br>37,980 Kj/h (3.0TR) FULL DC INVERTER R-32 SINGLE PHASE            | 113,195.00 | 76,764.30        | PHP | 76,764.30    |
| 2                                                    | UNIT/S | MODEL: KL-IF60-G6H1M32<br>KOLIN FLOOR MOUNTED AIRCONDITIONER<br>58,140 Kj/h (5.0TR) FULL DC INVERTER R32 SINGLE PHASE             | 165,995.00 | 108,836.30       | PHP | 217,672.60   |
| TOTAL UNIT COST                                      |        |                                                                                                                                   |            |                  | PHP | 2,037,406.10 |
| ESTIMATED COST OF INSTALLATION (please see attached) |        |                                                                                                                                   |            |                  | PHP | 1,471,770.00 |
| TOTAL ESTIMATED COST OF THE PROJECT                  |        |                                                                                                                                   |            |                  | PHP | 3,509,176.10 |

TERMS OF PAYMENT:

FULL PAYMENT OF UNIT AND DELIVERY CHARGE. IF CHECK, SUBJECT FOR 3 DAYS CLEARING.

WARRANTY:

FOR SPLIT TYPE : ONE (1) YEAR FREE PARTS AND LABOR, THREE YEARS (3) MAIN PCB , TEN (10) YEARS WARRANTY ON COMPRESSOR.  
FOR FLOOR MOUNTED (Inverter): ONE (1) YEAR FREE PARTS AND LABOR, FIVE (5) YEARS WARRANTY ON COMPRESSOR.

NOTES: \*\*\* Need to sign waiver agreement due to under capacity of unit choice (based on provided floor plan).

PRICES ARE SUBJECT TO CHANGE WITHOUT PRIOR NOTICE.

PRICES IS VAT INCLUSIVE.

We thank you for giving opportunity to offer our product and services, hoping we receive your purchase order.

If you need assistance, don't hesitate to call the under signed at 0917-807-8607 or email at kmi\_asst@kolinphil.com.ph

\*\* This quotation is based on provided floor plan only. Please carefully read installation notes on the attachment for scope of works.

\*\* Cost of Installation is Package with the Unit(s), this cost cannot avail separately (cost will be based on actual works).

Very Truly Yours,

JANELLEN S. LIM  
KMI-ASSISTANT

Noted by:  
MART NATHANIEL R. FLORES  
KMI-SUPERVISOR

Approved By:  
MS. EDITHA M. FLORES  
AVP - FINANCE

Conforme: \_\_\_\_\_  
SIGNATURE OVER PRINTED NAME

KMI-QUOTE-09-25-0703-rev3  
TCS-26%/7K/14K

Kolin Marketing, Inc.  
1854 Sta. Rita St., Guadalupe Nuevo, Makati City  
Tel.: (632) 8852-6473  
Fax: (632) 8852-2170 / (632) 8852-4792  
www.kolinphil.com.ph / kolinphilippines



|                   |                                                              |       |                    |
|-------------------|--------------------------------------------------------------|-------|--------------------|
| Customer Name:    | The Greenhouse                                               | Date: | September 17, 2025 |
| Customer Address: | Tourism rd. Brgy. Catangnan, General Luna, Surigao Del Norte |       |                    |

| Qty | Unit Model          | Unit Capacity/Type            |
|-----|---------------------|-------------------------------|
| 4   | KSG-IWF-10Wfy8K1M32 | 1.0HP Wall Mounted Inverter   |
| 1   | KSG-IWF-15Wfy8K1M32 | 1.5HP Wall Mounted Inverter   |
| 25  | KSG-IWF-20Wfy8K1M32 | 2.0HP Wall Mounted Inverter   |
| 1   | KSG-IWF-25Wfy8K1M32 | 2.5HP Wall Mounted Inverter   |
| 13  | KSG-IWF-30Wfy8K1M32 | 3.0HP Wall Mounted Inverter   |
| 1   | KLg-IF40-5G1M32     | 4.0HP Floor Standing Inverter |
| 2   | KL-IF60-G6H1M32     | 6.0HP Floor Standing Inverter |

GROUND FLOOR

|             |               |             |                     |                     |                             |
|-------------|---------------|-------------|---------------------|---------------------|-----------------------------|
| Location/s: | Foot Spa Area |             | Area:               | 20.00 sqm.          |                             |
| ACU #:      | 01            | Unit Model: | KSG-IWF-25WFY8K1M32 | Unit Capacity/Type: | 2.5HP Wall Mounted Inverter |

| <div> <div>Estimated Pipe Length = 65 ft</div> <div>Estimated Royal Cord Length = 70 ft</div> <div> <div>Initial Charge</div> <div> <div>10ft Copper tube</div> <div>10ft Royal Cord</div> <div>Outdoor bracket Wall/Floor</div> <div>Consumables</div> <div>Testing and Commisioning</div> </div> <div> <div>₱ 8,500.00</div> </div> </div> </div> |                       |       |               |             |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------|-------|---------------|-------------|
| Installation Materials                                                                                                                                                                                                                                                                                                                              | Specification         | Qty   | Price per qty | Subtotal    |
| Insulated Copper tube                                                                                                                                                                                                                                                                                                                               | 5/8"Ø x 1/4"Ø         | 55 ft | ₱ 400.00 /ft  | ₱ 22,000.00 |
| Royal Cord (Comm wire)                                                                                                                                                                                                                                                                                                                              | 2.0 sq.mm x 4c        | 60 ft | 100.00 /ft    | 6,000.00    |
| Royal Cord (Power Supply)                                                                                                                                                                                                                                                                                                                           | (#12) 3.5 sqmm. x 3c  | 5 ft  | 60.00 /ft     | 300.00      |
| Circuir Breaker Weather Proof                                                                                                                                                                                                                                                                                                                       | 30Amps / 1Ph          | 1 pc  | 1,000.00 /pc  | 1,000.00    |
| Pipe Hanger Assembly                                                                                                                                                                                                                                                                                                                                | Clamp and Full thread | 8 pc  | 420.00 /pc    | 3,360.00    |
| Rubber Insulation                                                                                                                                                                                                                                                                                                                                   | 2½" x 3/4" x 6'       | 7 pc  | ₱ 350.00 /pc  | ₱ 2,450.00  |
| Estimated Charges                                                                                                                                                                                                                                                                                                                                   |                       |       |               | ₱ 43,610.00 |

| <b>Location/s:</b>                                                                                                                                                                                                       |    | Massage Room1         |                     | <b>Area:</b>               | 10.00 sqm.                  |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|-----------------------|---------------------|----------------------------|-----------------------------|
| <b>ACU #:</b>                                                                                                                                                                                                            | 02 | <b>Unit Model:</b>    | KSG-IWF-10WFY8K1M32 | <b>Unit Capacity/Type:</b> | 1.0HP Wall Mounted Inverter |
| Estimated Pipe Length = 48 ft<br>Estimated Royal Cord Length = 53 ft<br><b>Initial Charge</b> ₱ 7,500.00<br>10ft Copper tube<br>10ft Royal Cord<br>Outdoor bracket Wall/Floor<br>Consumables<br>Testing and Commisioning |    |                       |                     |                            |                             |
| Installation Materials                                                                                                                                                                                                   |    | Specification         | Qty                 | Price per qty              | Subtotal                    |
| Insulated Copper tube                                                                                                                                                                                                    |    | 3/8"Ø x 1/4"Ø         | 38 ft               | ₱ 350.00 /ft               | ₱ 13,300.00                 |
| Royal Cord (Comm wire)                                                                                                                                                                                                   |    | 2.0 sq.mm x 4c        | 43 ft               | 100.00 /ft                 | 4,300.00                    |
| Royal Cord (Power Supply)                                                                                                                                                                                                |    | (#12) 3.5 sqmm. x 3c  | 5 ft                | 60.00 /ft                  | 300.00                      |
| Circuir Breaker Weather Proof                                                                                                                                                                                            |    | 20Amps / 1Ph          | 1 pc                | 1,000.00 /pc               | 1,000.00                    |
| Pipe Hanger Assembly                                                                                                                                                                                                     |    | Clamp and Full thread | 3 pc                | 420.00 /pc                 | 1,260.00                    |
| Rubber Insulation                                                                                                                                                                                                        |    | 2½" x 3/4" x 6'       | 3 pc                | ₱ 350.00 /pc               | ₱ 1,050.00                  |
| Estimated Charges                                                                                                                                                                                                        |    |                       |                     |                            | ₱ 28,710.00                 |

| <b>Location/s:</b>                                                                                                                                                                                                       |    | Massage Room2         |                     | <b>Area:</b>               | 10.00 sqm.                  |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|-----------------------|---------------------|----------------------------|-----------------------------|
| <b>ACU #:</b>                                                                                                                                                                                                            | 03 | <b>Unit Model:</b>    | KSG-IWF-10WFY8K1M32 | <b>Unit Capacity/Type:</b> | 1.0HP Wall Mounted Inverter |
| Estimated Pipe Length = 53 ft<br>Estimated Royal Cord Length = 58 ft<br><b>Initial Charge</b> ₱ 7,500.00<br>10ft Copper tube<br>10ft Royal Cord<br>Outdoor bracket Wall/Floor<br>Consumables<br>Testing and Commisioning |    |                       |                     |                            |                             |
| Installation Materials                                                                                                                                                                                                   |    | Specification         | Qty                 | Price per qty              | Subtotal                    |
| Insulated Copper tube                                                                                                                                                                                                    |    | 3/8"Ø x 1/4"Ø         | 43 ft               | ₱ 350.00 /ft               | ₱ 15,050.00                 |
| Royal Cord (Comm wire)                                                                                                                                                                                                   |    | 2.0 sq.mm x 4c        | 48 ft               | 100.00 /ft                 | 4,800.00                    |
| Royal Cord (Power Supply)                                                                                                                                                                                                |    | (#12) 3.5 sqmm. x 3c  | 5 ft                | 60.00 /ft                  | 300.00                      |
| Circuir Breaker Weather Proof                                                                                                                                                                                            |    | 20Amps / 1Ph          | 1 pc                | 1,000.00 /pc               | 1,000.00                    |
| Pipe Hanger Assembly                                                                                                                                                                                                     |    | Clamp and Full thread | 4 pc                | 420.00 /pc                 | 1,680.00                    |
| Rubber Insulation                                                                                                                                                                                                        |    | 2½" x 3/4" x 6'       | 3 pc                | ₱ 350.00 /pc               | ₱ 1,050.00                  |
| Estimated Charges                                                                                                                                                                                                        |    |                       |                     |                            | ₱ 31,380.00                 |

|                    |                 |              |                   |
|--------------------|-----------------|--------------|-------------------|
| <b>Location/s:</b> | <b>Wine Bar</b> | <b>Area:</b> | <b>54.00 sqm.</b> |
|--------------------|-----------------|--------------|-------------------|

|               |           |                    |                           |                            |                                    |
|---------------|-----------|--------------------|---------------------------|----------------------------|------------------------------------|
| <b>ACU #:</b> | <b>04</b> | <b>Unit Model:</b> | <b>KSG-IWF-30WY8K1M32</b> | <b>Unit Capacity/Type:</b> | <b>3.0HP Wall Mounted Inverter</b> |
|---------------|-----------|--------------------|---------------------------|----------------------------|------------------------------------|

Estimated Pipe Length = 59 ft

Estimated Royal Cord Length = 64 ft

**Initial Charge** ₱ 8,500.00

10ft Copper tube  
10ft Royal Cord  
Outdoor bracket Wall/Floor  
Consumables  
Testing and Commissioning

| Installation Materials        | Specification         | Qty   | Price per qty | Subtotal    |
|-------------------------------|-----------------------|-------|---------------|-------------|
| Insulated Copper tube         | 5/8"Ø x 1/4"Ø         | 49 ft | ₱ 400.00 /ft  | ₱ 19,600.00 |
| Royal Cord (Comm wire)        | 2.0 sq.mm x 4c        | 54 ft | 100.00 /ft    | 5,400.00    |
| Royal Cord (Power Supply)     | (#12) 3.5 sqmm. x 3c  | 5 ft  | 60.00 /ft     | 300.00      |
| Circuit Breaker Weather Proof | 30Amps / 1Ph          | 1 pc  | 1,000.00 /pc  | 1,000.00    |
| Pipe Hanger Assembly          | Clamp and Full thread | 4 pc  | 420.00 /pc    | 1,680.00    |
| Rubber Insulation             | 2½" x 3/4" x 6'       | 3 pc  | ₱ 350.00 /pc  | ₱ 1,050.00  |

Estimated Charges ₱ 37,530.00

|                    |                            |              |                   |
|--------------------|----------------------------|--------------|-------------------|
| <b>Location/s:</b> | <b>All Day Dining Area</b> | <b>Area:</b> | <b>94.00 sqm.</b> |
|--------------------|----------------------------|--------------|-------------------|

|               |           |                    |                        |                            |                                      |
|---------------|-----------|--------------------|------------------------|----------------------------|--------------------------------------|
| <b>ACU #:</b> | <b>05</b> | <b>Unit Model:</b> | <b>KL-IF60-G6H1M32</b> | <b>Unit Capacity/Type:</b> | <b>6.0HP Floor Standing Inverter</b> |
|---------------|-----------|--------------------|------------------------|----------------------------|--------------------------------------|

Estimated Pipe Length = 96 ft

Estimated Royal Cord Length = 101 ft

**Initial Charge** ₱ 14,000.00

10ft Copper tube  
10ft Royal Cord  
Indoor bracket (floor)  
Consumables  
Testing and Commissioning

| Installation Materials        | Specification         | Qty   | Price per qty | Subtotal    |
|-------------------------------|-----------------------|-------|---------------|-------------|
| Insulated Copper tube         | 5/8"Ø x 3/8"Ø         | 86 ft | ₱ 400.00 /ft  | ₱ 34,400.00 |
| Royal Cord (Comm wire)        | 2.0 sq.mm x 4c        | 91 ft | 100.00 /ft    | 9,100.00    |
| Royal Cord (Power Supply)     | (#10) 5.5 sqmm. x 3c  | 5 ft  | 70.00 /ft     | 350.00      |
| Circuit Breaker Weather Proof | 60Amps / 1Ph          | 1 pc  | 1,000.00 /pc  | 1,000.00    |
| Outdoor Unit Bracket Type     | Fabricated wall       | 1 set | 5,000.00 /set | 5,000.00    |
| Pipe Hanger Assembly          | Clamp and Full thread | 13 pc | 420.00 /pc    | 5,460.00    |
| Rubber Insulation             | 2½" x 3/4" x 6'       | 10 pc | ₱ 350.00 /pc  | ₱ 3,500.00  |

Estimated Charges ₱ 72,810.00

|        |    |             |                 |                     |                               |
|--------|----|-------------|-----------------|---------------------|-------------------------------|
| ACU #: | 06 | Unit Model: | KLK-IF40-5G1M32 | Unit Capacity/Type: | 4.0HP Floor Standing Inverter |
|--------|----|-------------|-----------------|---------------------|-------------------------------|

Estimated Pipe Length = 73 ft

Estimated Royal Cord Length = 78 ft

**Initial Charge**

₱ 11,000.00

10ft Copper tube  
10ft Royal Cord  
Indoor bracket (floor)  
Consumables  
Testing and Commisioning

| Installation Materials        | Specification         | Qty   | Price per qty | Subtotal    |
|-------------------------------|-----------------------|-------|---------------|-------------|
| Insulated Copper tube         | 5/8"Ø x 3/8"Ø         | 63 ft | ₱ 400.00 /ft  | ₱ 25,200.00 |
| Royal Cord (Comm wire)        | 2.0 sq.mm x 4c        | 68 ft | 100.00 /ft    | 6,800.00    |
| Royal Cord (Power Supply)     | (#10) 5.5 sqmm. x 3c  | 5 ft  | 70.00 /ft     | 350.00      |
| Circuir Breaker Weather Proof | 40Amps / 1Ph          | 1 pc  | 1,000.00 /pc  | 1,000.00    |
| Outdoor Unit Bracket Type     | Fabricated wall       | 1 set | 5,000.00 /set | 5,000.00    |
| Pipe Hanger Assembly          | Clamp and Full thread | 7 pc  | 420.00 /pc    | 2,940.00    |
| Rubber Insulation             | 2½" x 3/4" x 6'       | 6 pc  | ₱ 350.00 /pc  | ₱ 2,100.00  |

Estimated Charges ₱ 54,390.00

|        |    |             |                 |                     |                               |
|--------|----|-------------|-----------------|---------------------|-------------------------------|
| ACU #: | 07 | Unit Model: | KL-IF60-G6H1M32 | Unit Capacity/Type: | 6.0HP Floor Standing Inverter |
|--------|----|-------------|-----------------|---------------------|-------------------------------|

Estimated Pipe Length = 65 ft

Estimated Royal Cord Length = 70 ft

**Initial Charge**

₱ 14,000.00

10ft Copper tube  
10ft Royal Cord  
Indoor bracket (floor)  
Consumables  
Testing and Commisioning

| Installation Materials        | Specification         | Qty   | Price per qty | Subtotal    |
|-------------------------------|-----------------------|-------|---------------|-------------|
| Insulated Copper tube         | 5/8"Ø x 3/8"Ø         | 55 ft | ₱ 400.00 /ft  | ₱ 22,000.00 |
| Royal Cord (Comm wire)        | 2.0 sq.mm x 4c        | 60 ft | 100.00 /ft    | 6,000.00    |
| Royal Cord (Power Supply)     | (#10) 5.5 sqmm. x 3c  | 5 ft  | 70.00 /ft     | 350.00      |
| Circuir Breaker Weather Proof | 60Amps / 1Ph          | 1 pc  | 1,000.00 /pc  | 1,000.00    |
| Outdoor Unit Bracket Type     | Fabricated wall       | 1 set | 5,000.00 /set | 5,000.00    |
| Pipe Hanger Assembly          | Clamp and Full thread | 6 pc  | 420.00 /pc    | 2,520.00    |
| Rubber Insulation             | 2½" x 3/4" x 6'       | 5 pc  | ₱ 350.00 /pc  | ₱ 1,750.00  |

Estimated Charges ₱ 52,620.00

| Location/s:                                                                                                                                                                                                                                                                          |    | Kitchen               |                     | Area:         | 60.00 sqm.                                      |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|-----------------------|---------------------|---------------|-------------------------------------------------|
| ACU #:                                                                                                                                                                                                                                                                               | 08 | Unit Model:           | KSG-IWF-30Wfy8K1M32 |               | Unit Capacity/Type: 3.0HP Wall Mounted Inverter |
| <div>Estimated Pipe Length = 56 ft</div> <div>Estimated Royal Cord Length = 61 ft</div> <div>Initial Charge ₱ 8,500.00</div> <div>10ft Copper tube</div> <div>10ft Royal Cord</div> <div>Outdoor bracket Wall/Floor</div> <div>Consumables</div> <div>Testing and Commisioning</div> |    |                       |                     |               |                                                 |
| Installation Materials                                                                                                                                                                                                                                                               |    | Specification         | Qty                 | Price per qty | Subtotal                                        |
| Insulated Copper tube                                                                                                                                                                                                                                                                |    | 5/8"Ø x 1/4"Ø         | 46 ft               | ₱ 400.00 /ft  | ₱ 18,400.00                                     |
| Royal Cord (Comm wire)                                                                                                                                                                                                                                                               |    | 2.0 sq.mm x 4c        | 51 ft               | 100.00 /ft    | 5,100.00                                        |
| Royal Cord (Power Supply)                                                                                                                                                                                                                                                            |    | (#12) 3.5 sqmm. x 3c  | 1 ft                | 60.00 /ft     | 60.00                                           |
| Circuir Breaker Weather Proof                                                                                                                                                                                                                                                        |    | 30Amps / 1Ph          | 1 pc                | 1,000.00 /pc  | 1,000.00                                        |
| Pipe Hanger Assembly                                                                                                                                                                                                                                                                 |    | Clamp and Full thread | 4 pc                | 420.00 /pc    | 1,680.00                                        |
| Rubber Insulation                                                                                                                                                                                                                                                                    |    | 2½" x 3/4" x 6'       | 3 pc                | ₱ 350.00 /pc  | ₱ 1,050.00                                      |
| Estimated Charges                                                                                                                                                                                                                                                                    |    |                       |                     |               | ₱ 35,790.00                                     |

|                                     |    |                       |                     |                     |                             |
|-------------------------------------|----|-----------------------|---------------------|---------------------|-----------------------------|
| ACU #:                              | 09 | Unit Model:           | KSG-IWF-30Wfy8K1M32 | Unit Capacity/Type: | 3.0HP Wall Mounted Inverter |
| Estimated Pipe Length = 46 ft       |    |                       |                     |                     |                             |
| Estimated Royal Cord Length = 51 ft |    |                       |                     |                     |                             |
| Initial Charge                      |    |                       |                     |                     | ₱ 8,500.00                  |
| 10ft Copper tube                    |    |                       |                     |                     |                             |
| 10ft Royal Cord                     |    |                       |                     |                     |                             |
| Outdoor bracket Wall/Floor          |    |                       |                     |                     |                             |
| Consumables                         |    |                       |                     |                     |                             |
| Testing and Commisioning            |    |                       |                     |                     |                             |
| Installation Materials              |    | Specification         | Qty                 | Price per qty       | Subtotal                    |
| Insulated Copper tube               |    | 5/8"Ø x 1/4"Ø         | 36 ft               | ₱ 400.00 /ft        | ₱ 14,400.00                 |
| Royal Cord (Comm wire)              |    | 2.0 sq.mm x 4c        | 41 ft               | 100.00 /ft          | 4,100.00                    |
| Royal Cord (Power Supply)           |    | (#12) 3.5 sqmm. x 3c  | 5 ft                | 60.00 /ft           | 300.00                      |
| Circuir Breaker Weather Proof       |    | 30Amps / 1Ph          | 1 pc                | 1,000.00 /pc        | 1,000.00                    |
| Pipe Hanger Assembly                |    | Clamp and Full thread | 4 pc                | 420.00 /pc          | 1,680.00                    |
| Rubber Insulation                   |    | 2½" x 3/4" x 6'       | 4 pc                | ₱ 350.00 /pc        | ₱ 1,400.00                  |
| Estimated Charges                   |    |                       |                     |                     | ₱ 31,380.00                 |

| <b>Location/s:</b>                                                                                                                                                                                                       | Clinic/Lactation Room |                    | <b>Area:</b>        | 7.00 sqm.                                              |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------|--------------------|---------------------|--------------------------------------------------------|
| <b>ACU #:</b>                                                                                                                                                                                                            | 10                    | <b>Unit Model:</b> | KSG-IWF-10WFY8K1M32 | <b>Unit Capacity/Type:</b> 1.0HP Wall Mounted Inverter |
| Estimated Pipe Length = 40 ft<br>Estimated Royal Cord Length = 45 ft<br><b>Initial Charge</b> ₱ 7,500.00<br>10ft Copper tube<br>10ft Royal Cord<br>Outdoor bracket Wall/Floor<br>Consumables<br>Testing and Commisioning |                       |                    |                     |                                                        |
| Installation Materials                                                                                                                                                                                                   | Specification         | Qty                | Price per qty       | Subtotal                                               |
| Insulated Copper tube                                                                                                                                                                                                    | 3/8"Ø x 1/4"Ø         | 30 ft              | ₱ 350.00 /ft        | ₱ 10,500.00                                            |
| Royal Cord (Comm wire)                                                                                                                                                                                                   | 2.0 sq.mm x 4c        | 35 ft              | 100.00 /ft          | 3,500.00                                               |
| Royal Cord (Power Supply)                                                                                                                                                                                                | (#12) 3.5 sqmm. x 3c  | 5 ft               | 60.00 /ft           | 300.00                                                 |
| Circuir Breaker Weather Proof                                                                                                                                                                                            | 20Amps / 1Ph          | 1 pc               | 1,000.00 /pc        | 1,000.00                                               |
| Pipe Hanger Assembly                                                                                                                                                                                                     | Clamp and Full thread | 2 pc               | 420.00 /pc          | 840.00                                                 |
| Rubber Insulation                                                                                                                                                                                                        | 2½" x 3/4" x 6'       | 2 pc               | ₱ 350.00 /pc        | ₱ 700.00                                               |
| Estimated Charges                                                                                                                                                                                                        |                       |                    |                     | ₱ 24,340.00                                            |

| <b>Location/s:</b>                                                                                                                                                                                                       | Ground Floor Office  |                    | <b>Area:</b>        | * sqm.                                                 |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------|--------------------|---------------------|--------------------------------------------------------|
| <b>ACU #:</b>                                                                                                                                                                                                            | 11                   | <b>Unit Model:</b> | KSG-IWF-20WFY8K1M32 | <b>Unit Capacity/Type:</b> 2.0HP Wall Mounted Inverter |
| Estimated Pipe Length = 33 ft<br>Estimated Royal Cord Length = 38 ft<br><b>Initial Charge</b> ₱ 8,500.00<br>10ft Copper tube<br>10ft Royal Cord<br>Outdoor bracket Wall/Floor<br>Consumables<br>Testing and Commisioning |                      |                    |                     |                                                        |
| Installation Materials                                                                                                                                                                                                   | Specification        | Qty                | Price per qty       | Subtotal                                               |
| Insulated Copper tube                                                                                                                                                                                                    | 1/2"Ø x 1/4"Ø        | 23 ft              | ₱ 350.00 /ft        | ₱ 8,050.00                                             |
| Royal Cord (Comm wire)                                                                                                                                                                                                   | 2.0 sq.mm x 4c       | 28 ft              | 100.00 /ft          | 2,800.00                                               |
| Royal Cord (Power Supply)                                                                                                                                                                                                | (#12) 3.5 sqmm. x 3c | 5 ft               | 60.00 /ft           | 300.00                                                 |
| Circuir Breaker Weather Proof                                                                                                                                                                                            | 30Amps / 1Ph         | 1 pc               | 1,000.00 /pc        | 1,000.00                                               |
| Rubber Insulation                                                                                                                                                                                                        | 2½" x 3/4" x 6'      | 2 pc               | ₱ 350.00 /pc        | ₱ 700.00                                               |
| Estimated Charges                                                                                                                                                                                                        |                      |                    |                     | ₱ 21,350.00                                            |

| ACU #:                                                                                                                                                                                                                   | 12                    | Unit Model: | KSG-IWF-15Wfy8K1M32 | Unit Capacity/Type: | 1.5HP Wall Mounted Inverter |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------|-------------|---------------------|---------------------|-----------------------------|
| Estimated Pipe Length = 64 ft<br>Estimated Royal Cord Length = 69 ft<br><b>Initial Charge</b> ₱ 7,500.00<br>10ft Copper tube<br>10ft Royal Cord<br>Outdoor bracket Wall/Floor<br>Consumables<br>Testing and Commisioning |                       |             |                     |                     |                             |
| Installation Materials                                                                                                                                                                                                   | Specification         | Qty         | Price per qty       | Subtotal            |                             |
| Insulated Copper tube                                                                                                                                                                                                    | 3/8"Ø x 1/4"Ø         | 54 ft       | ₱ 350.00 /ft        | ₱ 18,900.00         |                             |
| Royal Cord (Comm wire)                                                                                                                                                                                                   | 2.0 sq.mm x 4c        | 59 ft       | 100.00 /ft          | 5,900.00            |                             |
| Royal Cord (Power Supply)                                                                                                                                                                                                | (#12) 3.5 sqmm. x 3c  | 5 ft        | 60.00 /ft           | 300.00              |                             |
| Circuir Breaker Weather Proof                                                                                                                                                                                            | 20Amps / 1Ph          | 1 pc        | 1,000.00 /pc        | 1,000.00            |                             |
| Pipe Hanger Assembly                                                                                                                                                                                                     | Clamp and Full thread | 6 pc        | 420.00 /pc          | 2,520.00            |                             |
| Rubber Insulation                                                                                                                                                                                                        | 2½" x 3/4" x 6'       | 5 pc        | ₱ 350.00 /pc        | ₱ 1,750.00          |                             |
| Estimated Charges                                                                                                                                                                                                        |                       |             |                     | ₱ 37,870.00         |                             |

|             |                 |       |           |
|-------------|-----------------|-------|-----------|
| Location/s: | Security and IT | Area: | 4.00 sqm. |
|-------------|-----------------|-------|-----------|

| ACU #:                                                                                                                                                                                                                   | 12a                  | Unit Model: | KSG-IWF-10Wfy8K1M32 | Unit Capacity/Type: | 1.0HP Wall Mounted Inverter |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------|-------------|---------------------|---------------------|-----------------------------|
| Estimated Pipe Length = 33 ft<br>Estimated Royal Cord Length = 38 ft<br><b>Initial Charge</b> ₱ 7,500.00<br>10ft Copper tube<br>10ft Royal Cord<br>Outdoor bracket Wall/Floor<br>Consumables<br>Testing and Commisioning |                      |             |                     |                     |                             |
| Installation Materials                                                                                                                                                                                                   | Specification        | Qty         | Price per qty       | Subtotal            |                             |
| Insulated Copper tube                                                                                                                                                                                                    | 3/8"Ø x 1/4"Ø        | 23 ft       | ₱ 350.00 /ft        | ₱ 8,050.00          |                             |
| Royal Cord (Comm wire)                                                                                                                                                                                                   | 2.0 sq.mm x 4c       | 28 ft       | 100.00 /ft          | 2,800.00            |                             |
| Royal Cord (Power Supply)                                                                                                                                                                                                | (#12) 3.5 sqmm. x 3c | 5 ft        | 60.00 /ft           | 300.00              |                             |
| Circuir Breaker Weather Proof                                                                                                                                                                                            | 20Amps / 1Ph         | 1 pc        | 1,000.00 /pc        | 1,000.00            |                             |
| Rubber Insulation                                                                                                                                                                                                        | 2½" x 3/4" x 6'      | 2 pc        | ₱ 350.00 /pc        | ₱ 700.00            |                             |
| Estimated Charges                                                                                                                                                                                                        |                      |             |                     | ₱ 20,350.00         |                             |

## SECOND FLOOR

|                    |                 |              |            |
|--------------------|-----------------|--------------|------------|
| <b>Location/s:</b> | Standard Room 4 | <b>Area:</b> | 26.00 sqm. |
|--------------------|-----------------|--------------|------------|

|               |    |                    |                     |                            |                             |
|---------------|----|--------------------|---------------------|----------------------------|-----------------------------|
| <b>ACU #:</b> | 13 | <b>Unit Model:</b> | KSG-IWF-20Wfy8K1M32 | <b>Unit Capacity/Type:</b> | 2.0HP Wall Mounted Inverter |
|---------------|----|--------------------|---------------------|----------------------------|-----------------------------|

Estimated Pipe Length = 30 ft

Estimated Royal Cord Length = 35 ft

**Initial Charge**

₱ 8,500.00

10ft Copper tube

10ft Royal Cord

Outdoor bracket Wall/Floor

Consumables

Testing and Commisioning

| Installation Materials        | Specification        | Qty   | Price per qty | Subtotal   |
|-------------------------------|----------------------|-------|---------------|------------|
| Insulated Copper tube         | 1/2"Ø x 1/4"Ø        | 20 ft | ₱ 350.00 /ft  | ₱ 7,000.00 |
| Royal Cord (Comm wire)        | 2.0 sq.mm x 4c       | 25 ft | 100.00 /ft    | 2,500.00   |
| Royal Cord (Power Supply)     | (#12) 3.5 sqmm. x 3c | 5 ft  | 60.00 /ft     | 300.00     |
| Circuir Breaker Weather Proof | 30Amps / 1Ph         | 1 pc  | 1,000.00 /pc  | 1,000.00   |
| Rubber Insulation             | 2½" x 3/4" x 6'      | 1 pc  | ₱ 350.00 /pc  | ₱ 350.00   |

Estimated Charges ₱ 19,650.00

|                    |                 |              |            |
|--------------------|-----------------|--------------|------------|
| <b>Location/s:</b> | Standard Room 3 | <b>Area:</b> | 26.00 sqm. |
|--------------------|-----------------|--------------|------------|

|               |    |                    |                     |                            |                             |
|---------------|----|--------------------|---------------------|----------------------------|-----------------------------|
| <b>ACU #:</b> | 14 | <b>Unit Model:</b> | KSG-IWF-20Wfy8K1M32 | <b>Unit Capacity/Type:</b> | 2.0HP Wall Mounted Inverter |
|---------------|----|--------------------|---------------------|----------------------------|-----------------------------|

Estimated Pipe Length = 37 ft

Estimated Royal Cord Length = 42 ft

**Initial Charge**

₱ 8,500.00

10ft Copper tube

10ft Royal Cord

Outdoor bracket Wall/Floor

Consumables

Testing and Commisioning

| Installation Materials        | Specification         | Qty   | Price per qty | Subtotal   |
|-------------------------------|-----------------------|-------|---------------|------------|
| Insulated Copper tube         | 1/2"Ø x 1/4"Ø         | 27 ft | ₱ 350.00 /ft  | ₱ 9,450.00 |
| Royal Cord (Comm wire)        | 2.0 sq.mm x 4c        | 32 ft | 100.00 /ft    | 3,200.00   |
| Royal Cord (Power Supply)     | (#12) 3.5 sqmm. x 3c  | 5 ft  | 60.00 /ft     | 300.00     |
| Circuir Breaker Weather Proof | 30Amps / 1Ph          | 1 pc  | 1,000.00 /pc  | 1,000.00   |
| Pipe Hanger Assembly          | Clamp and Full thread | 2 pc  | 420.00 /pc    | 840.00     |
| Rubber Insulation             | 2½" x 3/4" x 6'       | 2 pc  | ₱ 350.00 /pc  | ₱ 700.00   |

Estimated Charges ₱ 23,990.00

| <b>Location/s:</b>                                                                                                                                                                                                       | Standard Room 2      |                    | <b>Area:</b>        | 26.00 sqm.                                             |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------|--------------------|---------------------|--------------------------------------------------------|
| <b>ACU #:</b>                                                                                                                                                                                                            | 15                   | <b>Unit Model:</b> | KSG-IWF-20WFY8K1M32 | <b>Unit Capacity/Type:</b> 2.0HP Wall Mounted Inverter |
| Estimated Pipe Length = 31 ft<br>Estimated Royal Cord Length = 36 ft<br><b>Initial Charge</b> ₱ 8,500.00<br>10ft Copper tube<br>10ft Royal Cord<br>Outdoor bracket Wall/Floor<br>Consumables<br>Testing and Commisioning |                      |                    |                     |                                                        |
| Installation Materials                                                                                                                                                                                                   | Specification        | Qty                | Price per qty       | Subtotal                                               |
| Insulated Copper tube                                                                                                                                                                                                    | 1/2"Ø x 1/4"Ø        | 21 ft              | ₱ 350.00 /ft        | ₱ 7,350.00                                             |
| Royal Cord (Comm wire)                                                                                                                                                                                                   | 2.0 sq.mm x 4c       | 26 ft              | 100.00 /ft          | 2,600.00                                               |
| Royal Cord (Power Supply)                                                                                                                                                                                                | (#12) 3.5 sqmm. x 3c | 5 ft               | 60.00 /ft           | 300.00                                                 |
| Circuir Breaker Weather Proof                                                                                                                                                                                            | 30Amps / 1Ph         | 1 pc               | 1,000.00 /pc        | 1,000.00                                               |
| Rubber Insulation                                                                                                                                                                                                        | 2½" x 3/4" x 6'      | 1 pc               | ₱ 350.00 /pc        | ₱ 350.00                                               |
| Estimated Charges                                                                                                                                                                                                        |                      |                    |                     | ₱ 20,100.00                                            |

| <b>Location/s:</b>                                                                                                                                                                                                       | Standard Room 1       |                    | <b>Area:</b>        | 26.00 sqm.                                             |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------|--------------------|---------------------|--------------------------------------------------------|
| <b>ACU #:</b>                                                                                                                                                                                                            | 16                    | <b>Unit Model:</b> | KSG-IWF-20WFY8K1M32 | <b>Unit Capacity/Type:</b> 2.0HP Wall Mounted Inverter |
| Estimated Pipe Length = 37 ft<br>Estimated Royal Cord Length = 42 ft<br><b>Initial Charge</b> ₱ 8,500.00<br>10ft Copper tube<br>10ft Royal Cord<br>Outdoor bracket Wall/Floor<br>Consumables<br>Testing and Commisioning |                       |                    |                     |                                                        |
| Installation Materials                                                                                                                                                                                                   | Specification         | Qty                | Price per qty       | Subtotal                                               |
| Insulated Copper tube                                                                                                                                                                                                    | 1/2"Ø x 1/4"Ø         | 27 ft              | ₱ 350.00 /ft        | ₱ 9,450.00                                             |
| Royal Cord (Comm wire)                                                                                                                                                                                                   | 2.0 sq.mm x 4c        | 32 ft              | 100.00 /ft          | 3,200.00                                               |
| Royal Cord (Power Supply)                                                                                                                                                                                                | (#12) 3.5 sqmm. x 3c  | 5 ft               | 60.00 /ft           | 300.00                                                 |
| Circuir Breaker Weather Proof                                                                                                                                                                                            | 30Amps / 1Ph          | 1 pc               | 1,000.00 /pc        | 1,000.00                                               |
| Pipe Hanger Assembly                                                                                                                                                                                                     | Clamp and Full thread | 2 pc               | 420.00 /pc          | 840.00                                                 |
| Rubber Insulation                                                                                                                                                                                                        | 2½" x 3/4" x 6'       | 2 pc               | ₱ 350.00 /pc        | ₱ 700.00                                               |
| Estimated Charges                                                                                                                                                                                                        |                       |                    |                     | ₱ 23,990.00                                            |

| <b>Location/s:</b>                                                                                                                                                                                                       | Deluxe Room 4         |                    | <b>Area:</b>       | 31.00 sqm.                                             |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------|--------------------|--------------------|--------------------------------------------------------|
| <b>ACU #:</b>                                                                                                                                                                                                            | 17                    | <b>Unit Model:</b> | KSG-IWF-20WY8K1M32 | <b>Unit Capacity/Type:</b> 2.0HP Wall Mounted Inverter |
| Estimated Pipe Length = 38 ft<br>Estimated Royal Cord Length = 43 ft<br><b>Initial Charge</b> ₱ 8,500.00<br>10ft Copper tube<br>10ft Royal Cord<br>Outdoor bracket Wall/Floor<br>Consumables<br>Testing and Commisioning |                       |                    |                    |                                                        |
| Installation Materials                                                                                                                                                                                                   | Specification         | Qty                | Price per qty      | Subtotal                                               |
| Insulated Copper tube                                                                                                                                                                                                    | 1/2"Ø x 1/4"Ø         | 28 ft              | ₱ 350.00 /ft       | ₱ 9,800.00                                             |
| Royal Cord (Comm wire)                                                                                                                                                                                                   | 2.0 sq.mm x 4c        | 33 ft              | 100.00 /ft         | 3,300.00                                               |
| Royal Cord (Power Supply)                                                                                                                                                                                                | (#12) 3.5 sqmm. x 3c  | 5 ft               | 60.00 /ft          | 300.00                                                 |
| Circuir Breaker Weather Proof                                                                                                                                                                                            | 30Amps / 1Ph          | 1 pc               | 1,000.00 /pc       | 1,000.00                                               |
| Pipe Hanger Assembly                                                                                                                                                                                                     | Clamp and Full thread | 2 pc               | 420.00 /pc         | 840.00                                                 |
| Rubber Insulation                                                                                                                                                                                                        | 2½" x 3/4" x 6'       | 2 pc               | ₱ 350.00 /pc       | ₱ 700.00                                               |
| Estimated Charges                                                                                                                                                                                                        |                       |                    |                    | ₱ 24,440.00                                            |

| <b>Location/s:</b>                                                                                                                                                                                                       | Deluxe Room 3         |                    | <b>Area:</b>       | 31.00 sqm.                                             |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------|--------------------|--------------------|--------------------------------------------------------|
| <b>ACU #:</b>                                                                                                                                                                                                            | 18                    | <b>Unit Model:</b> | KSG-IWF-20WY8K1M32 | <b>Unit Capacity/Type:</b> 2.0HP Wall Mounted Inverter |
| Estimated Pipe Length = 32 ft<br>Estimated Royal Cord Length = 37 ft<br><b>Initial Charge</b> ₱ 8,500.00<br>10ft Copper tube<br>10ft Royal Cord<br>Outdoor bracket Wall/Floor<br>Consumables<br>Testing and Commisioning |                       |                    |                    |                                                        |
| Installation Materials                                                                                                                                                                                                   | Specification         | Qty                | Price per qty      | Subtotal                                               |
| Insulated Copper tube                                                                                                                                                                                                    | 1/2"Ø x 1/4"Ø         | 22 ft              | ₱ 350.00 /ft       | ₱ 7,700.00                                             |
| Royal Cord (Comm wire)                                                                                                                                                                                                   | 2.0 sq.mm x 4c        | 27 ft              | 100.00 /ft         | 2,700.00                                               |
| Royal Cord (Power Supply)                                                                                                                                                                                                | (#12) 3.5 sqmm. x 3c  | 5 ft               | 60.00 /ft          | 300.00                                                 |
| Circuir Breaker Weather Proof                                                                                                                                                                                            | 30Amps / 1Ph          | 1 pc               | 1,000.00 /pc       | 1,000.00                                               |
| Pipe Hanger Assembly                                                                                                                                                                                                     | Clamp and Full thread | 1 pc               | 420.00 /pc         | 420.00                                                 |
| Rubber Insulation                                                                                                                                                                                                        | 2½" x 3/4" x 6'       | 1 pc               | ₱ 350.00 /pc       | ₱ 350.00                                               |
| Estimated Charges                                                                                                                                                                                                        |                       |                    |                    | ₱ 20,970.00                                            |

| <b>Location/s:</b>                                                                                                                                                                                                       | Deluxe Room 2         |                    | <b>Area:</b>        | 31.00                      | sqm.                        |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------|--------------------|---------------------|----------------------------|-----------------------------|
| <b>ACU #:</b>                                                                                                                                                                                                            | 19                    | <b>Unit Model:</b> | KSG-IWF-20Wfy8K1M32 | <b>Unit Capacity/Type:</b> | 2.0HP Wall Mounted Inverter |
| Estimated Pipe Length = 38 ft<br>Estimated Royal Cord Length = 43 ft<br><b>Initial Charge</b> ₱ 8,500.00<br>10ft Copper tube<br>10ft Royal Cord<br>Outdoor bracket Wall/Floor<br>Consumables<br>Testing and Commisioning |                       |                    |                     |                            |                             |
| Installation Materials                                                                                                                                                                                                   | Specification         | Qty                | Price per qty       | Subtotal                   |                             |
| Insulated Copper tube                                                                                                                                                                                                    | 1/2"Ø x 1/4"Ø         | 28 ft              | ₱ 350.00 /ft        | ₱ 9,800.00                 |                             |
| Royal Cord (Comm wire)                                                                                                                                                                                                   | 2.0 sq.mm x 4c        | 33 ft              | 100.00 /ft          | 3,300.00                   |                             |
| Royal Cord (Power Supply)                                                                                                                                                                                                | (#12) 3.5 sqmm. x 3c  | 5 ft               | 60.00 /ft           | 300.00                     |                             |
| Circuir Breaker Weather Proof                                                                                                                                                                                            | 30Amps / 1Ph          | 1 pc               | 1,000.00 /pc        | 1,000.00                   |                             |
| Pipe Hanger Assembly                                                                                                                                                                                                     | Clamp and Full thread | 2 pc               | 420.00 /pc          | 840.00                     |                             |
| Rubber Insulation                                                                                                                                                                                                        | 2½" x 3/4" x 6'       | 2 pc               | ₱ 350.00 /pc        | ₱ 700.00                   |                             |
| <b>Estimated Charges</b>                                                                                                                                                                                                 |                       |                    |                     | ₱ 24,440.00                |                             |

| <b>Location/s:</b>                                                                                                                                                                                                       | Deluxe Room 1         |                    | <b>Area:</b>        | 31.00                      | sqm.                        |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------|--------------------|---------------------|----------------------------|-----------------------------|
| <b>ACU #:</b>                                                                                                                                                                                                            | 20                    | <b>Unit Model:</b> | KSG-IWF-20Wfy8K1M32 | <b>Unit Capacity/Type:</b> | 2.0HP Wall Mounted Inverter |
| Estimated Pipe Length = 32 ft<br>Estimated Royal Cord Length = 37 ft<br><b>Initial Charge</b> ₱ 8,500.00<br>10ft Copper tube<br>10ft Royal Cord<br>Outdoor bracket Wall/Floor<br>Consumables<br>Testing and Commisioning |                       |                    |                     |                            |                             |
| Installation Materials                                                                                                                                                                                                   | Specification         | Qty                | Price per qty       | Subtotal                   |                             |
| Insulated Copper tube                                                                                                                                                                                                    | 1/2"Ø x 1/4"Ø         | 22 ft              | ₱ 350.00 /ft        | ₱ 7,700.00                 |                             |
| Royal Cord (Comm wire)                                                                                                                                                                                                   | 2.0 sq.mm x 4c        | 27 ft              | 100.00 /ft          | 2,700.00                   |                             |
| Royal Cord (Power Supply)                                                                                                                                                                                                | (#12) 3.5 sqmm. x 3c  | 5 ft               | 60.00 /ft           | 300.00                     |                             |
| Circuir Breaker Weather Proof                                                                                                                                                                                            | 30Amps / 1Ph          | 1 pc               | 1,000.00 /pc        | 1,000.00                   |                             |
| Pipe Hanger Assembly                                                                                                                                                                                                     | Clamp and Full thread | 1 pc               | 420.00 /pc          | 420.00                     |                             |
| Rubber Insulation                                                                                                                                                                                                        | 2½" x 3/4" x 6'       | 1 pc               | ₱ 350.00 /pc        | ₱ 350.00                   |                             |
| <b>Estimated Charges</b>                                                                                                                                                                                                 |                       |                    |                     | ₱ 20,970.00                |                             |

| <b>Location/s:</b>                                                                                                                                                                                                       | <b>Co-Working Space</b> |                    | <b>Area:</b>        | 75.00 sqm.                                             |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|--------------------|---------------------|--------------------------------------------------------|
| <b>ACU #:</b>                                                                                                                                                                                                            | 21                      | <b>Unit Model:</b> | KSG-IWF-30WFY8K1M32 | <b>Unit Capacity/Type:</b> 3.0HP Wall Mounted Inverter |
| Estimated Pipe Length = 55 ft<br>Estimated Royal Cord Length = 60 ft<br><b>Initial Charge</b> ₱ 8,500.00<br>10ft Copper tube<br>10ft Royal Cord<br>Outdoor bracket Wall/Floor<br>Consumables<br>Testing and Commisioning |                         |                    |                     |                                                        |
| Installation Materials                                                                                                                                                                                                   | Specification           | Qty                | Price per qty       | Subtotal                                               |
| Insulated Copper tube                                                                                                                                                                                                    | 5/8"Ø x 1/4"Ø           | 45 ft              | ₱ 400.00 /ft        | ₱ 18,000.00                                            |
| Royal Cord (Comm wire)                                                                                                                                                                                                   | 2.0 sq.mm x 4c          | 50 ft              | 100.00 /ft          | 5,000.00                                               |
| Royal Cord (Power Supply)                                                                                                                                                                                                | (#12) 3.5 sqmm. x 3c    | 5 ft               | 60.00 /ft           | 300.00                                                 |
| Circuir Breaker Weather Proof                                                                                                                                                                                            | 30Amps / 1Ph            | 1 pc               | 1,000.00 /pc        | 1,000.00                                               |
| Pipe Hanger Assembly                                                                                                                                                                                                     | Clamp and Full thread   | 4 pc               | 420.00 /pc          | 1,680.00                                               |
| Rubber Insulation                                                                                                                                                                                                        | 2½" x 3/4" x 6'         | 4 pc               | ₱ 350.00 /pc        | ₱ 1,400.00                                             |
| <b>Estimated Charges</b>                                                                                                                                                                                                 |                         |                    |                     | <b>₱ 35,880.00</b>                                     |

| <b>ACU #:</b>                                                                                                                                                                                                            | 22                    | <b>Unit Model:</b> | KSG-IWF-30WFY8K1M32 | <b>Unit Capacity/Type:</b> 3.0HP Wall Mounted Inverter |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------|--------------------|---------------------|--------------------------------------------------------|
| Estimated Pipe Length = 72 ft<br>Estimated Royal Cord Length = 77 ft<br><b>Initial Charge</b> ₱ 8,500.00<br>10ft Copper tube<br>10ft Royal Cord<br>Outdoor bracket Wall/Floor<br>Consumables<br>Testing and Commisioning |                       |                    |                     |                                                        |
| Installation Materials                                                                                                                                                                                                   | Specification         | Qty                | Price per qty       | Subtotal                                               |
| Insulated Copper tube                                                                                                                                                                                                    | 5/8"Ø x 1/4"Ø         | 62 ft              | ₱ 400.00 /ft        | ₱ 24,800.00                                            |
| Royal Cord (Comm wire)                                                                                                                                                                                                   | 2.0 sq.mm x 4c        | 67 ft              | 100.00 /ft          | 6,700.00                                               |
| Royal Cord (Power Supply)                                                                                                                                                                                                | (#12) 3.5 sqmm. x 3c  | 5 ft               | 60.00 /ft           | 300.00                                                 |
| Circuir Breaker Weather Proof                                                                                                                                                                                            | 30Amps / 1Ph          | 1 pc               | 1,000.00 /pc        | 1,000.00                                               |
| Pipe Hanger Assembly                                                                                                                                                                                                     | Clamp and Full thread | 7 pc               | 420.00 /pc          | 2,940.00                                               |
| Rubber Insulation                                                                                                                                                                                                        | 2½" x 3/4" x 6'       | 6 pc               | ₱ 350.00 /pc        | ₱ 2,100.00                                             |
| <b>Estimated Charges</b>                                                                                                                                                                                                 |                       |                    |                     | <b>₱ 46,340.00</b>                                     |

|                    |                            |              |                   |
|--------------------|----------------------------|--------------|-------------------|
| <b>Location/s:</b> | <b>Pre - Function Room</b> | <b>Area:</b> | <b>24.00 sqm.</b> |
|--------------------|----------------------------|--------------|-------------------|

|               |           |                    |                            |                            |                                    |
|---------------|-----------|--------------------|----------------------------|----------------------------|------------------------------------|
| <b>ACU #:</b> | <b>23</b> | <b>Unit Model:</b> | <b>KSG-IWF-30Wfy8K1M32</b> | <b>Unit Capacity/Type:</b> | <b>3.0HP Wall Mounted Inverter</b> |
|---------------|-----------|--------------------|----------------------------|----------------------------|------------------------------------|

Estimated Pipe Length = 70 ft

Estimated Royal Cord Length = 75 ft

**Initial Charge** ₱ 8,500.00

10ft Copper tube  
10ft Royal Cord  
Outdoor bracket Wall/Floor  
Consumables  
Testing and Commisioning

| Installation Materials        | Specification         | Qty   | Price per qty | Subtotal    |
|-------------------------------|-----------------------|-------|---------------|-------------|
| Insulated Copper tube         | 5/8"Ø x 1/4"Ø         | 60 ft | ₱ 400.00 /ft  | ₱ 24,000.00 |
| Royal Cord (Comm wire)        | 2.0 sq.mm x 4c        | 65 ft | 100.00 /ft    | 6,500.00    |
| Royal Cord (Power Supply)     | (#12) 3.5 sqmm. x 3c  | 5 ft  | 60.00 /ft     | 300.00      |
| Circuir Breaker Weather Proof | 30Amps / 1Ph          | 1 pc  | 1,000.00 /pc  | 1,000.00    |
| Pipe Hanger Assembly          | Clamp and Full thread | 9 pc  | 420.00 /pc    | 3,780.00    |
| Rubber Insulation             | 2½" x 3/4" x 6'       | 8 pc  | ₱ 350.00 /pc  | ₱ 2,800.00  |

Estimated Charges ₱ 46,880.00

|                    |                      |              |                    |
|--------------------|----------------------|--------------|--------------------|
| <b>Location/s:</b> | <b>Function Room</b> | <b>Area:</b> | <b>220.00 sqm.</b> |
|--------------------|----------------------|--------------|--------------------|

|               |           |                    |                            |                            |                                    |
|---------------|-----------|--------------------|----------------------------|----------------------------|------------------------------------|
| <b>ACU #:</b> | <b>24</b> | <b>Unit Model:</b> | <b>KSG-IWF-30Wfy8K1M32</b> | <b>Unit Capacity/Type:</b> | <b>3.0HP Wall Mounted Inverter</b> |
|---------------|-----------|--------------------|----------------------------|----------------------------|------------------------------------|

Estimated Pipe Length = 39 ft

Estimated Royal Cord Length = 44 ft

**Initial Charge** ₱ 8,500.00

10ft Copper tube  
10ft Royal Cord  
Outdoor bracket Wall/Floor  
Consumables  
Testing and Commisioning

| Installation Materials        | Specification         | Qty   | Price per qty | Subtotal    |
|-------------------------------|-----------------------|-------|---------------|-------------|
| Insulated Copper tube         | 5/8"Ø x 1/4"Ø         | 29 ft | ₱ 400.00 /ft  | ₱ 11,600.00 |
| Royal Cord (Comm wire)        | 2.0 sq.mm x 4c        | 34 ft | 100.00 /ft    | 3,400.00    |
| Royal Cord (Power Supply)     | (#12) 3.5 sqmm. x 3c  | 5 ft  | 60.00 /ft     | 300.00      |
| Circuir Breaker Weather Proof | 30Amps / 1Ph          | 1 pc  | 1,000.00 /pc  | 1,000.00    |
| Pipe Hanger Assembly          | Clamp and Full thread | 3 pc  | 420.00 /pc    | 1,260.00    |
| Rubber Insulation             | 2½" x 3/4" x 6'       | 3 pc  | ₱ 350.00 /pc  | ₱ 1,050.00  |

Estimated Charges ₱ 27,110.00

| ACU #:                                                                                                                                                                                                                   | 25                    | Unit Model: | KSG-IWF-30WFY8K1M32 | Unit Capacity/Type: | 3.0HP Wall Mounted Inverter |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------|-------------|---------------------|---------------------|-----------------------------|
| Estimated Pipe Length = 65 ft<br>Estimated Royal Cord Length = 70 ft<br><b>Initial Charge</b> ₱ 8,500.00<br>10ft Copper tube<br>10ft Royal Cord<br>Outdoor bracket Wall/Floor<br>Consumables<br>Testing and Commisioning |                       |             |                     |                     |                             |
| Installation Materials                                                                                                                                                                                                   | Specification         | Qty         | Price per qty       | Subtotal            |                             |
| Insulated Copper tube                                                                                                                                                                                                    | 5/8"Ø x 1/4"Ø         | 55 ft       | ₱ 400.00 /ft        | ₱                   | 22,000.00                   |
| Royal Cord (Comm wire)                                                                                                                                                                                                   | 2.0 sq.mm x 4c        | 60 ft       | 100.00 /ft          |                     | 6,000.00                    |
| Royal Cord (Power Supply)                                                                                                                                                                                                | (#12) 3.5 sqmm. x 3c  | 5 ft        | 60.00 /ft           |                     | 300.00                      |
| Circuir Breaker Weather Proof                                                                                                                                                                                            | 30Amps / 1Ph          | 1 pc        | 1,000.00 /pc        |                     | 1,000.00                    |
| Pipe Hanger Assembly                                                                                                                                                                                                     | Clamp and Full thread | 8 pc        | 420.00 /pc          |                     | 3,360.00                    |
| Rubber Insulation                                                                                                                                                                                                        | 2½" x 3/4" x 6'       | 7 pc        | ₱ 350.00 /pc        | ₱                   | 2,450.00                    |
| Estimated Charges                                                                                                                                                                                                        |                       |             |                     | ₱                   | 43,610.00                   |

| ACU #:                                                                                                                                                                                                                   | 26                    | Unit Model: | KSG-IWF-30WFY8K1M32 | Unit Capacity/Type: | 3.0HP Wall Mounted Inverter |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------|-------------|---------------------|---------------------|-----------------------------|
| Estimated Pipe Length = 65 ft<br>Estimated Royal Cord Length = 70 ft<br><b>Initial Charge</b> ₱ 8,500.00<br>10ft Copper tube<br>10ft Royal Cord<br>Outdoor bracket Wall/Floor<br>Consumables<br>Testing and Commisioning |                       |             |                     |                     |                             |
| Installation Materials                                                                                                                                                                                                   | Specification         | Qty         | Price per qty       | Subtotal            |                             |
| Insulated Copper tube                                                                                                                                                                                                    | 5/8"Ø x 1/4"Ø         | 55 ft       | ₱ 400.00 /ft        | ₱                   | 22,000.00                   |
| Royal Cord (Comm wire)                                                                                                                                                                                                   | 2.0 sq.mm x 4c        | 60 ft       | 100.00 /ft          |                     | 6,000.00                    |
| Royal Cord (Power Supply)                                                                                                                                                                                                | (#12) 3.5 sqmm. x 3c  | 5 ft        | 60.00 /ft           |                     | 300.00                      |
| Circuir Breaker Weather Proof                                                                                                                                                                                            | 30Amps / 1Ph          | 1 pc        | 1,000.00 /pc        |                     | 1,000.00                    |
| Pipe Hanger Assembly                                                                                                                                                                                                     | Clamp and Full thread | 8 pc        | 420.00 /pc          |                     | 3,360.00                    |
| Rubber Insulation                                                                                                                                                                                                        | 2½" x 3/4" x 6'       | 7 pc        | ₱ 350.00 /pc        | ₱                   | 2,450.00                    |
| Estimated Charges                                                                                                                                                                                                        |                       |             |                     | ₱                   | 43,610.00                   |

| ACU #:                        | 27                    | Unit Model: | KSG-IWF-30WFY8K1M32 | Unit Capacity/Type: | 3.0HP Wall Mounted Inverter |
|-------------------------------|-----------------------|-------------|---------------------|---------------------|-----------------------------|
| Estimated Pipe Length         | =                     | 65          | ft                  |                     |                             |
| Estimated Royal Cord Length   | =                     | 70          | ft                  |                     |                             |
| <b>Initial Charge</b>         |                       |             |                     |                     | ₱ 8,500.00                  |
| 10ft Copper tube              |                       |             |                     |                     |                             |
| 10ft Royal Cord               |                       |             |                     |                     |                             |
| Outdoor bracket Wall/Floor    |                       |             |                     |                     |                             |
| Consumables                   |                       |             |                     |                     |                             |
| Testing and Commisioning      |                       |             |                     |                     |                             |
| Installation Materials        | Specification         | Qty         | Price per qty       | Subtotal            |                             |
| Insulated Copper tube         | 5/8"Ø x 1/4"Ø         | 55 ft       | ₱ 400.00 /ft        | ₱                   | 22,000.00                   |
| Royal Cord (Comm wire)        | 2.0 sq.mm x 4c        | 60 ft       | 100.00 /ft          |                     | 6,000.00                    |
| Royal Cord (Power Supply)     | (#12) 3.5 sqmm. x 3c  | 5 ft        | 60.00 /ft           |                     | 300.00                      |
| Circuir Breaker Weather Proof | 30Amps / 1Ph          | 1 pc        | 1,000.00 /pc        |                     | 1,000.00                    |
| Pipe Hanger Assembly          | Clamp and Full thread | 8 pc        | 420.00 /pc          |                     | 3,360.00                    |
| Rubber Insulation             | 2½" x 3/4" x 6'       | 7 pc        | ₱ 350.00 /pc        | ₱                   | 2,450.00                    |
| Estimated Charges             |                       |             |                     |                     | ₱ 43,610.00                 |

| ACU #:                        | 28                    | Unit Model: | KSG-IWF-30WFY8K1M32 | Unit Capacity/Type: | 3.0HP Wall Mounted Inverter |
|-------------------------------|-----------------------|-------------|---------------------|---------------------|-----------------------------|
| Estimated Pipe Length         | =                     | 57          | ft                  |                     |                             |
| Estimated Royal Cord Length   | =                     | 62          | ft                  |                     |                             |
| <b>Initial Charge</b>         |                       |             |                     |                     | ₱ 8,500.00                  |
| 10ft Copper tube              |                       |             |                     |                     |                             |
| 10ft Royal Cord               |                       |             |                     |                     |                             |
| Outdoor bracket Wall/Floor    |                       |             |                     |                     |                             |
| Consumables                   |                       |             |                     |                     |                             |
| Testing and Commisioning      |                       |             |                     |                     |                             |
| Installation Materials        | Specification         | Qty         | Price per qty       | Subtotal            |                             |
| Insulated Copper tube         | 5/8"Ø x 1/4"Ø         | 47 ft       | ₱ 400.00 /ft        | ₱                   | 18,800.00                   |
| Royal Cord (Comm wire)        | 2.0 sq.mm x 4c        | 52 ft       | 100.00 /ft          |                     | 5,200.00                    |
| Royal Cord (Power Supply)     | (#12) 3.5 sqmm. x 3c  | 5 ft        | 60.00 /ft           |                     | 300.00                      |
| Circuir Breaker Weather Proof | 30Amps / 1Ph          | 1 pc        | 1,000.00 /pc        |                     | 1,000.00                    |
| Pipe Hanger Assembly          | Clamp and Full thread | 6 pc        | 420.00 /pc          |                     | 2,520.00                    |
| Rubber Insulation             | 2½" x 3/4" x 6'       | 5 pc        | ₱ 350.00 /pc        | ₱                   | 1,750.00                    |
| Estimated Charges             |                       |             |                     |                     | ₱ 38,070.00                 |

## THIRD FLOOR

| <b>Location/s:</b>                                                                                                                                                                                                                                          | Premium Room A        |                    | <b>Area:</b>        | 48.00                      | sqm.                        |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------|--------------------|---------------------|----------------------------|-----------------------------|
| <b>ACU #:</b>                                                                                                                                                                                                                                               | 29                    | <b>Unit Model:</b> | KSG-IWF-30Wfy8K1M32 | <b>Unit Capacity/Type:</b> | 3.0HP Wall Mounted Inverter |
| Estimated Pipe Length = 60 ft<br>Estimated Royal Cord Length = 65 ft<br><b>Initial Charge</b> <span style="float: right;">₱ 8,500.00</span><br>10ft Copper tube<br>10ft Royal Cord<br>Outdoor bracket Wall/Floor<br>Consumables<br>Testing and Commisioning |                       |                    |                     |                            |                             |
| Installation Materials                                                                                                                                                                                                                                      | Specification         | Qty                | Price per qty       | Subtotal                   |                             |
| Insulated Copper tube                                                                                                                                                                                                                                       | 5/8"Ø x 1/4"Ø         | 50 ft              | ₱ 400.00 /ft        | ₱                          | 20,000.00                   |
| Royal Cord (Comm wire)                                                                                                                                                                                                                                      | 2.0 sq.mm x 4c        | 55 ft              | 100.00 /ft          |                            | 5,500.00                    |
| Royal Cord (Power Supply)                                                                                                                                                                                                                                   | (#12) 3.5 sqmm. x 3c  | 5 ft               | 60.00 /ft           |                            | 300.00                      |
| Circuir Breaker Weather Proof                                                                                                                                                                                                                               | 30Amps / 1Ph          | 1 pc               | 1,000.00 /pc        |                            | 1,000.00                    |
| Pipe Hanger Assembly                                                                                                                                                                                                                                        | Clamp and Full thread | 7 pc               | 420.00 /pc          |                            | 2,940.00                    |
| Rubber Insulation                                                                                                                                                                                                                                           | 2½" x 3/4" x 6'       | 6 pc               | ₱ 350.00 /pc        | ₱                          | 2,100.00                    |
| Estimated Charges                                                                                                                                                                                                                                           |                       |                    |                     | ₱                          | 40,340.00                   |

| <b>Location/s:</b>                                                                                                                                                                                                                                          | Premium Room B        |                    | <b>Area:</b>        | 58.00                      | sqm.                        |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------|--------------------|---------------------|----------------------------|-----------------------------|
| <b>ACU #:</b>                                                                                                                                                                                                                                               | 30                    | <b>Unit Model:</b> | KSG-IWF-30Wfy8K1M32 | <b>Unit Capacity/Type:</b> | 3.0HP Wall Mounted Inverter |
| Estimated Pipe Length = 70 ft<br>Estimated Royal Cord Length = 75 ft<br><b>Initial Charge</b> <span style="float: right;">₱ 8,500.00</span><br>10ft Copper tube<br>10ft Royal Cord<br>Outdoor bracket Wall/Floor<br>Consumables<br>Testing and Commisioning |                       |                    |                     |                            |                             |
| Installation Materials                                                                                                                                                                                                                                      | Specification         | Qty                | Price per qty       | Subtotal                   |                             |
| Insulated Copper tube                                                                                                                                                                                                                                       | 5/8"Ø x 1/4"Ø         | 60 ft              | ₱ 400.00 /ft        | ₱                          | 24,000.00                   |
| Royal Cord (Comm wire)                                                                                                                                                                                                                                      | 2.0 sq.mm x 4c        | 65 ft              | 100.00 /ft          |                            | 6,500.00                    |
| Royal Cord (Power Supply)                                                                                                                                                                                                                                   | (#12) 3.5 sqmm. x 3c  | 5 ft               | 60.00 /ft           |                            | 300.00                      |
| Circuir Breaker Weather Proof                                                                                                                                                                                                                               | 30Amps / 1Ph          | 1 pc               | 1,000.00 /pc        |                            | 1,000.00                    |
| Pipe Hanger Assembly                                                                                                                                                                                                                                        | Clamp and Full thread | 9 pc               | 420.00 /pc          |                            | 3,780.00                    |
| Rubber Insulation                                                                                                                                                                                                                                           | 2½" x 3/4" x 6'       | 7 pc               | ₱ 350.00 /pc        | ₱                          | 2,450.00                    |
| Estimated Charges                                                                                                                                                                                                                                           |                       |                    |                     | ₱                          | 46,530.00                   |

| <b>Location/s:</b>                                                                                                                                                                                                                                          | Deluxe Room 9         |                    | <b>Area:</b>        | sqm.                       |                             |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------|--------------------|---------------------|----------------------------|-----------------------------|
| <b>ACU #:</b>                                                                                                                                                                                                                                               | 31                    | <b>Unit Model:</b> | KSG-IWF-20Wfy8K1M32 | <b>Unit Capacity/Type:</b> | 2.0HP Wall Mounted Inverter |
| Estimated Pipe Length = 50 ft<br>Estimated Royal Cord Length = 55 ft<br><b>Initial Charge</b> <span style="float: right;">₱ 8,500.00</span><br>10ft Copper tube<br>10ft Royal Cord<br>Outdoor bracket Wall/Floor<br>Consumables<br>Testing and Commisioning |                       |                    |                     |                            |                             |
| Installation Materials                                                                                                                                                                                                                                      | Specification         | Qty                | Price per qty       | Subtotal                   |                             |
| Insulated Copper tube                                                                                                                                                                                                                                       | 1/2"Ø x 1/4"Ø         | 40 ft              | ₱ 350.00 /ft        | ₱ 14,000.00                |                             |
| Royal Cord (Comm wire)                                                                                                                                                                                                                                      | 2.0 sq.mm x 4c        | 45 ft              | 100.00 /ft          | 4,500.00                   |                             |
| Royal Cord (Power Supply)                                                                                                                                                                                                                                   | (#12) 3.5 sqmm. x 3c  | 5 ft               | 60.00 /ft           | 300.00                     |                             |
| Circuir Breaker Weather Proof                                                                                                                                                                                                                               | 30Amps / 1Ph          | 1 pc               | 1,000.00 /pc        | 1,000.00                   |                             |
| Pipe Hanger Assembly                                                                                                                                                                                                                                        | Clamp and Full thread | 5 pc               | 420.00 /pc          | 2,100.00                   |                             |
| Rubber Insulation                                                                                                                                                                                                                                           | 2½" x 3/4" x 6'       | 4 pc               | ₱ 350.00 /pc        | ₱ 1,400.00                 |                             |
| <b>Estimated Charges</b>                                                                                                                                                                                                                                    |                       |                    |                     | ₱ 31,800.00                |                             |

| <b>Location/s:</b>                                                                                                                                                                                                                                          | Deluxe Room 8         |                    | <b>Area:</b>        | 36.00 sqm.                 |                             |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------|--------------------|---------------------|----------------------------|-----------------------------|
| <b>ACU #:</b>                                                                                                                                                                                                                                               | 32                    | <b>Unit Model:</b> | KSG-IWF-20Wfy8K1M32 | <b>Unit Capacity/Type:</b> | 2.0HP Wall Mounted Inverter |
| Estimated Pipe Length = 37 ft<br>Estimated Royal Cord Length = 42 ft<br><b>Initial Charge</b> <span style="float: right;">₱ 8,500.00</span><br>10ft Copper tube<br>10ft Royal Cord<br>Outdoor bracket Wall/Floor<br>Consumables<br>Testing and Commisioning |                       |                    |                     |                            |                             |
| Installation Materials                                                                                                                                                                                                                                      | Specification         | Qty                | Price per qty       | Subtotal                   |                             |
| Insulated Copper tube                                                                                                                                                                                                                                       | 1/2"Ø x 1/4"Ø         | 27 ft              | ₱ 350.00 /ft        | ₱ 9,450.00                 |                             |
| Royal Cord (Comm wire)                                                                                                                                                                                                                                      | 2.0 sq.mm x 4c        | 32 ft              | 100.00 /ft          | 3,200.00                   |                             |
| Royal Cord (Power Supply)                                                                                                                                                                                                                                   | (#12) 3.5 sqmm. x 3c  | 5 ft               | 60.00 /ft           | 300.00                     |                             |
| Circuir Breaker Weather Proof                                                                                                                                                                                                                               | 30Amps / 1Ph          | 1 pc               | 1,000.00 /pc        | 1,000.00                   |                             |
| Pipe Hanger Assembly                                                                                                                                                                                                                                        | Clamp and Full thread | 2 pc               | 420.00 /pc          | 840.00                     |                             |
| Rubber Insulation                                                                                                                                                                                                                                           | 2½" x 3/4" x 6'       | 2 pc               | ₱ 350.00 /pc        | ₱ 700.00                   |                             |
| <b>Estimated Charges</b>                                                                                                                                                                                                                                    |                       |                    |                     | ₱ 23,990.00                |                             |

| <b>Location/s:</b>                                                                                                                                                                                                       | Deluxe Room 7         |                    | <b>Area:</b>        | 36.00 sqm.                                             |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------|--------------------|---------------------|--------------------------------------------------------|
| <b>ACU #:</b>                                                                                                                                                                                                            | 33                    | <b>Unit Model:</b> | KSG-IWF-20Wfy8K1M32 | <b>Unit Capacity/Type:</b> 2.0HP Wall Mounted Inverter |
| Estimated Pipe Length = 34 ft<br>Estimated Royal Cord Length = 39 ft<br><b>Initial Charge</b> ₱ 8,500.00<br>10ft Copper tube<br>10ft Royal Cord<br>Outdoor bracket Wall/Floor<br>Consumables<br>Testing and Commisioning |                       |                    |                     |                                                        |
| Installation Materials                                                                                                                                                                                                   | Specification         | Qty                | Price per qty       | Subtotal                                               |
| Insulated Copper tube                                                                                                                                                                                                    | 1/2"Ø x 1/4"Ø         | 24 ft              | ₱ 350.00 /ft        | ₱ 8,400.00                                             |
| Royal Cord (Comm wire)                                                                                                                                                                                                   | 2.0 sq.mm x 4c        | 29 ft              | 100.00 /ft          | 2,900.00                                               |
| Royal Cord (Power Supply)                                                                                                                                                                                                | (#12) 3.5 sqmm. x 3c  | 5 ft               | 60.00 /ft           | 300.00                                                 |
| Circuir Breaker Weather Proof                                                                                                                                                                                            | 30Amps / 1Ph          | 1 pc               | 1,000.00 /pc        | 1,000.00                                               |
| Pipe Hanger Assembly                                                                                                                                                                                                     | Clamp and Full thread | 1 pc               | 420.00 /pc          | 420.00                                                 |
| Rubber Insulation                                                                                                                                                                                                        | 2½" x 3/4" x 6'       | 1 pc               | ₱ 350.00 /pc        | ₱ 350.00                                               |
| Estimated Charges                                                                                                                                                                                                        |                       |                    |                     | ₱ 21,870.00                                            |

| <b>Location/s:</b>                                                                                                                                                                                                       | Deluxe Room 6         |                    | <b>Area:</b>        | 36.00 sqm.                                             |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------|--------------------|---------------------|--------------------------------------------------------|
| <b>ACU #:</b>                                                                                                                                                                                                            | 34                    | <b>Unit Model:</b> | KSG-IWF-20Wfy8K1M32 | <b>Unit Capacity/Type:</b> 2.0HP Wall Mounted Inverter |
| Estimated Pipe Length = 37 ft<br>Estimated Royal Cord Length = 42 ft<br><b>Initial Charge</b> ₱ 8,500.00<br>10ft Copper tube<br>10ft Royal Cord<br>Outdoor bracket Wall/Floor<br>Consumables<br>Testing and Commisioning |                       |                    |                     |                                                        |
| Installation Materials                                                                                                                                                                                                   | Specification         | Qty                | Price per qty       | Subtotal                                               |
| Insulated Copper tube                                                                                                                                                                                                    | 1/2"Ø x 1/4"Ø         | 27 ft              | ₱ 350.00 /ft        | ₱ 9,450.00                                             |
| Royal Cord (Comm wire)                                                                                                                                                                                                   | 2.0 sq.mm x 4c        | 32 ft              | 100.00 /ft          | 3,200.00                                               |
| Royal Cord (Power Supply)                                                                                                                                                                                                | (#12) 3.5 sqmm. x 3c  | 5 ft               | 60.00 /ft           | 300.00                                                 |
| Circuir Breaker Weather Proof                                                                                                                                                                                            | 30Amps / 1Ph          | 1 pc               | 1,000.00 /pc        | 1,000.00                                               |
| Pipe Hanger Assembly                                                                                                                                                                                                     | Clamp and Full thread | 2 pc               | 420.00 /pc          | 840.00                                                 |
| Rubber Insulation                                                                                                                                                                                                        | 2½" x 3/4" x 6'       | 2 pc               | ₱ 350.00 /pc        | ₱ 700.00                                               |
| Estimated Charges                                                                                                                                                                                                        |                       |                    |                     | ₱ 23,990.00                                            |

|                    |               |              |            |
|--------------------|---------------|--------------|------------|
| <b>Location/s:</b> | Deluxe Room 5 | <b>Area:</b> | 36.00 sqm. |
|--------------------|---------------|--------------|------------|

|               |    |                    |                    |                            |                             |
|---------------|----|--------------------|--------------------|----------------------------|-----------------------------|
| <b>ACU #:</b> | 35 | <b>Unit Model:</b> | KSG-IWF-20WY8K1M32 | <b>Unit Capacity/Type:</b> | 2.0HP Wall Mounted Inverter |
|---------------|----|--------------------|--------------------|----------------------------|-----------------------------|

Estimated Pipe Length = 34 ft

Estimated Royal Cord Length = 39 ft

**Initial Charge** ₱ 8,500.00

10ft Copper tube

10ft Royal Cord

Outdoor bracket Wall/Floor

Consumables

Testing and Commisioning

| Installation Materials        | Specification         | Qty   | Price per qty | Subtotal   |
|-------------------------------|-----------------------|-------|---------------|------------|
| Insulated Copper tube         | 1/2"Ø x 1/4"Ø         | 24 ft | ₱ 350.00 /ft  | ₱ 8,400.00 |
| Royal Cord (Comm wire)        | 2.0 sq.mm x 4c        | 29 ft | 100.00 /ft    | 2,900.00   |
| Royal Cord (Power Supply)     | (#12) 3.5 sqmm. x 3c  | 5 ft  | 60.00 /ft     | 300.00     |
| Circuir Breaker Weather Proof | 30Amps / 1Ph          | 1 pc  | 1,000.00 /pc  | 1,000.00   |
| Pipe Hanger Assembly          | Clamp and Full thread | 1 pc  | 420.00 /pc    | 420.00     |
| Rubber Insulation             | 2½" x 3/4" x 6'       | 1 pc  | ₱ 350.00 /pc  | ₱ 350.00   |

Estimated Charges ₱ 21,870.00

|                    |                 |              |            |
|--------------------|-----------------|--------------|------------|
| <b>Location/s:</b> | Standard Room 5 | <b>Area:</b> | 25.00 sqm. |
|--------------------|-----------------|--------------|------------|

|               |    |                    |                    |                            |                             |
|---------------|----|--------------------|--------------------|----------------------------|-----------------------------|
| <b>ACU #:</b> | 36 | <b>Unit Model:</b> | KSG-IWF-20WY8K1M32 | <b>Unit Capacity/Type:</b> | 2.0HP Wall Mounted Inverter |
|---------------|----|--------------------|--------------------|----------------------------|-----------------------------|

Estimated Pipe Length = 33 ft

Estimated Royal Cord Length = 38 ft

**Initial Charge** ₱ 8,500.00

10ft Copper tube

10ft Royal Cord

Outdoor bracket Wall/Floor

Consumables

Testing and Commisioning

| Installation Materials        | Specification        | Qty   | Price per qty | Subtotal   |
|-------------------------------|----------------------|-------|---------------|------------|
| Insulated Copper tube         | 1/2"Ø x 1/4"Ø        | 23 ft | ₱ 350.00 /ft  | ₱ 8,050.00 |
| Royal Cord (Comm wire)        | 2.0 sq.mm x 4c       | 28 ft | 100.00 /ft    | 2,800.00   |
| Royal Cord (Power Supply)     | (#12) 3.5 sqmm. x 3c | 5 ft  | 60.00 /ft     | 300.00     |
| Circuir Breaker Weather Proof | 30Amps / 1Ph         | 1 pc  | 1,000.00 /pc  | 1,000.00   |
| Rubber Insulation             | 2½" x 3/4" x 6'      | 1 pc  | ₱ 350.00 /pc  | ₱ 350.00   |

Estimated Charges ₱ 21,000.00

| <b>Location/s:</b>                                                                                                                                                                                                       | Standard Room 6 |                       | <b>Area:</b>        | 25.00                      | sqm.                        |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------|-----------------------|---------------------|----------------------------|-----------------------------|
| <b>ACU #:</b>                                                                                                                                                                                                            | 37              | <b>Unit Model:</b>    | KSG-IWF-20WFY8K1M32 | <b>Unit Capacity/Type:</b> | 2.0HP Wall Mounted Inverter |
| Estimated Pipe Length = 39 ft<br>Estimated Royal Cord Length = 44 ft<br><b>Initial Charge</b> ₱ 8,500.00<br>10ft Copper tube<br>10ft Royal Cord<br>Outdoor bracket Wall/Floor<br>Consumables<br>Testing and Commisioning |                 |                       |                     |                            |                             |
| Installation Materials                                                                                                                                                                                                   |                 | Specification         | Qty                 | Price per qty              | Subtotal                    |
| Insulated Copper tube                                                                                                                                                                                                    |                 | 1/2"Ø x 1/4"Ø         | 29 ft               | ₱ 350.00 /ft               | ₱ 10,150.00                 |
| Royal Cord (Comm wire)                                                                                                                                                                                                   |                 | 2.0 sq.mm x 4c        | 34 ft               | 100.00 /ft                 | 3,400.00                    |
| Royal Cord (Power Supply)                                                                                                                                                                                                |                 | (#12) 3.5 sqmm. x 3c  | 5 ft                | 60.00 /ft                  | 300.00                      |
| Circuir Breaker Weather Proof                                                                                                                                                                                            |                 | 30Amps / 1Ph          | 1 pc                | 1,000.00 /pc               | 1,000.00                    |
| Pipe Hanger Assembly                                                                                                                                                                                                     |                 | Clamp and Full thread | 2 pc                | 420.00 /pc                 | 840.00                      |
| Rubber Insulation                                                                                                                                                                                                        |                 | 2½" x 3/4" x 6'       | 2 pc                | ₱ 350.00 /pc               | ₱ 700.00                    |
| Estimated Charges                                                                                                                                                                                                        |                 |                       |                     |                            | ₱ 24,890.00                 |

| <b>Location/s:</b>                                                                                                                                                                                                       | Standard Room 7 |                      | <b>Area:</b>        | 25.00                      | sqm.                        |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------|----------------------|---------------------|----------------------------|-----------------------------|
| <b>ACU #:</b>                                                                                                                                                                                                            | 38              | <b>Unit Model:</b>   | KSG-IWF-20WFY8K1M32 | <b>Unit Capacity/Type:</b> | 2.0HP Wall Mounted Inverter |
| Estimated Pipe Length = 34 ft<br>Estimated Royal Cord Length = 39 ft<br><b>Initial Charge</b> ₱ 8,500.00<br>10ft Copper tube<br>10ft Royal Cord<br>Outdoor bracket Wall/Floor<br>Consumables<br>Testing and Commisioning |                 |                      |                     |                            |                             |
| Installation Materials                                                                                                                                                                                                   |                 | Specification        | Qty                 | Price per qty              | Subtotal                    |
| Insulated Copper tube                                                                                                                                                                                                    |                 | 1/2"Ø x 1/4"Ø        | 24 ft               | ₱ 350.00 /ft               | ₱ 8,400.00                  |
| Royal Cord (Comm wire)                                                                                                                                                                                                   |                 | 2.0 sq.mm x 4c       | 29 ft               | 100.00 /ft                 | 2,900.00                    |
| Royal Cord (Power Supply)                                                                                                                                                                                                |                 | (#12) 3.5 sqmm. x 3c | 5 ft                | 60.00 /ft                  | 300.00                      |
| Circuir Breaker Weather Proof                                                                                                                                                                                            |                 | 30Amps / 1Ph         | 1 pc                | 1,000.00 /pc               | 1,000.00                    |
| Rubber Insulation                                                                                                                                                                                                        |                 | 2½" x 3/4" x 6'      | 1 pc                | ₱ 350.00 /pc               | ₱ 350.00                    |
| Estimated Charges                                                                                                                                                                                                        |                 |                      |                     |                            | ₱ 21,450.00                 |

| <b>Location/s:</b>                                                                                                                                                                                                       |    | Standard Room 8       |                     | <b>Area:</b>               | 25.00 sqm.                  |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|-----------------------|---------------------|----------------------------|-----------------------------|
| <b>ACU #:</b>                                                                                                                                                                                                            | 39 | <b>Unit Model:</b>    | KSG-IWF-20Wfy8K1M32 | <b>Unit Capacity/Type:</b> | 2.0HP Wall Mounted Inverter |
| Estimated Pipe Length = 39 ft<br>Estimated Royal Cord Length = 44 ft<br><b>Initial Charge</b> ₱ 8,500.00<br>10ft Copper tube<br>10ft Royal Cord<br>Outdoor bracket Wall/Floor<br>Consumables<br>Testing and Commisioning |    |                       |                     |                            |                             |
| Installation Materials                                                                                                                                                                                                   |    | Specification         | Qty                 | Price per qty              | Subtotal                    |
| Insulated Copper tube                                                                                                                                                                                                    |    | 1/2"Ø x 1/4"Ø         | 29 ft               | ₱ 350.00 /ft               | ₱ 10,150.00                 |
| Royal Cord (Comm wire)                                                                                                                                                                                                   |    | 2.0 sq.mm x 4c        | 34 ft               | 100.00 /ft                 | 3,400.00                    |
| Royal Cord (Power Supply)                                                                                                                                                                                                |    | (#12) 3.5 sqmm. x 3c  | 5 ft                | 60.00 /ft                  | 300.00                      |
| Circuir Breaker Weather Proof                                                                                                                                                                                            |    | 30Amps / 1Ph          | 1 pc                | 1,000.00 /pc               | 1,000.00                    |
| Pipe Hanger Assembly                                                                                                                                                                                                     |    | Clamp and Full thread | 2 pc                | 420.00 /pc                 | 840.00                      |
| Rubber Insulation                                                                                                                                                                                                        |    | 2½" x 3/4" x 6'       | 2 pc                | ₱ 350.00 /pc               | ₱ 700.00                    |
| Estimated Charges                                                                                                                                                                                                        |    |                       |                     |                            | ₱ 24,890.00                 |

| <b>Location/s:</b>                                                                                                                                                                                                       |    | Standard Room 9      |                     | <b>Area:</b>               | 25.00 sqm.                  |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|----------------------|---------------------|----------------------------|-----------------------------|
| <b>ACU #:</b>                                                                                                                                                                                                            | 40 | <b>Unit Model:</b>   | KSG-IWF-20Wfy8K1M32 | <b>Unit Capacity/Type:</b> | 2.0HP Wall Mounted Inverter |
| Estimated Pipe Length = 34 ft<br>Estimated Royal Cord Length = 39 ft<br><b>Initial Charge</b> ₱ 8,500.00<br>10ft Copper tube<br>10ft Royal Cord<br>Outdoor bracket Wall/Floor<br>Consumables<br>Testing and Commisioning |    |                      |                     |                            |                             |
| Installation Materials                                                                                                                                                                                                   |    | Specification        | Qty                 | Price per qty              | Subtotal                    |
| Insulated Copper tube                                                                                                                                                                                                    |    | 1/2"Ø x 1/4"Ø        | 24 ft               | ₱ 350.00 /ft               | ₱ 8,400.00                  |
| Royal Cord (Comm wire)                                                                                                                                                                                                   |    | 2.0 sq.mm x 4c       | 29 ft               | 100.00 /ft                 | 2,900.00                    |
| Royal Cord (Power Supply)                                                                                                                                                                                                |    | (#12) 3.5 sqmm. x 3c | 5 ft                | 60.00 /ft                  | 300.00                      |
| Circuir Breaker Weather Proof                                                                                                                                                                                            |    | 30Amps / 1Ph         | 1 pc                | 1,000.00 /pc               | 1,000.00                    |
| Rubber Insulation                                                                                                                                                                                                        |    | 2½" x 3/4" x 6'      | 1 pc                | ₱ 350.00 /pc               | ₱ 350.00                    |
| Estimated Charges                                                                                                                                                                                                        |    |                      |                     |                            | ₱ 21,450.00                 |

|                    |                         |              |                   |
|--------------------|-------------------------|--------------|-------------------|
| <b>Location/s:</b> | <b>Standard Room 10</b> | <b>Area:</b> | <b>25.00 sqm.</b> |
|--------------------|-------------------------|--------------|-------------------|

|               |           |                    |                            |                            |                                    |
|---------------|-----------|--------------------|----------------------------|----------------------------|------------------------------------|
| <b>ACU #:</b> | <b>41</b> | <b>Unit Model:</b> | <b>KSG-IWF-20WFY8K1M32</b> | <b>Unit Capacity/Type:</b> | <b>2.0HP Wall Mounted Inverter</b> |
|---------------|-----------|--------------------|----------------------------|----------------------------|------------------------------------|

Estimated Pipe Length = 39 ft

Estimated Royal Cord Length = 44 ft

**Initial Charge** ₱ 8,500.00

10ft Copper tube  
10ft Royal Cord  
Outdoor bracket Wall/Floor  
Consumables  
Testing and Commisioning

| Installation Materials        | Specification         | Qty   | Price per qty | Subtotal    |
|-------------------------------|-----------------------|-------|---------------|-------------|
| Insulated Copper tube         | 1/2"Ø x 1/4"Ø         | 29 ft | ₱ 350.00 /ft  | ₱ 10,150.00 |
| Royal Cord (Comm wire)        | 2.0 sq.mm x 4c        | 34 ft | 100.00 /ft    | 3,400.00    |
| Royal Cord (Power Supply)     | (#12) 3.5 sqmm. x 3c  | 5 ft  | 60.00 /ft     | 300.00      |
| Circuir Breaker Weather Proof | 30Amps / 1Ph          | 1 pc  | 1,000.00 /pc  | 1,000.00    |
| Pipe Hanger Assembly          | Clamp and Full thread | 2 pc  | 420.00 /pc    | 840.00      |
| Rubber Insulation             | 2½" x 3/4" x 6'       | 2 pc  | ₱ 350.00 /pc  | ₱ 700.00    |
| Estimated Charges             |                       |       |               | ₱ 24,890.00 |

|                    |                         |              |                   |
|--------------------|-------------------------|--------------|-------------------|
| <b>Location/s:</b> | <b>Standard Room 11</b> | <b>Area:</b> | <b>25.00 sqm.</b> |
|--------------------|-------------------------|--------------|-------------------|

|               |           |                    |                            |                            |                                    |
|---------------|-----------|--------------------|----------------------------|----------------------------|------------------------------------|
| <b>ACU #:</b> | <b>42</b> | <b>Unit Model:</b> | <b>KSG-IWF-20WFY8K1M32</b> | <b>Unit Capacity/Type:</b> | <b>2.0HP Wall Mounted Inverter</b> |
|---------------|-----------|--------------------|----------------------------|----------------------------|------------------------------------|

Estimated Pipe Length = 39 ft

Estimated Royal Cord Length = 44 ft

**Initial Charge** ₱ 8,500.00

10ft Copper tube  
10ft Royal Cord  
Outdoor bracket Wall/Floor  
Consumables  
Testing and Commisioning

| Installation Materials        | Specification         | Qty   | Price per qty | Subtotal    |
|-------------------------------|-----------------------|-------|---------------|-------------|
| Insulated Copper tube         | 1/2"Ø x 1/4"Ø         | 29 ft | ₱ 350.00 /ft  | ₱ 10,150.00 |
| Royal Cord (Comm wire)        | 2.0 sq.mm x 4c        | 34 ft | 100.00 /ft    | 3,400.00    |
| Royal Cord (Power Supply)     | (#12) 3.5 sqmm. x 3c  | 5 ft  | 60.00 /ft     | 300.00      |
| Circuir Breaker Weather Proof | 30Amps / 1Ph          | 1 pc  | 1,000.00 /pc  | 1,000.00    |
| Pipe Hanger Assembly          | Clamp and Full thread | 2 pc  | 420.00 /pc    | 840.00      |
| Rubber Insulation             | 2½" x 3/4" x 6'       | 2 pc  | ₱ 350.00 /pc  | ₱ 700.00    |
| Estimated Charges             |                       |       |               | ₱ 24,890.00 |

|                    |                  |              |            |
|--------------------|------------------|--------------|------------|
| <b>Location/s:</b> | Standard Room 12 | <b>Area:</b> | 29.00 sqm. |
|--------------------|------------------|--------------|------------|

|               |    |                    |                     |                            |                             |
|---------------|----|--------------------|---------------------|----------------------------|-----------------------------|
| <b>ACU #:</b> | 43 | <b>Unit Model:</b> | KSG-IWF-20WFY8K1M32 | <b>Unit Capacity/Type:</b> | 2.0HP Wall Mounted Inverter |
|---------------|----|--------------------|---------------------|----------------------------|-----------------------------|

Estimated Pipe Length = 34 ft

Estimated Royal Cord Length = 39 ft

**Initial Charge** ₱ 8,500.00

10ft Copper tube  
10ft Royal Cord  
Outdoor bracket Wall/Floor  
Consumables  
Testing and Commisioning

| Installation Materials        | Specification        | Qty   | Price per qty | Subtotal   |
|-------------------------------|----------------------|-------|---------------|------------|
| Insulated Copper tube         | 1/2"Ø x 1/4"Ø        | 24 ft | ₱ 350.00 /ft  | ₱ 8,400.00 |
| Royal Cord (Comm wire)        | 2.0 sq.mm x 4c       | 29 ft | 100.00 /ft    | 2,900.00   |
| Royal Cord (Power Supply)     | (#12) 3.5 sqmm. x 3c | 5 ft  | 60.00 /ft     | 300.00     |
| Circuir Breaker Weather Proof | 30Amps / 1Ph         | 1 pc  | 1,000.00 /pc  | 1,000.00   |
| Rubber Insulation             | 2½" x 3/4" x 6'      | 1 pc  | ₱ 350.00 /pc  | ₱ 350.00   |

Estimated Charges ₱ 21,450.00

|                    |                  |              |            |
|--------------------|------------------|--------------|------------|
| <b>Location/s:</b> | Standard Room 13 | <b>Area:</b> | 25.00 sqm. |
|--------------------|------------------|--------------|------------|

|               |    |                    |                     |                            |                             |
|---------------|----|--------------------|---------------------|----------------------------|-----------------------------|
| <b>ACU #:</b> | 44 | <b>Unit Model:</b> | KSG-IWF-20WFY8K1M32 | <b>Unit Capacity/Type:</b> | 2.0HP Wall Mounted Inverter |
|---------------|----|--------------------|---------------------|----------------------------|-----------------------------|

Estimated Pipe Length = 39 ft

Estimated Royal Cord Length = 44 ft

**Initial Charge** ₱ 8,500.00

10ft Copper tube  
10ft Royal Cord  
Outdoor bracket Wall/Floor  
Consumables  
Testing and Commisioning

| Installation Materials        | Specification         | Qty   | Price per qty | Subtotal    |
|-------------------------------|-----------------------|-------|---------------|-------------|
| Insulated Copper tube         | 1/2"Ø x 1/4"Ø         | 29 ft | ₱ 350.00 /ft  | ₱ 10,150.00 |
| Royal Cord (Comm wire)        | 2.0 sq.mm x 4c        | 34 ft | 100.00 /ft    | 3,400.00    |
| Royal Cord (Power Supply)     | (#12) 3.5 sqmm. x 3c  | 5 ft  | 60.00 /ft     | 300.00      |
| Circuir Breaker Weather Proof | 30Amps / 1Ph          | 1 pc  | 1,000.00 /pc  | 1,000.00    |
| Pipe Hanger Assembly          | Clamp and Full thread | 2 pc  | 420.00 /pc    | 840.00      |
| Rubber Insulation             | 2½" x 3/4" x 6'       | 2 pc  | ₱ 350.00 /pc  | ₱ 700.00    |

Estimated Charges ₱ 24,890.00

|             |                  |       |       |      |
|-------------|------------------|-------|-------|------|
| Location/s: | Standard Room 14 | Area: | 25.00 | sqm. |
|-------------|------------------|-------|-------|------|

|        |    |             |                     |                     |                             |
|--------|----|-------------|---------------------|---------------------|-----------------------------|
| ACU #: | 45 | Unit Model: | KSG-IWF-20Wfy8K1M32 | Unit Capacity/Type: | 2.0HP Wall Mounted Inverter |
|--------|----|-------------|---------------------|---------------------|-----------------------------|

Estimated Pipe Length = 37 ft

Estimated Royal Cord Length = 42 ft

**Initial Charge**

₱ 8,500.00

10ft Copper tube

10ft Royal Cord

Outdoor bracket Wall/Floor

Consumables

Testing and Commisioning

| Installation Materials        | Specification         | Qty   | Price per qty | Subtotal   |
|-------------------------------|-----------------------|-------|---------------|------------|
| Insulated Copper tube         | 1/2"Ø x 1/4"Ø         | 27 ft | ₱ 350.00 /ft  | ₱ 9,450.00 |
| Royal Cord (Comm wire)        | 2.0 sq.mm x 4c        | 32 ft | 100.00 /ft    | 3,200.00   |
| Royal Cord (Power Supply)     | (#12) 3.5 sqmm. x 3c  | 5 ft  | 60.00 /ft     | 300.00     |
| Circuir Breaker Weather Proof | 30Amps / 1Ph          | 1 pc  | 1,000.00 /pc  | 1,000.00   |
| Pipe Hanger Assembly          | Clamp and Full thread | 2 pc  | 420.00 /pc    | 840.00     |
| Rubber Insulation             | 2½" x 3/4" x 6'       | 2 pc  | ₱ 350.00 /pc  | ₱ 700.00   |

Estimated Charges ₱ 23,990.00

|             |                  |       |       |      |
|-------------|------------------|-------|-------|------|
| Location/s: | Standard Room 15 | Area: | 23.00 | sqm. |
|-------------|------------------|-------|-------|------|

|        |    |             |                     |                     |                             |
|--------|----|-------------|---------------------|---------------------|-----------------------------|
| ACU #: | 46 | Unit Model: | KSG-IWF-20Wfy8K1M32 | Unit Capacity/Type: | 2.0HP Wall Mounted Inverter |
|--------|----|-------------|---------------------|---------------------|-----------------------------|

Estimated Pipe Length = 50 ft

Estimated Royal Cord Length = 55 ft

**Initial Charge**

₱ 8,500.00

10ft Copper tube

10ft Royal Cord

Outdoor bracket Wall/Floor

Consumables

Testing and Commisioning

| Installation Materials        | Specification         | Qty   | Price per qty | Subtotal    |
|-------------------------------|-----------------------|-------|---------------|-------------|
| Insulated Copper tube         | 1/2"Ø x 1/4"Ø         | 40 ft | ₱ 350.00 /ft  | ₱ 14,000.00 |
| Royal Cord (Comm wire)        | 2.0 sq.mm x 4c        | 45 ft | 100.00 /ft    | 4,500.00    |
| Royal Cord (Power Supply)     | (#12) 3.5 sqmm. x 3c  | 5 ft  | 60.00 /ft     | 300.00      |
| Circuir Breaker Weather Proof | 30Amps / 1Ph          | 1 pc  | 1,000.00 /pc  | 1,000.00    |
| Pipe Hanger Assembly          | Clamp and Full thread | 5 pc  | 420.00 /pc    | 2,100.00    |
| Rubber Insulation             | 2½" x 3/4" x 6'       | 4 pc  | ₱ 350.00 /pc  | ₱ 1,400.00  |


Estimated Charges ₱ 31,800.00

**Validity:** This quotation is valid for a period of fifteen (15) days from the date thereof, subject to our confirmation thereafter.

**Installation notes:**

- 1 Indoor Location based in floor plan only.
- 2 Proposed copper tube lay out (green color) location for outdoor units (red color) based on floor plan are subject for **approval.**
- 3 AC drain line will be provided by the customer's contractor.
- 4 Assumed ceiling height on all rooms are 2.7 meters.
- 5 Mechanical Plans, Permits, Electrical permits not included.
- 6 Issuance of waiver for air conditioning units states that are undersized in relation to the floor plan's specified allowable model type per area, this also may result to reduced the compresor warranty
- 6 Deflectors, masonry, carpentry, chipping & plastering (finishing & restoration) are not included in the installation.
- 7 Air conditioning drain line and Electrical power supply (feeder line) 220v/ 60hz/ 1ph, should be provided by customer's contractor.
- 8 **Final charges will be based on actual installation.**

Prepared by:



Engr. Kenneth Zamora  
Service Supervisor  
Field and Shop Supervisor





